The Paper, which was received on 11 March, 1957, is accompanied by twenty-six sheets of diagrams and twenty-three photographs, from some of which the half-tone page plates, folding Plates 1 and 2, and the Figures in the text have been prepared.

CORRESPONDENCE on this Paper should be forwarded to reach the Institution before 15 August, 1957. Contributions should not exceed 1,200 words.—SEC.

Discussion

The Authors introduced the Paper with the aid of a film.

Mr F. N. G. Taylor (Director, Charles Brand and Son Limited), said that he had been impressed by the amount of information condensed into a few thousand words.

167. The Authors referred in § 50 to a decanting lock at the top of the shafts in connexion with the cable tunnels. That was the first time Mr Taylor's firm had tried that method, which had proved very satisfactory, except that the time limit of 5 min for the men to leave the working chamber and be recompressed in the decanting lock had at first not been strictly adhered to by the men; but they had soon altered their ideas when a few of them got slight "bends", and after that they had adhered strictly to the 5-min rule. The same procedure had applied in the cooling-water tunnels when the decanting lock was placed in the cast-iron-lined cross-passage, referred to in § 73.

168. In § 83 the Authors referred to a substantial leakage in "A" station tunnels. That had not shown itself whilst constructing the concrete lining and brickwork, but it was unfortunate that the 4½-in. ring brickwork had five courses of headers, one at each side of the springer, one at each of the shoulders, and one in the roof. That had made it very difficult to consolidate the concrete without disturbing the brickwork, and since concrete and brickwork had had to be constructed together, no collar joint could be used.

169. The concrete in "B" station tunnels had been pumped from the central batching plant, down the shafts, along the tunnels to the pneumatic placer. That method of pumped concrete required careful quantity calculations, otherwise a good deal of waste was inevitable if the pipe was still full when each section of the lining was completed. However, since the moving shutter did not provide for the invert, any concrete remaining in the pipe had been used for that purpose, and since the invert was a known quantity, it had not been difficult to calculate the amount of concrete required. Consequently, once the scheme had got under way, there had been very little wastage.

170. Referring to §§ 94–104, Mr Taylor said that there had been difficulties in driving those tunnels, and although his firm had been assisted financially with the 1,600 tons of temporary support material used, the progress of the work had been very considerably delayed by its erection.

171. With regard to the foreshore works (§ 129) it was interesting to compare the original "A" station method* with the present one. One interesting point in connexion with the "A" station was that there had been a fixed price for breaking up and dredging the shelf, but at that time his firm had considered the quoted rate of £5/cu. yd as rather excessive, so it had been suggested to the consulting engineers that they should

* See footnote 1, p. 789.

PORTISHEAD "B" POWER STATION WITH PARTICULAR REFERENCE TO
THE CIRCULATING-WATER WORKS

PLATE I
PORTISHEAD "B" POWER STATION

FIG.4. - TUNNELS. GEOLOGICAL SECTIONS

PORTISHEAD "B" POWER STATION WITH PARTICULAR REFERENCE TO THE CIRCULATING-WATER WORKS

FIG. 6.—CROSS-SECTION THROUGH POWER STATION

themselves hire the plant and carry out the work on a cost-plus basis with a fifty-fifty saving to be shared between the employers and themselves. That had turned out profitable to both sides.

172. It was also a remarkable fact that although the method carried out on the foreshore had been entirely different from the "A" station works, the comparison in cost per cubic yard of the two methods was directly in relation to the rise in cost of wages and material. The quantities were almost identical, roughly 10,000 cu. yd. The "A" station cost was just over £3 per cu. yd and the "B" station was three and a half times that amount, owing to the rise of wages and materials. The other difference in construction had been the building and placing of the outlet ends—for the "A" station those had been fabricated in a graving dock in Bristol and brought down by tugs and barges with the outlet ends carried by cat heads over the bows of two barges, the barges being lashed together. Those outlets had then been lowered into position at full high water by steam winches situated in the hold of each barge. At low water they had then been placed accurately and inspected by the diver.

173. The portal units had been cast in a vertical position on a tilting table referred to (§ 143) and not horizontal as required for handling purposes. That was because the section was rather thin and heavily reinforced, and a better job could be made by consolidating the concrete round the internal shutter in one operation. The latter was of steel and had already been in use for the lining of the 10-ft-dia. cast-iron tunnel, as shown in Fig. 17c. Further, the granite people had promised to provide an accurate surface on the granite stones so that if those granite stones could be placed on a rigid base without showing any deflexion, and if there was some method of tilting those units into the horizontal position, a better job would be made and fine-axeing of the granite would be unnecessary. The first effort had not been wholly successful and the granite had had to be fine-axed, but from that experience the other three had been successfully carried out. The placing of the units had proved to be relatively simple, though always full of risk, and great credit was due to Mr H. N. Croft, who had been the sub-agent in charge of the foreshore works, and to his men, for successfully carrying out that work.

174. He wished to close on a rather personal note. He was now in his fiftieth year of employment with his firm, and he could truthfully say that no contract had given him greater pleasure and interest than the work at Portishead.

Mr A. G. Thirtle (Divisional Controller, Central Electricity Authority) said that the subject was of particular importance in the light of the programme for nuclear power station development; two of such stations had now been scheduled for construction on the southern bank of the Severn estuary. Those nuclear stations would require vast quantities of circulating water and their situation would also most likely demand deep tunnelling work. He felt that the information recorded in the present Paper would be of considerable value.

176. The siting of the two stations at Portishead had been very largely determined by the facilities which the Portishead dock afforded for the receipt of sea-borne coal from South Wales; the substantial additional cost of the deep tunnel working had been partly offset by the availability of those dock facilities. Apart from the tunnel work, the general construction work on the "B" station had been very much handicapped by the limited nature of the site, which was a very narrow strip of land between the dock and the "A" station.

177. The narrow site had made it necessary to adopt a longitudinal layout of the six turbo-alternators with two boilers per set instead of the modern practice of one boiler per set unit arrangement. However, economy had been exercised in the design of the buildings and the volume had worked out at 38.3 cu. ft./kW, compared with an average of 47.4 cu. ft./kW for stations of the same design year. Those figures were quoted from the Report of the Committee of Enquiry into economy in the construction of power stations in 1953.

178. Referring to the method of construction of the tunnels, could the Authors state if experience on the job had fully justified the decision to carry out the operation of tunnel construction solely from the screen shafts instead of sinking temporary working shafts as had been done for the tunnels on the "A" station in 1927? That earlier method had given the advantage of six working faces and three outlets for spoil for each tunnel, but, of course, it had involved expenditure on four additional shafts.

179. The information given in §§ 153-156 referring to the use of fly ash on some of the mass concrete on the job would, he thought, do much to remove the prejudice against the use of fly ash for concrete in mass in building construction. Fig. 24 showed the superior strength with 30% cement replacement. In addition to that advantage, Mr Thirlie stated that the use of that material was of considerable national importance, since the quantity of ash from powdered fuel to be disposed of from power stations of Great Britain was now approaching 4,000,000 tons. Where building contracts were being executed in the vicinity of such power stations some economies could be effected by using that material.

180. The first half of the station was now in full commercial operation, i.e., the first three of the six 60-MW sets were turning out units to the Central Electricity grid system. The station performance had been up to full expectation. Over the recent winter period the thermal efficiency of the station had been the highest of all the C.E.A. stations operating on similar steam thermal conditions.

Mr A. F. Haxton (Director, Charles Brand and Son Limited) remarked that § 160 implied that the Authors had never been in doubt that the river works could be completed in three seasons. His firm had not dared to be so confident, since, to quote only one example, so much depended on the reliable operation of the derrick travelling up and down the foreshore, and it had been all too easy to foresee some disaster which could put the machine out of action for many months. The risk had had to be faced, however, and, in the event, by the exercise of special care and precaution at all times, only eleven tides had been lost by reason of breakdown.

182. During the design stage it had soon become obvious that it would be essential to consider any eventuality, however unlikely, and he was glad to say that all members of the team had trained themselves to think along those lines. That had undoubtedly contributed materially to the success of a hazardous, some might say foolhardy, operation. Mr Taylor had been a constant inspiration. Great credit was also due to Messrs Joseph Westwood, who had co-operated in the design and fabrication of much of the special plant.

183. Before leaving the subject of the foreshore, he wished to amplify what Mr Taylor had said about the comparison of cost between the two stations. First, the proportion of cost as between dredging and culvert ends was within 1% of what it had been in 1928. Secondly, the total cost of the new works at 1951 rates for wages and materials was just over three and a half times that of 1928. The dredging cost, including plant and charges, was 231s/cu. yd. That comparison exposed the fallacy of attempting to relate costs to hourly wage rates. In 1928 the basic hourly rate had been 1s 3d; in 1951 it had been 2s 8d, an increase of slightly more than double. In 1928 the working week (at plain-time rates) had been 54 hours, and there had been few plus-rates for skill and conditions. The labourer's weekly wage had been about £3 10s or, with bonus for that class of work, about £4 per week. The addition in 1951 of overtime payments for hours over 44 per week (as against 54 in 1928), of plus-rates for skill and conditions, of greatly increased incentive bonus payments, of holidays with pay (which incidentally now in effect increased the hourly rate by about 2½d), of travelling and subsistence allowances, etc.—the addition of all those factors increased the theoretical basic weekly wage from about £6 (44 hours at 2s 8d) to produce an average weekly wage of £12 to £16, or three or four times what had been paid in 1928.

184. Mr Haxton then referred to Table 3 and said it would be instructive to know for the structural steelwork contract the total man-hours expended on shop fabrication. That

information would make the cost per man-hour figures more comparable. The close agreement between the civil engineering and the building costs was striking. Was that common?

185. The Authors' description of the sinking of the 45-ft-dia. pump pits (§§ 64-71) was very comprehensive, and that had been a very interesting task. He had recently been told that the contractors for the pipe work had now designed a satisfactory making-up piece which would avoid the necessity for the extreme accuracy of setting the cast-iron shaft eyes. Would that modification have represented an economy?

186. The final concrete lining of the 21-ft-dia. screen shafts (§§ 72-80) by means of continuous concreting behind a sliding shutter had proved very successful, except that the irregular shape of the shaft, as shown in Fig. 15, had tended to deflect the shutter. The shafts had, however, been completed within the relatively small tolerances demanded. The depth of the sliding shutters used was 4 ft and not 3 ft, as stated in the Paper.

187. The circulating-water tunnels had been driven with the use of feed-leg mountings for the drills, the spoil being loaded into 20-cu. ft wagons by Eimco mechanical loaders, size 21.

188. Mr Taylor had referred to the compressed-air work in the cable tunnels and the circulating-water tunnels, and the decompression of the men by the decanting method. The total number of recompressions of shift workers because of "bends"—the shift workers being the only ones who had been decanted, the men who were on for only a short time had come out normally in the lock—in the cable tunnels, with a working pressure of 27 to 30 lb/sq. in., had been 151 in a total decompression of 3,014, which represented a percentage of 5. In the circulating-water tunnels, the average working pressure had rarely exceeded 18 lb/sq. in., there had been no trouble with the decanting and there had been no recompressions. On a more recent contract at Shoreham Harbour, where the same decanting method had been used and the working pressure had reached 33 lb/sq. in., with an average pressure of 26 to 27%, the total number of recompressions for shift workers had been 69 in 2,079, representing 2.3%.

Mr F. W. Aries (Senior Assistant Engineer (Civil) South Western Division, Central Electricity Authority) said that in § 56, there was a reference to the weed blankets which sometimes blocked the "A" station coarse screens. It had been noted in the past that those blankets usually occurred between 4 hours and 0 hours before high water, always on spring tides and sometimes associated with storms. It had been suggested once that they might be associated with the high-tide debris on the high-tide line. Had the Authors any information on that? Sometimes the load on the "A" power station arising from such a stoppage had had to be dropped to half, and on one occasion the load had actually had to be dropped to 10%.

190. Those weed blankets were usually removed by reversing the flow in the culverts, and that was the main reason for continuing that system in the "B" station. In the early days at the "A" station it had been found that the situation was improved by removing alternate bars in the coarse screens at the tunnel mouths, and the coarse screens there were now roughly the same centres as those adopted at the "B" station.

191. It was interesting to note that so far there had been no similar experience on the "B" station, and that might be due to the horizontal inlets and to the fact that the inlet tunnels were led off a dredged channel instead of a shelf. The dredged channel had, however, caused some recirculation—rather more than at the "A" station. The seriousness of it had not been assessed as yet, but in 1 month, with three sets running, it had amounted to about 16 degree-hours per tide, and the actual temperature rise had at one time been as much as 17 degrees.

192. The "A" station tunnels were canted slightly upwards, and, owing to the rather more favourable slope of the rock, the dredging had been formed to a level shelf about 3 ft below the culvert inlets. At the "B" Station the slope of the rock was not so favourable (the contours being more widely spaced), and it had been necessary to form a channel.

193. The sloping type of inlet had one or two advantages. Mr Aries thought that the placing of the culvert ends in a sloping channel might have made it easier to meet the prefabricated end with the tunnel. There was also the point that doors opening with the tilted tunnel were slightly more clear of the dredged shelf or channel, and if there were any obstructions there which might make the opening or closing of the doors difficult, they would be less likely to cause trouble with the doors tilted. There was also the point that the outfall culverts tilted upwards might assist in stratification of the water stream; hot water above and cold water below. Finally, when the doors were held in the open position, there was the tendency on the sloping type for the doors to rest against the stops and not flap so much in the tide. So there appeared to be quite a lot of advantages on that side. Could the Authors give their reasons for choosing the horizontal type?

194. The accuracy of the culvert portal granite blocks was very high indeed, and everyone concerned was to be congratulated. One measurement of tunnel seepage had been taken and it had amounted to 10 gal/min only. That was in the whole tunnel measured at the screen shaft.

195. With regard to the foundations, Mr Aries could not see in the Paper any note of the rock bearing pressure design. On other sites it had been possible at times to use a colloidal concrete or else a grouted aggregate form of foundation, and that type of foundation had been used elsewhere quite recently in his experience, and tests had been taken. Those tests had been very crude, he admitted: simply filling 6-in. cube boxes with aggregate and grouting them up. Those tests had given 1,300 lb/sq. in. at 7 days and 2,800 lb/sq. in. at 28 days. Perhaps the Authors would comment on any reason why that method of founding had been considered unwise at Portishead.

Mr J. A. Maughan (Civil Engineer, Atomic Power Constructions Ltd) said that early in 1956 Mr Sancha had kindly shown him round the power-station site. The items which he had noticed particularly were (a) the supports for the shedding of the temporary end of the turbine house which were of an ingenious tubular construction; (b) the uncommon method of construction used for the river end of the cooling-water tunnels; (c) the sudden changes in direction of the ground strata, which were clearly visible on the hillside; (d) the high standard of workmanship; the finish of the concrete and brickwork being particularly good.

197. Mr Maughan then said it was true that the siting of power stations had always been difficult, but the normal practice had been to place the station at the centre of gravity of the electrical load. Since the advent of nuclear power, the siting of power stations had become even more difficult.

198. With regard to Fig. 1, he noticed that the Severn Barrage scheme was not shown, and although it was estimated that that scheme would save 1 million tons of coal a year, it had evidently been shelved. Mr Morgan was well acquainted with that scheme, so perhaps he might comment upon it.

199. The "A" power station, like Portishead "B" (the construction of which had been spread over about 9 years and which had a rigid layout), was not economical because it was not possible to take advantage of recent technical developments. Trouble had been caused on the "A" station by blankets of seaweed collecting on the coarse screens at the intake ends of the cooling-water tunnels, and it seemed likely that similar trouble would be experienced at the "B" station, particularly in view of the shape of the dredged shelf and the velocity through the coarse screens at the ends of the tunnels. Usually the velocity of the water through the roughing screens was kept below 1 ft/sec, whereas the normal velocity at Portishead "B" was over 6.3 ft/sec, which could rise to over 12.6 ft/sec if the whole of the flow passed through the tunnel. Probably a rough screen chamber would be more satisfactory. However, if the reverse flow could clear the screens quickly enough to prevent the shedding of electrical load, a more elaborate system would not be justified. Blanketing troubles would be much more serious should the River Board request that smolt-screens be fitted at the river end of the tunnels.

200. The normal rise in temperature of the cooling water when passing through a condenser was 12 to 15°F and in those cases where the outfall discharged into a restricted area the River Boards often stated that the general rise in the temperature of the water in the restricted area must not exceed 3 or 4°F because a high temperature encouraged the teredo worm to breed and timber piles in the area were eaten away.

201. In the reverse-flow system each tunnel was used as an inlet tunnel at one period and as an outlet tunnel at another period. In some cases, in order to kill marine growth such as mussels, the temperature of the outlet was raised occasionally to 100 or 120°F for 1½ hours every 4 weeks.

202. In the case of Portishead "B" the ends of the intake and outlet tunnels were very close together, and it seemed that some recirculation was unavoidable. It would be interesting to know what the various water temperatures were, particularly at low water.

203. At some power stations chlorine was used to kill the marine growth and that system was very efficient when the mussels were young. In the case of one cooling-water tunnel about 300 tons of mussels had had to be removed at the end of 1 year before chlorine was used, but only 3 tons had had to be removed at the end of 1 year after chlorine was added to the cooling water.

204. The cost of the civil engineering and building works, given as £18·22/kW installed, was rather high for a conventional power station and no doubt that arose from the site conditions. The cost, however, was considerably less than that for a nuclear power station of the same electrical output. If larger and more efficient turbines had been installed at Portishead "B" the capital and operating costs would have been lower still.

205. Portishead "B" power station was one of the many power stations built by the Electricity Authority as part of the great expansion of the electricity-supply industry which had taken place since 1947 when the industry had been nationalized. The station, with a net thermal efficiency of about 30·3%, would help to raise the average net thermal efficiency of the power stations in England and Wales. In 1956 the average net thermal efficiency of those power stations had increased from 24·14% to 24·70%, and thus saved about 1,000,000 tons of coal in the year. In the future when several of the larger turbo-alternators (with the higher net thermal efficiencies—120 MW, 34·7%; 550 MW, 45%) were commissioned, millions of tons of coal would be saved each year.

206. The report on the use of fly ash as a replacement of some of the Portland cement in the concrete mix was very interesting, and the increase in the compressive strength of the concrete at 28 days was rather surprising. Some details of the cost would be very useful.

Mr H. E. Whyte (Agent at Portishead "B" power station, Charles Brand and Son Limited) said that he would amplify some of the descriptions of the foreshore works. The bridge which carried the drilling tower had been fixed for level at the inshore end by the level of the girders resting on the trestles. It had been essential that the bridge be horizontal in order that the drilling tower be vertical. The seaward end of the bridge had therefore been adjusted for level after each move by winching it up or down in the galleons on the tripod. To prevent movement of the bridge, the landward end had been clamped to the girders and the seaward end had been secured to a continuous anchor cable, tensioned to up to 3 tons. Even with that tension it had been calculated that the seaward end might move 3 in. or more because of wind and tide.

208. The placing and firing of the charges was of interest. The charge of 2-in.-dia. P.A. gelignite was placed in a waxed cardboard tube of 2½ in. internal diameter. The bottom end was sealed with a pointed wooden plug nailed to the tube, the point, of course, pointing away from the tube. The detonation of the charge was by Cordtex which was itself detonated by an electric detonator. The length of the Cordtex was sufficient to allow of its detonation taking place just below the surface of the water. The top end of the charge was sealed by a plain wooden plug again nailed to the cardboard tube, experience having shown that the current was sufficient on occasions to pull the charge out of the

tube. To prevent the completely sealed charge from being pulled out of the drilled hole, two small spring-steel strips were nailed to the sloping sides of the pointed plug, the loose ends projecting outwards outside the cardboard tube and therefore pressing against the sides of the drilled hole.

209. That method had been 100% effective in ensuring that the charges did not move. The charges had been fired two at a time, using one detonator, and, to prevent sympathetic detonation of the Cordtex, the two lines to be fired had been pulled as far as possible towards one end of the bridge. Despite those precautions, sympathetic detonation had occurred on a very few occasions, fortunately without serious effect.

210. When work had started on the excavation of the second half of the dredged shelf, it had been necessary to blast within 25 ft of the front of No. 3 unit. A few trial blasts had shown that every explosion caused the greenheart doors to be sucked open slightly and then banged shut. There had obviously been a danger of at least damaging the hinges, and to prevent the movement of the doors a screen of air bubbles had been arranged in front of the doors during blasting, and had proved completely effective. The screen had been provided by $\frac{1}{8}$ -in.-dia. holes at 3-in. centres in a 4-in.-dia tube, 14-ft long, air being supplied at about 80 lb/sq. in. in effective pressure.

211. A special rig had been constructed to drill the cut-off holes on the inshore slope of the dredged shelf. The slope had been at 1 in 2.2 to the vertical and the rig had been constructed so that it could be mounted on the girders supporting the inshore end of the drilling bridge. The drill guide tubes of that rig had been set at the 1 in 2.2 slope and, since the girders were set parallel to the dredged shelf, one could be certain that the cut-off holes were on the correct line. Those holes had been 3-in. dia. and at $7\frac{1}{2}$ -in. centres, and there had been no known case of two of those holes merging.

212. The tilting table had been supported on four concrete pillars and the purpose of the machined face had been to avoid having to dress the face of the granite blocks to a plane after the unit had been cast. That had not been successful in the case of the first unit cast, and had been attributed to slight settlement of one or more of the four concrete pillars. A three-point support might have proved more successful, but would have entailed major alterations to the table, so, for the three subsequent units, the concrete columns had been tested to 50% overload and checked for settlement. If any settlement had occurred, the base of the column had been enlarged until the settlement was reduced to acceptable proportions.

213. The 5-ton derrick had been brought into use for concreting around the precast units after they had been placed in position in order to release the 10-ton derrick for excavation on the dredged shelf. It had obviously not been an economic proposition to install further tracks up and down the beach and another large winch, so some form of drive motor had had to be found which would stand up to submersion every tide. A 40-B.H.P. air motor had seemed to be the only possible answer, but the initial inquiry to the manufacturers had produced little more than astonishment on their part. They had, however, eventually been persuaded that their motor would withstand the submersion and, in fact, it had performed admirably and required surprisingly little maintenance, despite 22 weeks working under such conditions.

214. The tremie tube used for depositing concrete at the sides of the units after placing was constructed with a hopper and platform at its top end. The platform was large enough to carry two men and when in use with the 10-ton derrick, which was of the double drum type, the concrete skip was lifted up by one rope, while the other held on to the tremie tube. The men on the platform then released the bottom-opening skip and so filled the tremie tube. The skip was then deposited and the tremie tube, with the men on the platform, was then swung round and lowered into position, being finally placed by diver. When in position, the diver said so over his telephone, and the catch holding the flap at the bottom end of the tremie tube was withdrawn by one of the men using a hand winch at platform level. The tremie tube was then raised slowly in order that the concrete should be deposited without disturbance.

Mr M. F. Palmer (Chief Engineer and Director, Joseph Westwood and Company, Limited) said that he would refer to the trial erection in the yard. The erection had been made in order to confirm that the tripod would act in the way it was intended to do. When the whole structure had been lifted by the 10-ton crane from the top of the gallows, it had not been known how the tripod would settle on the irregular foreshore. Subsequently it had been found that the foreshore was not as irregular as had been imagined. At the bottom of the gallows there was a knuckle which had a foot slung from it and it could rest anywhere within an area of 2 ft dia. or more on a steel plate. There had been uncertainty, when the gallows were lifted by the crane and the tripod slung from chains on the underside of the gallows, how it would actually land.

216. When the design was being developed a tide of 4 knots had been given, and when the design was almost concluded the information had suddenly been supplied that 7 knots had been registered at the site, which meant that there had to be a reinvestigation, but the main difference which had been necessitated was the introduction of land anchors. The main problem had been to keep the load at the top of the gallows down to a maximum of 10 tons to suit the crane. There had been a weighing dial in the yard which was used to check that. He thought it had come to a little bit more than 10 tons, but that could not be avoided. The whole construction (girders, tripod, and gallows) had been welded for lightness. The girder for the bridge had been 75 ft long, 11 ft wide, and 9 ft deep, and it had been sent from Millwall to the site in one piece.

217. Another point in design was that when the crane at the site lifted the gallows and moved the seaward end of the bridge along about 4 ft, vertical hinges and a horizontal pivot were brought into action at the landward end. The landward end was then moved along the fixed trestles by means of winches to align the bridge in its new position ready for drilling a further line of holes.

218. Mr Palmer then referred to the drilling frame placed on the girder at the works, and the drilling tube. Originally an ordinary single tube was visualized, but it had not been long before the contractors said that they wanted a slot right down the drilling tube to enable the Cordtex to pull clear as the frame was moved along the top of the bridge. That had been got over by building a triangular frame of three tubes and putting a slot in the drilling tube.

Dr T. P. O'Sullivan (Consulting Engineer, T. P. O'Sullivan and Partners) said that it was extremely useful to know that where fly ash had been mixed with the cement substantially the same strength concrete had been obtained, with a consequent great saving in cost. He thought that that was probably a fact which was not generally known, and it was a very good thing that attention had been drawn to it.

220. Another interesting fact, on the design side, was that the structural high-carbon steel had been welded. It was generally understood that high-carbon steel could not be welded. In § 34 it was stated that the steel had been specified to have a slightly reduced carbon content, and as a result of that the consulting engineers had been able to introduce welding into the high-tensile steel.

221. On the question of chimneys, owing to the necessity for matching up with Portishead "A" station, brickwork had had to be introduced and that had undoubtedly increased the cost. Would brick facing have been more economical?

222. With regard to Fig. 8, the Authors stated in § 31 that the foundations for the turbine house had been taken down to such a depth that no lateral pressure was exerted on the condenser-pit walls. It occurred to him that with the thickness of the wall shown at the foot of the Figure and the fact that it was reinforced, it might conceivably have been raised to a small extent. Limited lateral pressure could possibly have been allowed without the pressure being a serious design factor in that wall.

223. In § 5 it was mentioned that eight of the boilers were for oil or coal and four for oil only. Could the Authors give some idea of the relative costs of the boilers that were available for both fuels?

224. Referring to § 9 Dr O'Sullivan recognized that the Paper had had to be compressed, but information was always required on test records, and it was interesting to know, both with in-situ and with precast piles, what sort of results had been achieved; to know how the loading test results stood in relation to driving formulae. Perhaps the Authors could give some further information on that matter.

**** Mr John Whitehead** referred to Mr Morgan's theory that a "wet blanket" arose from an eddy forming a miniature Sargasso Sea. That theory might be tested by aerial photography, possibly with the aid of radar. Similar methods were used to trace shoals of fish. It might then prove possible to divert the eddy by building a breakwater, or by dredging, or by the judicious dumping of spoil.

The Authors, in reply, first welcomed Mr Taylor's contribution, since it gave very interesting additional information. Mr Taylor's unique and varied experience had been of great assistance in the successful conclusion of the tunnel and foreshore works.

227. Mr Thirtle raised the question of additional working shafts and whether, had they been employed, the cost of the tunnels would have been reduced. The contract had been so framed that schedule items were provided only for the screen shafts, but had there been any overall saving to be made the contractor could have elected to sink additional shafts.

228. The Authors welcomed Mr Thirtle's remarks and those of Dr O'Sullivan and Mr Maughan on the use of fly-ash concrete. There had, not unnaturally, been opposition to use of that material, because it was not easy to handle. Furthermore, no interest seemed to have been shown by cement manufacturers in marketing fly-ash cement. It was understood that that had already been done in France, and it was a pity that was not being followed in Britain. However, the Authors thought that it would soon be realized generally that it was an important new additive material for concrete, but it should not be confused with admixtures to give special characteristics. It was also satisfactory to note that the Central Electricity Authority, in their latest contracts, called for fly ash where appropriate without the alternative of ordinary concrete.

229. There were considerable variations between different fly ashes, and of course care in selecting the material was essential. They had been very lucky at Portishead because they had had a particularly good fly ash—at least as good as the much-vaunted fly ash from Chicago, about which they had read so much. As Mr Thirtle had noted, after 28 days they had been better off than with ordinary Portland cement only. Mr Maughan and Dr O'Sullivan had asked about costs. On the sort of mix used at Portishead one would look for a gross saving of 6s/cu. yd of concrete, and then there was the saving of approximately 6d to 9d also related to a cubic yard of concrete in disposing of the fly ash. The resultant saving to be expected under usual conditions would be between 2s and 4s/cu. yd of concrete. At the Hungry Horse Dam in America it had been stated that a saving of 3s 6d/cu. yd had been effected.

230. The Authors were grateful to Mr Haxton who had given much useful additional information. In reply to his question regarding the man-hours expended on shop fabrication for structural steelwork, the Authors would be pleased to ascertain for him the requested figures. Regarding the close agreement in the cost per man-hour between the civil engineering and building contracts, the Authors confirmed that it was not unusual for the two figures to be of the same order. In connexion with the sinking of the 45-ft.-dia. pump pits, the high degree of accuracy demanded by the plant contractors had been costly; therefore Mr Haxton was correct in suggesting that there would be considerable saving if a make-up piece could have been used, but that had been contrary to the

**** This contribution was submitted in writing after the closure of the oral discussion.—S.E.O.**

Authors' instructions. They understood that the plant supplier would not accept the suggestion.

231. In regard to § 160, there was some ambiguity, perhaps because of condensing the Paper. Mr Haxton had commented that the Authors appeared from the paragraph to have been more optimistic than his firm had been. What the Authors had meant in referring to the three summer seasons was that they were confident of success with that particular contractor! It was, perhaps, a little ambiguous, but that had been the intention.

232. In reply to Mr Aries, although the Authors had recently been notified that some recirculation had taken place for the "B" station, they were waiting for the operational data, after which detailed consideration could be given to the problem.

233. The Authors fully appreciated Mr Aries's remarks upon the advantages of having the tunnel ends upon a slope, as had been done with the "A" station. However, they wished to note that the ruling factor had been one of cost. Having fixed the level of the soffit of the outlet to give sufficient water cover, any tilt in the tunnel end would have increased the depth, and accordingly the cost of the very expensive screen shafts and pump pits. There was no special virtue in the sloping end.

234. Mr Aries had referred to the bearing pressures upon the formation level; they had ranged between 4 and 6 tons/sq. ft.

235. In regard to colloidal concrete, the Authors had experience of that method of placing concrete, but had not found it economic in a situation such as that at Portishead; it had, therefore, not been discarded upon technical grounds as suggested by Mr Aries.

236. Mr Aries had raised the point of the weed blankets. The Authors had studied the matter a good deal in the Severn Estuary and higher up the river, and were certain that at every stage of the tide in a river with such an enormous rise of tide there was sometimes a different regimen at certain points at each tidal level. What was meant by that was that at one point there might be an eddy somewhere which developed at that particular water level. When the water level rose higher, that eddy probably ceased to exist or moved elsewhere. It was believed that what happened was that the debris collected in those eddies and gave the blanket formation; then the tide level changed, and the thing detached itself and went downstream in one large mass. It arrived suddenly at the intake, and of course was very inconvenient. It had been concluded that it was a phenomenon of rivers with a very large rise of tide usually associated with tidal estuaries. The situation was aggravated at extreme tides when there was a great deal of beach debris which was washed off and brought down.

237. The Authors were interested in Mr Maughan's remarks in general.

238. The Authors were aware of the normal velocity of water passing through coarse screens, but at Portishead it would have been very costly to have reduced the velocity through the screens to the usual net figure of about 1 ft/sec. However, as remarked by Mr Aries, by opening out the spacing of the coarse screens a satisfactory arrangement had been arrived at with the "A" station using the higher velocity of flow.

239. Regarding Mr Maughan's reference to the overall cost of the power station being rather high, the Authors felt that that was a little dogmatic since, bearing in mind the conditions, the total cost was not in their opinion unfavourable in relation to present-day power-station construction costs.

240. The Authors wished to thank Mr Whyte and Mr Palmer for their contributions, both of which added materially to the Paper.

241. Referring to Dr O'Sullivan's remarks on the welding of high-tensile steel, it might be of interest to note that, providing that the carbon content was not higher than 0.26%, satisfactory welds could be laid. However, it should be noted that certain difficulties remained, such as having to contend with a tendency for lamination during the rolling of plates; also there had been difficulties in obtaining the required yield strengths with the reduced carbon content.

242. In relation to the relative costs of boilers for oil or oil and coal firing, that was outside the scope of the Authors' work since it affected purely the plant; it might be added that there was no difference from the civil engineering point of view, apart from the question of fuel storage.

243. Dr O'Sullivan had asked for details of the test piling, and the Authors referred him to a Paper by Morgan and Haswell,² which covered the test piling at Portishead.

244. Mr Whitehead had referred to the possible means of diverting the eddies holding the blankets of sea-weed. Whilst his suggestions were interesting, the Authors did not consider them to be practicable or economic.

² H. D. Morgan and C. K. Haswell, "The driving and testing of piles." Proc. Instn Civ. Engrs, Pt I, vol. 2, p. 43 (Jan. 1953).