Paper No. 6576

Diving and salvage†

by

Reginald Walter Bishop, O.B.E., B.Sc.(Eng.), M.I.C.E.*

and

Peter Farquhar Flett, O.B.E.

Discussion

Mr J. W. Hunter (Director of Navy Works, Admiralty) said that in the department to which Mr Bishop and he belonged, the young civil engineers had to qualify as divers. That enabled them to inspect under-water jobs as necessary, which was very important in the Navy Works Department.

63. In his opening, Mr Flett had referred to the use of a craft working with a diving bell but in the Paper itself there was no reference to diving-bell work. On occasion he had known a diving bell to be used with success, as, for example, in Gibraltar on a dredging job where the rock proved too hard to be handled by the largest Admiralty rock-breaking dredger. An attempt was then made to blast the rock, using helmet divers drilling under water. That proved too slow, and a diving bell, which became available, was effectively used instead. It was approximately 14 ft × 10 ft (Fig. 20) and had a shaft reaching above water, which was supported by a craft 88 ft × 38 ft, and the divers entered through an air lock at the top and worked in the actual bell at the bottom. Fig. 21 showed the arrangements in the craft. Boilers provided the power for the lifting gear on the same deck to work the diving bell up and down. There were two compressors to supply the divers and their tools separately. The craft speeded the work because the holes could be drilled in the rock from inside the diving bell.

64. It was found, however, that the holes could not be drilled properly if silt was left on the rock surface. Mr Bishop, in his section of the Paper, had referred to the air lift. They had first tried to move the silt off the rock by an air lift. It lifted the silt quite well but with so much water that when the silt was discharged into a hopper barge it ran out through the doors back on to the sea bed. It was found better to use the method described by Mr Flett for working underneath ships; viz. a pressure jet of water, so that, when the bell was moved on to rock that had been cleared, the drills could work properly.

65. The holes were plugged after they were drilled, and as the bell was required for other purposes, the holes were charged and blasted by helmet divers. The rock was then dredged with a grab. Some 3000 cu. yd of rock were moved in this way.

66. Fig. 24* was a photograph of the craft. The air lock could be seen at the top, and the platform from which the men went in. The men were able to work in the bell for 3–4 hours about 36 ft below the surface of the sea.

67. In § 43 Mr Flett talked about the self-assurance required of divers. Not every man made a good diver. Some men were quite useful divers, but hated it. Others wanted to dive but could not. The men had to be picked for the job; they had to be resourceful.

† Proc. Instn. civ. Engrs, vol. 21 (Feb. 1962), pp. 347–366

* Figs 24–40 are photographs and are placed between pp. 768–769

FIG. 20.—DIVING BELL BARGE SECTION AT DIVING BELL

FIG. 21.—DIVING BELL BARGE PLAN AT LOWER DECK

68. He wished to put in a plea for engineers working with divers not to restrict themselves to one form of diving. He could recall several jobs where Asian and African skin divers had proved more satisfactory than helmet divers.

69. He recalled another occasion where the work had to be carried out in a shaft 40 ft deep, 4 ft × 4 ft 6 in. It was found that the best way to do this job was to work with a modified gas-mask supplied with air from the surface, and let the men wear plimsols with lead soles inside to ballast them down.

70. As engineers engaged on marine works they depended to a large extent on their working divers, and a lot of credit was due to these men, who were versatile and tenacious, and on occasion courageous. The working chargehands who supported them by organizing the work, and by deciding what were unreasonable risks to take, also deserved some of the credit.

Mr Peter Mason (Partner, Brian Colquhoun and Partners) said that Mr Bishop had made a comment in his opening remarks that civil engineers were not normally expected to have diving included in their curricula. He now wished to show very briefly something which might indicate that this did not necessarily obtain now.

72. When an engineering project involved diving, up to now the normal procedure had been for professional divers or a professional diving firm to be employed. There was one disadvantage about this, however, and that was that the engineers responsible for the job could only obtain the important under-water information at second-hand; they had to rely on the diver's interpretation of what he could see and feel. To overcome this, his firm had trained some of their engineers as a team of aqualung divers.

73. In 1960 in thick fog two steel barges laden with petrol and fuel oil ran into a column of a bridge over the Severn. At the time there was a flash and a large explosion, and in the morning it was seen that one of the piers was demolished and that two spans had disappeared. It was important from an insurance point of view to pin down the exact cause of the damage, whether it was due to fire, explosion or impact. His firm had been appointed to carry out the investigations. First of all they had used the diving team to find and plot the exact positions of the various bits of bridge that were in the water; not only to find their positions but to examine them to find out whether there was evidence of fire on the timber decking, how the members might have distorted, the way the rivets had sheared and so on. The diving team did this. The diving conditions were however, rather difficult. There was a 5-knot current much of the time. The depth of water was only about 30 ft but there was practically no still water, and it was very difficult for the divers to maintain position and find the various things. They found the spans by using a grab. When it hooked to a span they went down the grab line and worked their way along the wreckage, examining it carefully as they went.

74. The grab would not hook on to the piers, which were 7 ft diameter columns, so an area of river was squared off by the use of survey instruments from the remaining part of the bridge, and a systematic diving search was made to find and identify all the various portions of the pier. This was successfully carried out.

75. When all this information had been assessed it proved possible to make a conclusive report on the causes and mode of failure of the bridge. The use of technically qualified divers had proved invaluable on this investigation.

76. There were one or two other specialist jobs on which this diving team had also been used. One was the investigation of chemical damage to a long cooling-water conduit. The divers were used on this because they could go down without the cooling water being cut off and so examine the conduit under working conditions, trace leaks and carry out remedial work without the factory concerned having to shut down.

77. A rather more interesting job concerned a water-treatment sedimentation tank which was without any moving parts. The method of operation of the tank was as follows. The water to be treated was previously mixed with a coagulating agent and put in at the top of a central cone. The water passed down the cone and up into an outer chamber, where it gradually lost velocity because of the increasing width of the

FIG. 24.—TENDER TO DIVING BELL SHOWING SHAFT REACHING ABOVE WATER

(Aberdeen Journals Ltd)

FIG. 25.—SWEDISH TANKER *Oljaren* AGROUND ON MUCKLE SKERRY, APRIL 1951

FIG. 26.—SEAS BREAKING OVER THE AFTER DECK OF *Oljaren*

(Kemsley Newspapers)

FIG. 27.—GENERAL VIEW OF THE STARBOARD SIDE OF THE *Oljaren* IN DOCKING TRIM

(Grayson, Rollo, and Glover Docks Ltd
and Elsam, Mann, and Cooper Ltd)

FIG. 28.—*Oljaren*, IN DRYDOCK, SHOWING STARBOARD SIDE DAMAGE BELOW BRIDGE
58*

(Grayson, Rollo, and Glover Docks Ltd
and Elsam, Mann, and Cooper Ltd)
FIG. 29.—*Oljaren* SHOWING DAMAGE TO STARBOARD SIDE
AFTER-MAST

(Grayson, Rollo, and Glover Docks Ltd
and Elsam, Mann, and Cooper Ltd)
FIG. 30.—*Oljaren* SHOWING DAMAGE TO STARBOARD SIDE
ABREAST ENGINE ROOM

(Grayson, Rolto, and Glover Docks Ltd
and Elsam, Mann, and Cooper Ltd)

FIG. 31.—*Oljaren* SHOWING DAMAGE IN WAY OF AFTER COMPARTMENTS AND STERN GEAR

(Grayson, Rollo, and Glover Docks Ltd
and Elsam, Mann, and Cooper Ltd)

FIG. 32.—*Oljaren* SHOWING DAMAGE UNDER STARBOARD BOW

FIG. 33.—*Oljaren* SHOWING TYPICAL VIEW OF BOTTOM DAMAGE, STARBOARD SIDE

FIG. 34.—350-TON SECTION BEING CARRIED ACROSS DOVER HARBOUR

FIG. 35.—350-TON SECTION BEACHED ON BREAKING-UP SITE

FIG. 36.—200-TON SECTION BEING CARRIED ACROSS DOVER HARBOUR

FIG. 37.—STERN VIEW OF SALVAGE VESSELS

FIG. 38.—SECTION BEACHED ON BREAKING-UP SITE

FIG. 39.—SMALL SECTION OF BLOCK SHIP BEING CARRIED ACROSS THE HARBOUR ON THE HORNS OF THE COASTAL CLASS SALVAGE VESSEL

FIG. 40.—DREDGE *Hapai* SUPPORTED BY CAMELS

(Whites Aviation Ltd (N.Z.)

FIG. 41.—S.S. *Benledi* ON FIRE OFF MALTA

chamber. At a certain level the sinking rate of the floc which formed matched the rate of the rising water and a sludge blanket formed across the tank. Eventually chunks of it fell away into the bottom sump, where it was removed by static pressure. To make sure that the tank was working most efficiently (it was very difficult to see what was happening from outside) divers were sent down. They let themselves sink very slowly through these rather unpleasant conditions. They could actually see the forming of this sludge blanket. They could see if the floc was forming at the right rate and size, that there were no undue eddies formed and that there was no undue aeration. They went further down into the sludge-collecting troughs and although they could not see anything in the sludge, by touch they could say exactly how the sludge blanket was forming and whether it was creeping up the walls or settling in any way unfavourable to its eventual ejection by static pressure.

78. From these examinations of the tank under working conditions, the engineering divers could come back to the drawing board and design improvements to facilitate the actual operation of the tank.

Mr G. L. Hargreaves (Deputy Director, Navy Works Department, Admiralty) said that his criticism (which he thought both Authors would admit was just) was that the Paper made the whole thing seem far too easy. Both on the diving side (on which he could speak from a little experience) and, he strongly suspected, on the salvage side, things were very much more difficult than was indicated by either the text or the illustrations. This was an important point because there were many engineers, who had occasion to make use of the services of divers, who should not be misled into underestimating the divers' problems. There was ample proof of this in that one never heard of diving work on a disaster of any kind without many people enquiring why the divers could not do something that on the face of it seemed quite simple. Similarly, many engineers who had been on jobs employing divers were firmly of the opinion that the divers were lazy and spent most of their time sitting on the bottom drawing high pay.

80. The position on the average engineering job was difficult. He had with him two bottles of water, one taken from the tidal basin at Portsmouth and one from just off the north wall. By holding one of them up to the light one's fingers could just be seen through the bottom, having shaken up the silt. Holding up two of them one's finger could not be seen even 6 in. away. That water was clean compared with some of the water in which he personally had dived. It could be just like ink in the Firth of Forth, for instance, and in the Medway. He could say with perfect truth that at no time in any of his earlier days' diving had he ever seen anything out of his face plate except right at the top, coming up the ladder. The diver was working blind.

81. The first reaction of the average person was to say "What about lights?" He would be most interested to hear whether there had been any recent developments, because in his day lights were not popular with divers. Divers would do anything rather than take a light down with them. One reason was that in dirty water (and practically all the water round the ports was very dirty) the effect of a light was like a car headlight in a snowstorm with black snow. All the light was reflected back before it got to the target, and the only time one could see anything with a light (speaking of some time ago) was when one held the light a few inches away from the object. The average diver would say that at that distance it was quite useless, that he could "see" much better with his hands. Many divers would bear him out on that. They could make a better sketch from what they felt with their hands than they could from using the light.

82. It might interest the audience (and possibly the Authors would comment on it) that in the famous salvage operations carried out on *Egypt*, which was sunk in 70 fathoms off the mouth of the Channel, although it was very dark and the water was clear, with reasonably good conditions (one would have thought) for lights, the Italian divers practically throughout the operation relied on natural daylight, working from an

observation chamber, and they allowed about half an hour to let their eyes become accustomed to the gloom.

83. Next to darkness, the diver's greatest enemy—particularly if he were working on something other than inspecting—was cold. He could keep his body reasonably warm but he could not keep his hands warm, and he understood that the salvage operations on one of the M class submarines had been seriously handicapped and finally abandoned because the water was so cold that the divers could not work. It was deep water and it took them some time to come up. They had reached the submarine but their hands were so cold that they could hardly operate their dresses.

84. The difficulty of doing actual work under water was not fully appreciated by the man on top. A diver in a standard dress was wearing a bulky, cumbersome garment with heavy weights strung round his person, and the act of carrying out any action with his hands and arms, such as trying to undo a bolt or saw through something or bend on a line or handle a shackle was considerably harder than it was on top. Further, he was breathing compressed air, which he believed made for quicker exhaustion than working under normal conditions. It would be most interesting if the Authors would expand on their very brief comment, comparing the self-contained dress and the standard dress for arduous physical work under water.

85. There were other factors that one might take into account in work where there was any tidal current. A current of only a few knots was a tremendous handicap to the unfortunate diver, who either had to lie down flat to work, or hang on with one hand and have only one hand for working. He usually had to work on a very soft bottom with mud and old cables and bottles round him, and although he might spend hours on the bottom doing what appeared to be 20 minutes' work on top, if one endeavoured to duplicate some of these conditions, such as sitting in a flower bed on a frosty night and endeavouring to saw through a link of chain, one would have some idea of what the unfortunate diver had to do.

Commander C. G. Forsberg (Deputy Director of Marine Services, Admiralty) said that he would like to illustrate some of the difficulties and also to amplify and illustrate the rather short section at the end on deep water identification and recovery.

87. He had used an Admiralty Research Laboratory camera conceived, and produced in about three weeks from an ordinary outside broadcast camera from the B.B.C. On the bottom there was a "cage work" to prevent the lens from being damaged by being bumped on the bottom. Supposing the visibility under water was 12 ft and the camera was 12 ft off the bottom, so that one could get a good field of view, and there was a 12 ft swell on the surface, the camera was alternately hoisted up to 24 ft off the bottom, and plunged with its face in the mud, so that the cage was useful to protect the lens of the camera. That was an early model; today equipment is more robust.

88. When they wanted to adjust the camera they had to remove 48 nuts and bolts. Doing this on the rolling deck of the ship at sea was an extremely annoying operation, because when one came to put them back there were usually only 47.

89. Photographs had been taken by the television camera of pieces of Comet aircraft on the sea-bed off Elba. The camera had a very small field of view, so that one could not use the television camera for searching. Our navigational efficiency was not good enough, but it was very useful for identification purposes. They liked it very much in conjunction with diving but not as a substitute.

Captain W. R. Colbeck (Marine Surveyor and Water Bailiff, Mersey Docks and Harbour Board) said that he would like to endorse a previous speaker's remarks concerning the visibility problems of divers. In certain of the rivers around British coasts there was absolutely nil visibility. The Admiralty had done quite a lot of research work on this and their assistance had been given on the salvage of the *Empress of Canada*, when they produced a device which was very useful in dock diving. It was a Perspex cone which was machined and fixed to the face plate of the helmet, about 6 in. long, and that

gave the diver a line of vision about 9 in. from his eyes which enabled him to make inspections, and if the water was not too bad, enabled him to have it fairly close to his hands, giving him 6 in. more of clear vision than he would otherwise have. They had not used it in the tideway but it had been successful in one or two jobs in the docks. Some attempts had been made to clear the diver's vision by injecting streams of clear water, but the problem always was that the right salinity could not be obtained and it probably stirred up more mud than was actually displaced. He wondered whether anything further had been done on those lines.

91. He endorsed Mr Bishop's caution in § 32 on the dangers of producing an explosion during underwater cutting. He had had several cases of that happening. On one such occasion the diver's face could not be seen for blood, though fortunately it was only a bleeding nose. It was not the hydrogen from the cutting equipment (they were using the oxy-arc cutting gear) but the collection of marsh gas from the mud, and the explosive mixture was probably ignited by the arc.

92. He took issue with Mr Flett on the question of clamps. Although they had been used very extensively, not only by the Admiralty but by the Port of London as well, in his experience they were not nearly so positive, particularly when running against time on a rising tide and when a couple of the impact wrenches packed up and one might have to abandon the job. When turning up on bollards the ends were definitely solid and further they were easier to slip, certainly for slipping simultaneously. Working on a lift of 2,000 tons or so, and using four camels, placing the wire ropes, one could not always be completely sure of having them absolutely tight with an even strain on all of them. If two or three of them were slack just on getting the full weight one might lose all the weight on one pair of camels, which meant that the other pair were probably trying to carry the whole load. Lifting in still water it was all right, but in a tide rising at $1\frac{1}{2}$ to 2 in. per minute one had to be able to slip pretty rapidly. He had slipped with 650 tons on them, which was a little frightening. It could be done with bollards but he would not have liked to attempt it using clamps.

93. One point not touched on in the Paper was that, unless in shallow water, vessels, particularly those damaged by collision, usually turned on their side when they sank, which added considerably to the problems of placing the wire ropes, and when the vessel was lifted and put into shallower water there was the problem of uprighting, usually done by par-buckling. That could be done but added a great deal to the complexity of the job. With a ship sitting upright, lifting was comparatively simple, because one of the problems when she was on her side was that the wire ropes on one side came up the ship's bottom, which was relatively good, and on the other side had to come through the bulwarks, which probably would not carry the full weight. One had to get the wires positioned and tight when one had about 5 ft or 6 ft rise left, so that one got the full weight on the wire ropes at the top of high water to break in any weak structure. The wire ropes could be made fast at the following low water to get the lift.

94. Could Mr Flett give some information on the fire referred to in § 55 and the use of CO₂? Captain Colbeck had had to deal with some 35 or 40 ship fires which had been kept under control for varying periods with the use of an inert gas, usually CO₂, and in no case had they been able to discharge the cargo without the use of water subsequently. The CO₂ inhibited the combustion, but with packed cargo in a hold there was practically no cooling effect.

95. When the CO₂ was removed, which was necessary before the cargo could be discharged, in a very short time the fire started again. An American liberty ship had caught fire in mid-Atlantic. The fire was brought under control with CO₂ and she came into port but she had poor stability, a metacentric height of only 4 in. so it would not have been safe to flood a hold. The deck cargo and cargo in the 'tween decks and the upper part of the lower holds was discharged, leaving the affected hold, No. 2, intact, improving her metacentric height (GM in Fig. 12) to about 18 in. No. 2 hold had general cargo in the 'tween decks and cotton in the lower hold.

96. They opened up and took the gas down to the lower hold and discharged the

'tween decks and then similarly in the lower hold, taking the gas down a bale at a time and testing as the stevedores were working. They got down two thirds of the way and during the change of shift they took the gas down another tier of bales, but within 10 minutes the hold was a mass of flames. Would the Authors say what was the cargo in the hold in question and whether they had any trouble subsequently?

Commander J. R. Carr (Superintendent of Diving, Admiralty Experimental Diving Unit, Portsmouth) said that Mr Bishop had spoken of the naval sets and they had seen in them the transition from the standard diving gear that had served so well for over a century to the demand valve sets that were easier to use and lighter. These sets had been designed specifically for naval requirements, and some of them were unduly complicated for divers regularly operating in civil engineering work. In the Navy they had to employ a number of part-time divers who did not get nearly as much training or practice as he would wish, the design must therefore virtually include belt and braces. He suggested that the naval sets should be regarded only as typifying the change of family of diving apparatus.

98. There was a tremendous transition going from the heavy-booted diver, with his attendant, and his life dependent on the man up top, to the man who was neutrally buoyant so could not fall and who had a very different outlook in approaching his work under water. For this reason he suggested it was time to stop pitying the poor diver and instead to make him get on with the work. The diver was capable with today's apparatus of doing a great deal more than formerly.

99. It was, of course, true that visibility, certainly on the east coast of England, was extremely limited, but even then for special jobs the equipment could be forthcoming. They had heard of the cone of Perspex. One could also take a plastic bag full of clean water, shine one's torch through it and inspect anything one leaned it against. He could assure Mr Hargreaves that divers had now begun to like lights and to take them down with them. Lights were being made so that most of the rays could reach the target without undue snowstorm effect.

100. As far as cold was concerned, one of the handicaps with the standard diver was that if he had large wrists he could not move his hands at all because of the tight fit, and when the circulation was cut off it helped him to get cold even quicker. By having either much lighter rubber or by wearing wrist rings they were able to overcome this. Going through the North-West Passage the Canadians put divers down every other day to check the screws and they wore wrist rings and surgeon's gloves. Normally with a light rubber cuff and a "wet" Neoprene glove, divers could keep their hands warm quite a long time, and they were not handicapped nearly so much as they used to be in the old days.

101. The other great advantage was that it was not necessary to disturb the bottom and therefore it was a little easier to see anything that was there—unless, of course, the diver flicked his fins about too hard.

102. The most reassuring thing for the diver was to have communication with the surface. (Commander Carr then demonstrated the bone conductor telephone which was described in Mr Bishop's Paper.) The diver put it under the strap to his face mask either outside or inside his hood—wherever comfortable to him—and he could both speak and hear through this apparatus.

103. It was now possible for the diver to be in constant communication with the surface. This meant that anybody attending the diver could hear him breathing all the time, which was most reassuring for the supervisor. He could even hear the diver clearing his ears as he went down, and the diver could speak back. There was, of course, a certain technique in speaking under water. It was necessary to speak much more slowly, because one could not get one's breath quickly enough to speak at the rate at which one spoke on the surface; once the diver had learned how to talk under water he could do surprisingly well, even with a mouthpiece in his mouth.

Mr H. Murray Taylor (Marine Consultant, formerly Salvage Director, Metal Industries (Salvage) Limited) as a professional salvor, was pleased to say that there was nothing in the Paper with which he would wish to disagree.

105. The only matter which he would like to see enlarged a little was the use of compressed air as a primary means of salvage. It was referred to briefly in the Paper, but the only example given (§ 45) related to its use merely to supplement lifting by other means, in which compressed air provided only some 16% of the total buoyancy required.

106. In their Paper (§ 40), the Authors stated that buoyancy could often be restored by sealing individual compartments and displacing the flood-water by injecting compressed air, and he would give an example of how this method worked out in practice.

107. From a number of vessels successfully salvaged primarily by the use of compressed air, ranging from trawlers in shallow water to upturned battleships in quite considerable depths, he would like to take as his example the Swedish motor tanker *Oljaren*, which grounded on Muckle Skerry, Pentland Skerries, in April 1951, when fully loaded with some 13,500 tons of oil.

108. The Pentland Skerries are islands guarding the eastern approaches to the Pentland Firth and are consequently exposed to the influence of both the North Sea and the Atlantic, giving rise to strong tides, heavy and confused seas and changes of unusual rapidity.

109. Fig. 25 shows the *Oljaren* aground on the west side of the island which, although the largest in the group, is only $\frac{1}{2}$ mile long and $\frac{1}{4}$ mile wide and offered little shelter from any direction, and certainly none from the Atlantic.

110. The flood tide sets from the west at 7 knots during neaps and 10 knots at springs, carrying with it the sea and swell from the Pentland Firth and far beyond. The ebb tide divides to the eastward of the island and the two streams met just off the casualty, causing considerable turbulence over a wide area. Thus, even under favourable weather conditions, approach by sea was difficult and could only be accomplished for occasional brief periods at slack water, and then only by relatively small craft.

111. Soundings taken at low water outside the *Oljaren* showed 15 ft forward, increasing along the port side to 42 ft aft. On the starboard side, however, due to the spurs of rock which could be clearly seen running out towards the ship (Fig. 25), the soundings were reduced to 7 ft and even 4 ft at a number of points along her length.

112. At the first inspection the starboard side was found to be breached up to deck level in one place and almost every compartment in the ship was tidal, including the engine room. At least 10,000 tons of oil had been released as the result of bottom damage in way of the cargo tanks.

113. From the outset it was decided that the use of compressed air would alone be practicable in this instance, and no further consideration was given to any possible alternative method of salvage. At the first opportunity, therefore, a small salvage party was embarked together with the necessary air compressors, tools, stores and victuals, to enable them to operate as a self-contained unit throughout the preparatory phase of sealing and preparing the various compartments for the reception of compressed air.

114. The operation had proceeded satisfactorily enough for two days when the wind freshened from the west and the sea was soon breaking over the decks, both forward and aft, bringing all work to a standstill. Fig. 26 showed the after deck being swept by the sea, at this stage of the operation.

115. It was necessary to take steps to destroy completely such buoyancy as had been restored, in an endeavour to prevent movement of the ship which could only have given rise to further damage. The wind and sea continued to increase until about midnight when the ship was struck amidships by what was best described as a tide lump—a solid wall of water which rose some 40 ft above the general level of the sea. The force of the sea was such that *Oljaren*, representing a relatively inert mass of some 5,500 tons, was lifted bodily and thrown against the spurs of rock, causing extensive damage which at the time could not be even approximately assessed. At the same time the

compressors and salvage paraphernalia were wrecked and much of the work already done could be discounted.

116. Following this undoubted set-back, it was considered prudent to withdraw the salvage party from the wreck for the time being, while the whole proposition was re-examined. By the following afternoon, the sea had run down sufficiently for them to be taken off by motor boat.

117. The starboard side was now found to be breached over wide areas almost to deck level in a number of places in way of the cargo tanks, engine room and after compartments. As diving was quite impracticable, no reliable estimate could be made of the full extent of the underwater damage. Apart, then, from the greatly increased difficulty of salvage, there was now the added risk of the vessel being beyond economical repair in which event salvage, even if practicable, would obviously prove unrewarding.

118. However, salvage would not be what it is without an undoubted element of risk, and so it was decided to accept the situation which had developed and to proceed with the operation as soon as weather conditions would allow. Within 24 hours of leaving, the party was back on board and, as opportunities made this possible, additional air compressors, plant and stores were embarked, and the work pushed forward with all reasonable speed.

119. In due course, that is after a total of 8 days' work on board, the vessel was ready for refloating and, as the flood tide set directly on to the ship, it was necessary to make provision for flotation to become effective during the falling tide. The tug was connected to the stern at high-water slack and maintained position throughout the ebb, refloating being effected without incident at about dead low water on April 30, 1951.

120. The tug was then transferred ahead and the casualty towed to Longhope Bay, where she was anchored the same evening. Preparations were then put in hand for towage to a drydock for examination. This necessitated reclaiming additional buoyancy in the after compartments, again by the use of compressed air, to enable her draft aft, which was over 42 ft at the time of refloating, to be reduced in accordance with docking requirements. It was necessary, also, to remove all the remaining oil from the ship, and some 3,000 tons was transferred to coastal tankers and shipped away. Following this, all compartments were freed of gas and the usual preparations made for the projected tow to the Mersey.

121. Fig. 27 showed the starboard side of the ship in final docking trim, in which the upper limits of the damage to the side can be clearly seen in relation to the deck and water line.

122. On completion of the necessary preparatory work, *Oljaren* was towed to Liverpool and dry-docked, revealing for the first time the full extent of the damage. Figures 28 to 31 showed the damage to the starboard side below the bridge, abreast the after mast, in way of the engine room and finally in the vicinity of the aftermost tanks and stern gear.

123. Fig. 32 showed something of the damage underneath the starboard bow, whilst Fig. 33 showed a typical view of the bottom damage in which the extent to which the bottom generally had been set up could be gauged by reference to the keel blocks placed at 4 ft above the dock bottom.

124. After the survey had been completed and tenders taken, the vessel was refloated once more on compressed air and towed to Bremerhaven, Germany, for repairs. Altogether she was kept afloat for some 8 weeks and towed over 1,500 miles after refloating in the condition shown, throughout which time the buoyancy necessary was obtained entirely by the displacement of water by means of air under pressure.

125. Mr Murray Taylor felt that this example would be of particular interest at the present time because tankers of 10 times the capacity of the *Oljaren* had recently been completed and even larger vessels of this type were projected, to which a similar method of salvage could be applied.

Mr J. Shombrot (Senior Civil Engineer, Navy Works Department, Admiralty) said

that the Authors had given a very good picture of the various types of equipment available to divers; but what civil engineers were perhaps more particularly concerned with were the relative merits of that equipment in their day-to-day civil engineering tasks. He would confine his remarks to the actual diving dress. It was quite remarkable that they should still be using equipment introduced more than 100 years ago, with comparatively little modification and adaptation of the basic form of diving dress. Civil engineers were especially conscious of their responsibility to protect the lives of those engaged in underwater work, and the fact that standard dress had stood the test of time was surely evidence that it was a safe and proven method of diving.

127. There were bound to be hazards in any diving operation, but such accidents as occurred were almost invariably caused by infringement of regulations, lack of proper safety precautions, defects of equipment, sometimes even to lack of adequate training on the part of either the diver or his attendant, and often to a number of extraneous circumstances which could not have been foreseen. He recalled a particularly unfortunate and fatal accident to a diver working in standard dress in a dock. A ship had just entered the dock as the blocks were being adjusted and the ship's pumps were still working. The diver's air pipe was sucked into one of the intakes and the hose became kinked, thereby cutting off the air supply. The diver must have tried to cut himself free but failed to do so with the diminishing air supply. The standby diver was not fully dressed at the time; part of his equipment was not readily to hand and by the time he got down it was unfortunately too late. He quoted this as an illustration of the type of accident which certainly need never have happened, but it did show how a series of contributory factors could in practice cause accidents. The particular incident was not connected with his own Department.

128. Still on the subject of standard dress, apart from the physical discomfort of the heavy and cumbersome gear on getting into the water and on leaving it (and it must be admitted to be cumbersome) it was nevertheless comfortable enough below water for the type of jobs that civil engineers had to do. The substantial weight of the standard dress was an added advantage when working in a tidal current or on an uneven bottom. Against that the extra weight could be a danger if the diver were suddenly subjected to a fall and if his attendant were not quite alert at the time.

129. The reserve of air in the standard diving dress was also of value in an emergency or to a diver doing prolonged physical work. He could in fact readily take a breather if he wished to, and the physical and psychological advantage of being able to breathe freely inside a rigid helmet was somewhat better than the rather tightly-fitting mouth-piece of some of the self-contained equipment.

130. With standard dress there was direct contact with the surface at all times and it was a comfort to have both an air pipe and a breast rope on which to signal should the need arise. Unfortunately, these same links with the surface could be a danger if the diver were working in a confined space or anywhere where there were projections on which to foul his lines—underneath an open piled jetty, for example, where there were all sorts of obstructions.

131. On the subject of communications, his experience had been that telephones tended to be of a rather hit-and-miss kind. They seemed to fail just at crucial moments. He certainly welcomed this evening the opportunity to see some of the latest equipment, if in fact it was going to ensure greater reliability. The present type of telephone line carried in the breast rope added greater weight and tended to make the whole movement of the diver very much more sluggish.

132. With standard dress, the support on the surface in the way of diving crews, pumps and so on was important to the manning of a diving job. Although in average conditions in civil engineering divers did not work in depths of more than about 30–40 ft of water, there were occasions (with submarine pipelines, for example) when they needed to work in greater depth, and if there were manual pumps then of course the pumping crews were very much greater in number. As the Authors had pointed out, the use of compressors for prolonged working or in depths greater than 99 ft was adopted, but

there was a growing tendency to use them in shallower depths and for alongside work.

133. Compressors also brought other dangers with them, some of which were not always known. He was thinking particularly of the danger of the air supply to the diver being fouled by the exhaust from the compressor, resulting in slow carbon monoxide poisoning of the diver. This could easily be avoided by making sure that the exhaust was carried well away.

134. Turning now to the self-contained equipment, which certainly had the advantage of lightness and greater mobility, diving inspections could be undertaken more quickly without the relatively elaborate support on the surface. The fact that there was generally no air line with the self-contained equipment dispensed with at least one hazard to be fouled by obstructions. At the same time, it introduced another and graver risk in the event of the diver becoming fouled and unable to extricate himself or to be freed by another diver before his air supply ran out. Always, even with self-contained equipment, a lifeline was a wise precaution. The Factories Act prohibited the use of self-contained equipment which was regenerative and acting on a closed circuit.

135. On balance, with the exception perhaps of inspection and simple under-water tasks, and in spite of having already passed its hundredth birthday, he suggested that the standard dress had many more useful years of life ahead in civil engineering, perhaps with some modification and adaptation on the lines of the surface-demand equipment which had been described in the Paper.

Mr L. G. Ellis (Resident Engineer, Medway Bridge; Freeman, Fox and Partners) described briefly the construction of the foundations of the new Medway Bridge at depths reaching 60 ft below high-water level, using standard diving equipment as well as self-contained diving equipment.

137. The two river piers of the Medway Bridge supported between them approximately 900 ft of motorway and as Resident Engineer he personally inspected the formation before underwater concreting and used self-contained compressed air diving equipment for this purpose.

138. After excavation had been completed, the cofferdam was divided into five compartments by precast concrete panels fixed underwater by divers using standard equipment. Each reinforced concrete dividing wall consisted of three separate sections attached together by metal brackets, with dowel bars keying the panel into the underwater concrete. The brackets were burnt off after concreting any one particular compartment and recovered. The formation of each compartment was cleared of loose chalk by a 6-in. dia. air-lift pipe.

139. For inspection purposes a shot line (Fig. 22a) was dropped in the centre of a cleared compartment, with a large hook at the bottom to which a stray line was attached. The diver descended the shot line feet first and communicated with the surface by signal line. The lamp leads were kept separate to avoid fouling the diver's lines. A wet suit was used made of Isoprene, a combination of latex and Neoprene having great flexibility and heat insulating powers. The signal line was attached to the front of the harness.

140. The Medway was one of the most polluted rivers in Britain and visibility was nil below 10 ft depth. Artificial lighting provided by two 1500-watt lamps just enabled the diver to see the amount of sediment covering bedrock chalk, but generally the bottom conditions were interpreted by the feel of the chalk formation.

141. 2-in. diameter pipes were fixed in the formation to check the possibility of grouting any voids formed at the juncture of the fissured chalk and underwater concrete, but the grout acceptance was small. To check settlements, a 6-in. diameter pipe rising above the water level, had a 2-ft square plate welded to the bottom, firmly embedded in the chalk formation (Fig. 22b).

142. For concreting under water, the contractor used 4-cu. yd bottom-opening skips in preference to tremie pipes on account of the weight and lack of mobility of the winching gear. Each underwater concrete pour took approximately 24 hours and divers were sent down at intervals to take sample tins of underwater concrete.

FIG. 22a

FIG. 22b

FIG. 22A AND B.—UNDERWATER INSPECTION AT MEDWAY BRIDGE USING SELF-CONTAINED DIVING EQUIPMENT

143. The results obtained by these inspections had been very satisfactory. Half the total dead load had now been imposed on the formation and settlements had not exceeded $\frac{1}{4}$ in.

144. The chief disadvantages of the self-contained equipment were the lack of communication with the surface and the absence of the head protection afforded by standard equipment. The bone conductor was a possible answer to the first problem and elaborate precautions had been taken at Medway Bridge for the diver's safety.

Mr V. Campbell (Marine Services Division, Admiralty) said that a previous speaker had dealt with many of the points he had intended raising on compressed air, but he wished to continue where the speaker left off and to say that compressed air was used and was a main medium for raising the Admiralty floating docks in Malta and Singapore. As many might know, these docks were sunk by enemy action and were sitting in about 70 ft of water. The only means of raising these sections of dock was by introducing compressed air. It was not possible to build cofferdams extending above the surface or to employ salvage pumps in order to gain buoyancy so compressed air had to be used. In each section of the dock, along the centre-line, a spill pipe was fitted. This meant that a pipe of 8-in. to 10-in. diameter was lowered right into the bottom of the compartment, and the air was introduced on the surface, displacing the water, which was spilled out through the pipe. Each spill pipe was fitted with a non-return or flap valve. When the compartment was emptied and the air commenced to escape, when the water pressure outside overcame the air pressure inside, the valve closed and the compartment was kept dry. That was the method used to raise the dock initially on to its end, where-by they could use their pumps.

146. The Author had referred to lifting by mechanical means and no doubt had in mind the Coastal Class salvage vessels. These useful little ships were 150 ft long and between 800 and 900 tons displacement or something of that nature, and were of great help. Their safe working load for lifting was 100 tons but this was far exceeded at times.

147. These ships had been used extensively around the United Kingdom and had been actively engaged in clearing the western entrance to Dover Harbour, a job which to everyone's annoyance had dragged on for many years. It was an exposed position; there was no shelter from the piers. Dover was an artificial harbour with a couple of walls and huge gaps in them here and there, so that the ships were lying in rather an exposed place, and the tidal currents were very strong; in fact, the diver was only able to work there from an hour before high water to about three hours after, at each tide.

148. Other speakers before him had emphasized the cold during the winter months. The divers had suffered terribly with cold during underwater lifting and cutting and in fact one or two of them had to be laid off and operations suspended at times.

149. Fig. 34 showed a section weighing approximately 350 tons, and carried (submerged) on the bows of two of the lifting craft, the two small Coastal Class salvage vessels. Here they were lifting rather more than they were designed to lift. Fig. 35 showed the section on the beach.

150. Fig. 36 was another section suspended on the bows of the two salvage vessels. When the ships were heavily laden forward like this they were unable to steam under their own power, so the two Dover Harbour Board tugs were assisting here. Fig. 37 showed a stern view, and Fig. 38 showed the section beached. The weight of the section was 200 tons. Fig. 39 was a small section of one of the blockships being carried across the harbour on the horns of the Coastal Class salvage vessel.

Surgeon Lieutenant-Commander D. E. Mackay (Admiralty Experimental Diving Unit and Royal Naval Physiological Laboratory, Gosport) said that he unfortunately had the job of investigating diving accidents, and two very prominent lessons arose. It did not matter what equipment divers were wearing, it was the state of training in that equipment

that was important. Most of the accidents occurred with people who had had very short training. A man who had been diving for years did not seem to run into difficulties.

152. Most of the accidents had been in sets that were regenerative. This was mainly because of the naval connexion, but they did use compressed-air sets in the Navy as well as standard equipment, and neither of those types had caused him any trouble yet. People did sometimes get trapped. If there were any snags it was with lines, air pipes and so on, and this was again an indication of the relatively untrained man. With a fully trained man and nothing trailing one did not expect accidents and they did not seem to happen. His advice to people was not to be frightened of diving. Accidents were an indication of the state of training. When a diver passed from the "L" stage to the stage where he was given a licence it did not mean that he was a fully qualified or experienced diver at once. Similarly, a man who had just passed his course in diving was not yet fully responsible for all his actions.

Mr D. H. Little (Superintending Civil Engineer, Navy Works Department, Admiralty, Pinner) said that a question often put in this Institution to the Authors of papers was "How much did it cost?" He was not going to put that question tonight; he was going to answer it. Diving and salvage were very very expensive, so that it paid a shipowner not to let his ship run aground. It paid a civil engineer not to include any more diving in his designs than he had to. He did not want this to be thought a carping criticism. Obviously there were occasions when one must have diving and salvage. The Paper tonight had been a most interesting and valuable contribution, but these factors had to be borne in mind—that it was expensive work and should not be included deliberately in civil engineering works.

Mr R. V. Watson (Senior Civil Engineer, Soil Mechanics Ltd) asked the Authors to give their views on the question of using divers in boreholes of say 3 ft in diameter, sometimes filled with clear water and at other times muddy. On occasions people wanted to know what the bottom of a borehole was like. How sensible was it to put a diver down?

The following contributions were received in writing:

Captain W. O. Shelford, R.N. retired (Manager, Underwater Division, Siebe, Gorman and Co. Ltd) wrote that the Paper being presented by two Admiralty officers, not unnaturally described diving equipment developed for naval purposes, and was therefore to some extent misleading to civil engineers.

156. In particular, the swimmers' air breathing apparatus and the surface-demand diving equipment were not available outside the Services, and were far too expensive and complicated for civilian purposes. There were equivalent apparatuses, designed for the commercial market, which were just as effective, far cheaper, and easier to maintain.

157. The Navy used light-alloy cylinders largely to achieve non-magnetic apparatus, for which there was no need in civilian work, and the cylinders used on these two equipments did not comply with present or proposed Regulations for the Compressed Gases. Equally the light-alloy storage cylinders described in § 15 were not used nor available commercially. The normal practice in such cases was to use standard steel storage cylinders which were available for hire in the United Kingdom and at many ports abroad at very low rates.

158. In describing underwater communications in § 21, the Authors specifically referred to "all-metal transceivers". These had been shown to have a very low efficiency and were not used outside the Navy. The Admiralty apparatus described in this paragraph was not transistorized but valve-operated. Transistorized telephones were however available.

159. Though not yet widely used in marine salvage, the latest trend in underwater television development was the "diver-held" camera. This was a smaller version of the

heavy deep-water cameras used in the *Comet* and *Vulcan* salvage operations and its cost was about one fifth of the larger unit. It had proved extremely useful in tracing cracks and faults in the masonry of breakwaters, dock walls, and dams⁶.

160. This camera could also be used in deep water without a diver, and the Scottish Hydro-electric Board had one permanently installed for inspection of the inlet gratings of one of their dams.

Mr K. A. McKechnie, (Resident Civil Engineer, Johore Bahru Power Station, Malaya; Freeman, Fox and Partners) wrote that he had read the Paper with considerable interest. His own experience in this field had been limited to Malaya and his remarks must therefore be qualified to the extent that they only applied to tropical (and hence warm) waters.

162. His first experience of diving was in connexion with the Connaught Bridge Power Station cofferdam mentioned by Packshaw⁵. After two or three attempts, he ceased to use the full Siebe-Gorman equipment for two reasons. The first was the difficulty of movement in confined spaces inside the cofferdam and the greater risk of entanglement due to the number of projections on both the equipment, and the cofferdam. The second and even more persuasive reason was the time lost in dressing and undressing in the suit and the physical discomfort due to the heat while so engaged.

163. He therefore took to using a converted gas mask,—the conversion being to remove the canister and connect through a valve mounted on the diver's belt to a pressure hose supplied from a conventional diving pump.

164. This equipment proved quite satisfactory once the user was able to time his breathing to the rhythm of the pump. It was of course outclassed by the modern free diving or surface diving equipment referred to in the Paper.

165. It had the advantage (mentioned in § 28) that the airline provided both reassurance and a means of signalling to the attendant above. It also frequently provided a safe route back to the surface if the diver had lost his bearings in the discoloured water.

166. He had used similar equipment during the construction of the circulating-water works for the power stations at Malacca and Johore, and he was confident that for normal inspection work when dives were limited to 20 to 30 minutes' duration it had the advantage of quicker preparation, greater mobility under water and less risk as the whole outfit could easily be jettisoned if the hose became entangled or damaged and the diver could then swim up to the surface. The only refinements on his present equipment were the use of a modern face mask which relieved the face of the wearer from the pressure of the water and the use of compressed air cylinders as a substitute for the pump, thereby reducing the number of men required to assist the diver.

167. He had used this equipment up to depths of 45 ft which was about the limit normally required on civil engineering works. If the equipment were to be used in colder climates a rubber suit such as that used by the Admiralty would be of considerable benefit to the diver.

168. An air lift of the type referred to in § 24 was successfully used at Connaught Bridge to lift from the cofferdam silt and small pebbles which had been excavated by the divers using water jets from areas inaccessible to the grab. It was a more primitive version than the one described in the Paper being simply a 1-in. diameter pipe projecting some 6 to 9 in. into the bottom end of a 6-in. diameter steel pipe, with a 6-in. diameter armoured suction hose at the top to discharge the material over the side of the cofferdam. The only limit to its lifting power appeared to be that the material must be small enough to enter the bottom of the main pipe without fouling the 1-in. diameter pipe.

169. The same air-lift was used to remove the laitance and loose concrete from the top of each pour of underwater concrete, again in conjunction with diver-operated water jets.

Lieutenant Commander H. Wardle, R.N. retired (Head of Diving Division, Reed and Mallik Limited, Civil Engineering Contractors) wrote that the Paper dealt adequately

with the material development of diving apparatus and the section on salvage work was excellent. He thought that to the civil engineer associated with work using divers, the first part of the Paper was incomplete without reference to the modern diver and the effect of new material developments on his capabilities.

171. There were many constructional works which necessitated the employment of divers, but on the other hand, the appearance of divers on other sites meant trouble. In the writer's experience of dealing with engineers, there appeared to be widely divergent views on divers generally, he considered, therefore, that discussions on diving could not begin without first attempting to define the diver.

172. The broad definition, that he was a man capable of working under water was far from complete. The varying grades of diver were legion. Even in the Royal Navy there were certain short courses which qualified a man to go under water and carry out limited work. The following list illustrated some of the variations:—

Naval trained

173. *The standard diver* had received at least 3 months' training, mainly in the orthodox helmet equipment. Such divers who left the Navy within the last 10 years had also been trained in the use of various forms of light-weight equipment. Many leaving before this had been trained in earlier forms of light-weight equipment.

174. *The clearance diver*. He had received at least 5 months' training mainly in lightweight equipment, was a highly trained underwater swimmer, but had limited training in standard diving.

175. *The free diver*. He had received at least 6 weeks' training in light-weight equipment. As the name implied, he was an underwater swimmer, trained to carry out simple tasks under water.

176. *The shallow water diver*. He had received between 1 and 3 weeks' training in lightweight equipment, and was trained to carry out elementary underwater work.

177. The above covered the main naval courses. Both the standard and clearance divers could have completed further training to qualify for higher grading. From time to time there had been other short diving courses which came broadly under the heading of shallow water diver. In the writer's view, only the standard and clearance diver could be regarded as professional divers.

178. The civilian-trained diver was hard to define: some had completed a course of 2 or 3 weeks' duration and held rather grandiloquent certificates of qualification, others had started as a diver's linesman and had "picked it up" under the guidance of another diver, and lastly there were the amateur divers from various sub-aqua clubs. Broadly these types of diver could not be compared with the ex-naval standard or clearance diver although, as in all things, there were exceptions. There were divers who, although they had not received extensive training, had become first class in their trade.

179. How had the post-war introductions of the various types of light-weight diving equipment effected the potentiality of the diver? There was no doubt in the writer's mind that it had been enhanced enormously, there were many tasks which the diver in light-weight equipment could complete equally effectively and more speedily than the helmet diver.

180. It was as well to point out at this juncture that to carry out "work" using light-weight equipment the divers must be highly trained and 100% competent in all conditions. The layman watching the adventures of various well known personalities swimming around in still clear water received the impression that it was a simple matter to use the aqualung. In British waters if the water was clear it was usually moving and if it was still it was black, usually for diving it was both moving and murky.

181. On the other hand the amateur having had some swimming-bath training and a few dips in places like Lulworth Cove was often carried away and enthusiastically decided he wished to become a diver. Such people naturally found it difficult to obtain employment with reputable firms, and seldom reached the standard required. Undoubtedly whilst "feeling their way" they were hazarding their lives. Any diver

under water was always conscious of the primeval instinct to survive, the less experienced the diver, the stronger the instinct. It followed that the diver's ability to concentrate on his work (and therefore his efficiency) varied directly with time spent under water.

182. Many engineers had had some experience in helmet diving and, therefore, were aware of the way in which movement was restricted. Another "snag" was working "head down" so often necessary on foundation work; as the outlet valve on the helmet was lowered in relation to the flexible dress, air built up in the suit itself, and it was necessary, therefore, to raise the head frequently to release the excess air. But the light-weight diver could work literally standing on his head.

183. Some people considered, for heavy work and for work in the black and muddy depths of docks, that light-weight equipment was unsuitable. The writer did not support this view "providing the diver is 100% efficient". Some comparisons were listed below. The light-weight equipment referred to was surface supplied by air compressor. For contracting work it was considered that the short endurance of the aqualung was too great a limiting factor though it was, of course, ideal for survey work.

Advantages

184. The diver was more mobile. Apart from the obvious advantages the need to moor the diving boat or platform immediately over the works was often avoided.

185. The light-weight diver could work in strong tides. The surface area presented to the movement of water was less (approximately 1.2 knots as opposed to 0.8 knots).

186. He required less air, approximately 1 cu. ft/min. per atmosphere against 1.5 cu. ft/minute for the standard diver.

187. The whole equipment was less bulky and therefore was more speedily moved and required a smaller working area.

188. The light-weight diver could work in any attitude and in a smaller space.

Disadvantages

189. The light-weight equipment was less robust, required more frequent maintenance and replacements.

190. It had no satisfactory telephones as yet in commercial production.

191. For prolonged work in the cold water the kit was not so warm and comfortable as the standard equipment.

192. The diver seldom remained completely dry, and precautions were necessary in polluted water.

193. The inexperienced diver was more likely to get into difficulty.

194. Reed and Mallik had been faced with the need to carry out underwater work from time to time and decided, some three years ago, to form a Diving Division within the main structure of the company. For this purpose, the writer, having retired from his appointment as Deputy Superintendent of Diving, Royal Navy, joined the firm, and, having gained some experience of civil engineering, took over the task of organizing and operating this Division.

195. All the divers employed had been trained in the Royal Navy and since joining the Division had worked on a wide variety of works in docks, harbours, rivers, lochs and the open sea. They had also carried out ship work and all had experience in the use of underwater cameras and television.

196. It had been found from the civil engineer's point of view, especially when time was vital, that the diver with surface-demand equipment was so flexible in his operations that diving work had been speeded up to a point where divers were not being used as a last resort but as integral members of a construction team. The new types of equipment had not only affected the outlook of the site engineer but appeared to have brought forth a new type of diver free from the old-fashioned conservative ideas and more than willing to try out new equipment and techniques.

Mr J. P. Mahony (Civil Engineer, Navy Works Department, Bahrain) said that brief

mention had been made of the Comet airliner which crashed into the sea, south of Elba, on 10th January 1954. This was undoubtedly one of the most important salvage operations undertaken in recent years. Because the plane had been flying at considerable height and speed when it exploded, he would be interested to know how the wreckage had been located over such a wide area.

Mr Philip S. Hutchinson (Designing Engineer, Auckland Harbour Board) wrote that he was particularly interested in the section of the Paper dealing with sunken wrecks. In 1957, the Auckland Harbour Board's bucket dredge *Hapai* overturned and sank, $\frac{3}{4}$ mile off shore, and was found lying on her starboard side in 26 feet of water, with a considerable portion of her hull above water level at low tide.

199. No special salvage equipment or lifting vessels were available in New Zealand or Australia, and the job was tackled using any standard gear and winches which were readily available, together with lifting camels designed and built for this one job.

200. In order to right the dredge, eight frames, made of hardwood and steel, were erected from the exposed bilge. These were designed to transmit a pull of 60 tons each, using timber piles driven into the sandy harbour bed, 500 ft from the wreck, as anchorages. A righting moment of 28,000 tons-ft could then be obtained, with the use of heavy tackle with an eleven-fold purchase and 5-ton diesel and steam winches. The dredge was successfully righted using this equipment in an operation lasting about 3 hours. This left her with the deck about 10 feet under water at low tide.

201. Cylindrical pontoons (Fig. 40) were constructed to give sufficient buoyancy to lift and move the *Hapai* to shallower water, when, with the deck above water level, the hull could be pumped out and the ship refloated. The diameter of the camels was determined by the buoyancy required to be spaced out along both sides of the ship. The displacement of the *Hapai* was approximately 1,400 tons and the submerged weight 1,150 tons. After some consideration, the dimensions decided upon were—12 camels, 17 ft diameter, 24 ft long, weight 18 tons, with 138 tons net buoyancy each, and 1,656 tons total net buoyancy.

Structural design of the camels

202. The pressures, acting on the walls of the submerged camel under load, were calculated and an additional 5 lb/sq. in. was added as a contingency. The resultant pressure was independent of depth. Ring girders were provided at 4-ft centres, and bending moments in these were calculated by the column analogy, 4 in. $\times$ 3 in. R. S. J's being found sufficient.

203. Shell thickness was calculated from stresses due to circumferential, longitudinal and bending tensile forces, these being 2,080 lb/sq. in, 2,080 lb/sq. in and 4,160 lb/sq. in. respectively for $\frac{1}{4}$ -in. plate. This plate thickness was considered to be the smallest desirable, to withstand subsequent handling and local loading. The shell was also checked for crinkling through bending as a beam by a formula from Conway's "Aircraft Strength of Materials".

204. The load on the flat ends of the camel was taken by three pairs of boiler stay tubes extending end to end, three vertical internal 10 $\times$ 5 in. R.S.J's and seven horizontal external 4 $\times$ 3 in. R.S.J. stringers at centres varying from 21 in. at the top to 2 ft 6 in. at the bottom. The plate thickness was calculated to be $\frac{5}{16}$ in. from Crashof's, Pounder's, Bach's and Timoshenko's formulae. The central bulkhead was of similar construction to the ends. The weight of each camel was 18 tons approximately, including over $\frac{1}{2}$ ton of ballast.

205. Towers consisted of two 6 $\times$ 6 $\times$ $\frac{1}{2}$ in. angles with a central 10 $\times$ 6 in. R.S.J. and extending 4 feet above the camel were constructed at each end to enable the fixing of lifting wires to be carried out above water level at low tide.

206. The lifting wires were led around a fairlead at the centre of each end of the camel. Thus the towers could be maintained vertical (or at any required angle) without imparting a rotational force to the camel.

207. Buffers were provided at each end to keep the thin shell away from the hull and to transfer all the heavy loads through the ends. The buffer width was 12 in., 18 in. or 24 in. depending upon the curves of the belting of the *Hapai* in the vicinity.

208. Calculations for the size of the valves were based on the use of one compressor of 250 cu. ft/min. capacity per pair of camels. This required a 6-in. water valve at the bottom of each compartment and a 1-in. inlet valve and air hose. With this arrangement a pair of camels could be blown out to full buoyancy without undue pressure drop through the 6-in. valve, in about 40 minutes. Safety valves were included and these could be opened when faster sinking was desired.

209. To enable full buoyancy to be obtained in less than 1 hour, a total of six compressors with capacities from 155 cu. ft/min. to 250 cu. ft/min. were accommodated in a cargo lighter moored alongside but held clear of the camels, by two piles fitted each end with rubber buffers, and hung horizontally between the *Hapai* and the lighter. Individual 1-in. hose led from each compressor to the control device called "the organ", situated on a temporary bridge constructed on the *Hapai's* upper works well above water level. From a common 3-in. pipe manifold, 15 ft long, blowing and venting valves, and 0-15 lb/sq. in. pressure gauges, were arranged to allow the control and measurement of buoyancy in all 24 compartments of the camels. From a measurement of the camel freeboard or submergence, together with the internal air pressure, the buoyancy to the nearest ton could be obtained from a table. The internal air pressure could be read only when blowing or venting was stopped.

Attachment of camels:

210. The largest wire rope available in New Zealand in sufficient quantity was 7 in. circumference 6/37 galvanized wire. This was cut into lengths of about 230 ft to pass, doubled, around the hull of the *Hapai* opposite each end of each camel. Before the dredge was righted, the ends of the wires were coiled as far under the ship's side as possible, and the wire laid around the upturned hull. After rolling over, both ends were then available.

211. Perhaps the most vexing problem of all, was how to fix the 7 in. wires to the camels. Finally conventional dog clips were made in aluminium bronze, five of these withstanding the test load of 70 tons. The pair of camels was then evened up to the correct height with the assistance of a floating crane on each side, and a full buoyancy test carried out. The friction of the wire rope against the hull was relied upon completely, to prevent rendering, and it was necessary, during test and subsequently, to ensure as near as possible, the same buoyancy in each camel of the pair.

212. The wreck was lifted into shallower water in two stages using the tide rise to give a vertical lift of 8 ft. and 9 ft. 6 in. In this position the deck was above low-water level and the hull could be pumped out.

213. The dredge was now again in operation. The cost of the twelve camels was £35,000. The cost of the salvage was £110,000 and refitting and cleaning amounted to another £50,000. A replacement dredge would have cost approximately £750,000.

Mr I. D. Scott (Terresearch Limited) was interested in compressed air equipment, particularly in the design of the automatic demand valve. This demand valve was invented in 1942 by two Frenchmen, Jacques-Yves Cousteau and Emile Gagnan, and it was tested in the Riviera under the noses of the Germans who, fortunately, did not realize that the range for self-contained diving was being increased to 30 fathoms.

Mr D. L. Bell (Retired Civil Engineer, Malta, G.C.) suggested that the Paper had met a long-felt need in drawing the attention of engineers to modern developments in underwater equipment, and particularly to diving technique. This should change their attitude to underwater works. Until quite recently, very few civil engineers were competent helmet divers, largely because of the sheer physical effort needed and the extreme personal fitness called for.

216. Now that modern self-contained compressed-air equipment was readily available at reasonable cost, together with training facilities, it was practicable for engineers, on a much larger scale, to inspect underwater sites prior to design and also work in progress, instead of leaving these important duties in unskilled and non-professional hands.

217. However, the diving equipment outlined by the Authors was really only a beginning. The requirement for major underwater projects was power tools of capacity and dimension. The sheer physical labour of transporting them and working them below water would be eliminated in due course even as the digger and bulldozer had replaced the shovel.

218. A beginning had been made and Mr Bell invited the Authors' attention to a unit called "Mini-Sub" which was already being produced by Messrs Robot Operators and Electronic Automation.

219. This was a torpedo-shaped underwater vessel, driven by electric batteries capable of an underwater speed of about three knots. It was used to transport the diver, wearing compressed-air equipment, quickly to and from the site. This was an important consideration as the duration of a dive at depth was limited in spite of modern equipment. The "Mini-Sub" could also carry small power tools for minor works and a television camera so that engineers, supervising the works from above water, could instruct drivers as necessary.

220. This was a useful start on the right lines but it was too limited and for major civil engineering projects a "Mini-Sub" of larger size was needed, capable of carrying large power tools, with high-capacity compressed-air bottles and possibly other sources of power.

221. Mr Bell hoped that the lead which the Authors had given would be followed in such a way that really major civil engineering works requiring foundations down to a depth of, say, 200 ft (as might be the case for a Channel Bridge) could be tackled with confidence and with much greater economy than at present.

Mr Bishop, in reply, firstly wished to thank all who had contributed to the discussion; they had obviously spoken from personal experiences and many interesting points had been raised. It was a pleasure to see so many Naval officers at an Institution meeting and the remarks by those who had taken part in the discussion had certainly widened the scope of the Paper.

223. Mr Hunter had said that not everybody made a good diver. This was true because aptitude was an important factor but it should be remembered that even a trained man required regular practice if he were to remain efficient. The frequency of diving largely depended upon the nature of the job but in the Navy Works Department all qualified divers, including civil engineers, were required to have a few refresher dives at least once every twelve months.

224. Mr Mason had mentioned the advantages of civil engineers being able to dive, but there was one aspect which was possibly overlooked: it gave great encouragement to men working underwater if engineers occasionally went down themselves to see what was going on, instead of relying on reports by other people.

225. The hazards of diving were emphasized by Mr Hargreaves. The standard equipment, which weighed about 190 lb above water, was undoubtedly cumbersome but many divers derived a good deal of self-assurance from the fact that they were dressed in robust equipment of proved reliability and, even if they blacked out, they were still safe. The density of air increased with pressure. In shallow water this was hardly noticeable but, in depths exceeding 100 ft, there was an increased stiffness in breathing. However, provided a man tackled his work calmly, breathed regularly, and took occasional short rests to avoid a build-up of carbon dioxide, there was usually no discomfort.

226. In depths greater than 200 ft a diver was subject to nitrogen narcosis, or what Captain Cousteau termed "rapture of the deep". Considerable research had failed to reveal the cause but the symptoms were similar to drunkenness—a carefree abandon

and a loss of clarity in thought. This could be avoided if the air were replaced by an oxygen/helium mixture and, in 1956, Senior Commissioned Boatswain G. Wookey, wearing standard equipment fitted with an injector unit, descended to the record depth of 600 ft without any ill effects. The pressure on him at that depth was 17 tons per square foot.

227. A simulated dive to 820 ft in a wet decompression chamber had subsequently been made by Hans Keller, a Swiss mathematician, but details of his breathing mixture and decompression tables had not been published. The claim that he had made a break-through which utterly changed recompression concepts had aroused a good deal of speculation, especially in the U.S.A.

228. A fall under water in standard equipment could be dangerous. A diver was subject to Boyle's Law, and if he fell from the surface to 33 ft, before the pumps could increase the pressure of air in his suit, the absolute pressure on him would be doubled and the volume of his suit would be halved. If, on the other hand, he fell from, say, 99 ft to 132 ft the absolute pressure would be increased by only 25%. The "squeeze" caused by a fall could be fatal, especially in shallow water.

229. From this aspect, a diver was safer in compressed-air equipment because the flexible rubber suit, which fitted closely to his body, did not form part of the breathing system and the pressure of air to his lungs was automatically adjusted according to depth by the demand valve. Any discomfort, due to the small amount of air trapped in the diver's thick woollen under-clothes, could be obviated by partly inflating the suit from a small bottle of compressed air carried at waist level. (Fig. 15). The Neoprene suit did not suffer from this disadvantage because the material was porous.

230. The bone-conductor type of telephone equipment had been demonstrated by Commander Carr. The idea had originated in Sweden but it had been developed by the Admiralty Experimental Diving Unit at H.M.S. *Vernon*. The apparatus was compact, robust, and efficient, and it would be a boon to civil engineers and salvors. Voice reception was remarkably good but it was surprising to hear a man literally talking out of the back of his head.

231. Commander Carr had commented on Mr Hargreaves' query about cold hands. When visibility was poor, divers depended upon their sense of touch and they were therefore not keen on gloves. However, some type of light-weight glove was desirable, even as protection against cuts and abrasion. It was not unusual for a diver to surface and find his hands streaming with blood from cuts which he had not felt.

232. Mr Shombrot had raised an important point. Which was the most suitable type of diving equipment for civil engineering work? The answer was not easy because conditions were so varied, but the Author agreed with Mr Shombrot that for heavy manual work, especially where conditions were difficult, standard equipment was preferable. For instance, if a man in standard equipment accidentally struck his head against a piece of jagged steel, there was just a dull clonk and maybe a dent in his copper helmet. But, if the man was using compressed-air equipment and only wearing a soft hood, the result would be very different.

233. None the less, compressed-air equipment had other advantages which had been emphasized by several speakers and, provided conditions were reasonable, it was of considerable value in the hands of experienced men. The surface-demand, or "hookah", equipment was of special interest to civil engineers and was suitable for light work and inspection purposes.

234. A life-line was essential with all types of equipment and, as an additional safety precaution, divers using self-contained equipment should be trained in "free ascent". If a man, who had to jettison his equipment, attempted to hold his breath while ascending to the surface, he could be very seriously injured. A positive pressure of only 2 lb/sq. in. in a man's lungs, caused by a small change in depth, could burst his lungs and air would be forced into the blood stream.

235. Mr Ellis had described the use of bottom-opening skips for underwater concreting. Maltese divers favoured bottom-opening canvas bags and this method had

been a success on a number of Admiralty jobs. In still water it was not difficult to obtain good results but, it was important that the mouth of the concrete container—whether it were a skip, bag, or tremie—should be immersed in the mass of wet concrete before it was discharged.⁷

236. Underwater work was expensive and, as Mr Little had said, it should be kept to a minimum on civil engineering work. Prefabrication above water could be the answer and many interesting jobs had been carried out in this manner⁸. On the other hand, some engineers who were not divers themselves tended to think automatically in terms of cofferdams and other forms of temporary construction when divers could possibly carry out the work more economically. As in other fields, underwater “know-how” had increased considerably in recent years and several firms now thought it worth their while to set up special underwater divisions.

237. Mr Waterson had asked if it were sensible to put a diver down in a 3-ft dia. borehole. There was no apparent danger but many men would suffer from claustrophobia. As a general rule, no man should be called upon to dive in a space which was so confined that another man could not go to his assistance in an emergency.

238. Captain Shelford had pointed out that there were differences between naval and civilian compressed-air equipment. This, of course, was true because different requirements had to be met, but all equipment functioned on the same basic principles. Equipment manufactured for civilian use was kept as simple as possible but the quality of workmanship was impressive and some interesting features were incorporated. For example, the Siebe Gorman *Mistral* demand valve was venturi-assisted; and the Normalair demand valve was located at chin level, thus obviating the mouth-piece.

239. The fact that Mr McKechnie’s diving experience had been limited to the tropics should cause him no regrets; the clear warm waters of the East Indies were preferable to the murky depths of the Clyde. He had described the successful use of a converted gas mask. This had been used extensively during the war but it was a dangerous form of diving. The face piece could easily be knocked off and if, for some reason or other, the air supply suddenly failed, the diver could be asphyxiated. Improvised equipment should not be used unless the circumstances justified the risk.

240. The air-lift was a simple but very effective piece of underwater equipment. The pipe was usually about 8-in. diameter and the air chamber surrounding it was 2-3 ft from the lower end. Air was supplied at 20/30 lb/sq. in. in excess of the water pressure at the bottom of the pipe. The efficiency of the equipment decreased with every foot of pipe that projected above surface level and it failed when the emerged portion exceeded one third of the total length.

241. Lieutenant-Commander Wardle had emphasized the importance of proper training. His comments were fair because a number of untrained men found their way into this specialized sphere and, after a little experience, they seemed to think that they were ready to tackle anything. A diver need not be particularly athletic but physical fitness was another important factor. A medical examination before diving was essential and, if the job were protracted, at least once every 3 months thereafter. Medical authorities⁹ recommended that special attention should be paid to the respiratory and cardiovascular systems. The main disqualifying conditions were usually those which interfered with “ear clearing”. Doubtful cases were submitted to a test dive in a compression chamber.

242. Mr Bishop was glad that Mr Scott had mentioned Cousteau¹⁰ and Gagnan because they had pioneered the development of compressed-air underwater breathing apparatus. New equipment, incorporating their fully automatic demand valve, was first tried out in 1943 and Cousteau reached 140 ft without any difficulty. Five years later, Frederic Dumas, another member of the famous French diving team, reached 305 ft and that was regarded as the *absolute* limit for compressed-air equipment. In some form or another, a demand valve was now incorporated in all modern equipment and Fig. 23 was a diagram of the valve used by the Navy.

FIG. 23.—DIAGRAM OF NAVAL DEMAND VALVE

Mr Flett, in reply, agreed with Mr Hargreaves that salvage work was more difficult in actual execution than had been made apparent in the Paper but practical difficulties could not be described. They had to be experienced to be fully appreciated.

244. The efficiency of artificial lights largely depended upon the clarity of the water; sand and mud caused reflexion. Mr Hargreaves had mentioned that the Italians, engaged on the *Egypt* salvage operations, had worked at 420 ft without any artificial light. During the salvage of the *Comet*, which crashed off Elba, this was found possible at a depth of 300 ft until the sea-bed was disturbed by trawling; visibility then became very restricted and artificial lights were of little help.

245. Captain Colbeck's comments were much appreciated. He had mentioned the use of clamps as opposed to turning up on bollards. Mr Flett's experience had been mostly with clamps and he had found no difficulty provided all wires were properly laid out and were clear to run. A plentiful supply of working impact-wrenches certainly helped. Nevertheless, whichever method were adopted, success largely depended on how the salvage crews were trained and what they were used to.

246. Regarding the use of CO₂ in controlling a fire, it was essential—in common with other measures—to exclude air from the compartment. In the case described in § 55, CO₂ was used to keep the fire subdued until 6-in. × 6-in. holes with prepared patches had been cut between all stiffeners on the after end of the bulkhead. Each frame space was dealt with on its own. No chances could be taken because the cargo in the hold consisted of 500 tons of sugar and 30 tons of matches. Fig. 41 was a photograph of the *Benledi* on fire.

247. Mr Murray Taylor's account of the salvage of the *Oljaren* was an interesting addition to the discussion and he was to be congratulated on having accomplished a most difficult salvage feat. Compressed air had been widely used by the Admiralty but space had not allowed this subject to be dealt with in the Paper.

248. Mr Mahony had raised a question about the recovery of aircraft wreckage; it was invariably scattered over a very wide area and up to now the same procedure—sweeping the sea-bed by trawl—had been adopted in every case. Of course, there were limitations because, in places, the sea-bed was rough and undulating.

249. The salvage of the *Comet* had attracted much attention. In the first instance, the various pieces of wreckage were located by otterboard fishing trawls and marked with buoys. Salvage vessels then laid special moorings, and television cameras were lowered to identify the wreckage and direct the grabs which were used for recovery.

250. In the case of the *Victor*, practically all the wreckage was recovered by trawling: ordinary fishing nets were adopted but the mesh was smaller than usual so as to collect small pieces of aircraft strewn over the sea-bed.

251. The American B.66, which was lost off the East Coast of England, was eventually located a long way from the reported position of the accident. Diving was restricted because tide, visibility and weather conditions were bad, and the movement of salvage vessels to pick up every small piece of wreckage could not be justified. It was therefore decided to engage commercial trawlers and these vessels, working to the directions of Admiralty Salvage Officers, recovered 75% of the aircraft. The trawls were made of wire and it was surprising to see what could be towed behind a 115 ft trawler with a 700-h.p. diesel engine.

252. In all these cases, the exact accident positions were unknown, and the successful location and recovery of aircraft wreckage was largely due to the fact that experienced fishermen worked alongside the salvage teams.

253. Captain Shelford and Commander Forsberg had referred to the use of underwater television cameras; they were undoubtedly a great help in confirming any object on the sea-bed, especially when the water was too deep for normal diving. These cameras were not used on the B.66 because tidal conditions were bad and visibility was poor, but they were used with success on the salvage of both the *Comet* and the *Victor* aircraft.

254. Mr Hutchinson's description of the salvage of the *Hapai* showed how slender a margin there was between profit and loss on salvage work. The Admiralty had recently carried out a similar operation at Rosyth Dockyard where a dredger was sunk off the North Wall. However, it was simpler than the salvage of the *Hapai* because the winches for parbuckling could be set up on the North Wall. Mr Hutchinson's task of providing solid anchoring points on the sea-bed was much more difficult and he was to be commended on successfully achieving what some might have considered the impossible.

255. In conclusion, Mr Flett agreed that salvage was expensive but pointed out that it was not always the value of the ship that mattered. She might be blocking a harbour or navigable channel; or, as with the *Comet*, the knowledge gained by examining the salvaged wreckage could be of inestimable value to aircraft designers.

REFERENCES

5. Savile Packshaw, "Cofferdams", Proc. Instn civ. Engrs, vol. 21, Feb. 1962, p. 388
6. W. O. Shelford, "Underwater television in docks and harbours", Dock Harb. Author., vol. 43, May 1962, pp. 24-26.
7. Civil Engineering Code of Practice No. 4, 1954, Part 8.
8. G. C. Grove and D. H. Little, "The design and construction of some slipways up to 1,200 tons". Instn civ. Engrs, Maritime Paper No. 17. 1951.
9. British Medical Journal No. 5068, 22 February, 1958, p. 475.
10. J-Y. Cousteau, "The Silent World", Hamish Hamilton, London, 1953.