Mr. J. F. BATEMAN, F.R.S., said, from his long connection with the Clyde, he might be permitted to commence the discussion. He was quite sure the Meeting had been interested by the Paper, but it might possibly seem to some of the Members that it might have been written by a Glasgow antiquarian, historian, or statistician, inasmuch as it gave but little professional or engineering account of the works by which, during the last hundred years, the Clyde had been brought into its present condition. When, however, the Paper was read in detail, it would be found that much information which appeared to be wanting was really contained in it. He might state that he believed the Author intended at a future time to give—beyond the history of the navigation and of its progress—a description of the engineering processes which had brought about the great results attained. It appeared that, though, some two hundred years ago, the inhabitants of Glasgow made some attempts to improve the bed of the river, it was not until 1768, that any decided course of improvement was determined upon. The proposals of Golborne were then adopted, and from his recommendations the whole of the operations carried out, from that time to the present, had probably originated.

Although Smeaton, in 1765, reported upon the Clyde, Golborne was the first person to determine and recommend the means by which improvements could be brought about. When it was considered that one hundred years ago there were only 12 in. to 15 in. of water in the channel of the river where there were now 14 ft.; that vessels of only 3 ft. draught could pass where now vessels of 22 ft. draught could ride with ease and safety; and, further, that the tide, which occupied 3 hrs. between Greenock and Glasgow, now accomplished the same distance in 1 hr. 5 mins., those results must be regarded as of a most gratifying character. Those improvements had been effected, first, by narrowing the river, by means of groynes, or jetties, as Golborne had recommended, and in addition, by removing shoals and obstructions which impeded the flow of the water. Inasmuch as the river was in many parts too wide, and spread over extensive sand banks, it was considered desirable to concentrate its force in a narrower channel, in order that, after the removal of the gravel on the surface, the increased velocity of the stream should work its own way upon the sandy beds.

Thirteen years after the first introduction of the groynes, namely, in 1781, Golborne reported his great gratification that, though he only expected, by the works proposed in his first report, to get a depth of some 4 ft., a depth of 12 ft. or 14 ft. had been obtained

by the simple means he had recommended. The process of putting in groynes, or jetties, was, on the recommendation of Rennie, carried out to a still greater extent, and their number was increased from fifty to more than five hundred. Subsequently, on the advice of Telford, the groynes were shortened, and retaining walls were put in from groyne to groyne, to prevent interruption in the velocity and to secure uniform scouring effects from the current of the river. The channel had since, from time to time, been enlarged, to such an extent that in effect the dimensions of the river now differed greatly from what they were formerly. Its width at the Broomielaw, which was 160 ft., or 180 ft., fifty years ago, was now 450 ft., or more; and it would bear vessels afloat of from 20 ft. to 23 ft. draught at high water, and from 14 ft. to 16 ft. draught at low water. The present object of the Trustees was to deepen the channel at low water to 20 ft. The greatest credit was due to all connected with the management of the river Clyde for the foresight, the energy, and the admirable manner in which they had administered their trust; and also to the various engineers for the skill they had displayed; and to no one more, perhaps, than to the Author, who had modestly refrained from mentioning the very considerable improvements effected during the years he had been in charge of the river, although they had still further rendered it conducive to the prosperity of the district, and to the convenience and advantage of the commerce of the world.

It would be interesting to those who had listened to the successive modes adopted for deepening the channel by dredging, to hear the gradual results that were obtained by that operation. Thus, in those portions of the channel where, from 1755 to 1768, vessels could pass which drew only 3 ft. of water, the available depth was gradually improved up to 1830, to 15 ft.; in 1839, to 17 ft.; in 1854, to 19 ft.; in 1861, to 20 ft.; in 1862, to 21 ft.; in 1870, to 22 ft.; and works were now in contemplation for obtaining a greater depth. During the last twenty-eight years there had been an amount of material removed by dredging equal to 15,000,000 cubic yards, or an average of about 500,000 cubic yards per annum for twenty-eight years. The quantity dredged last year was about 1,000,000 cubic yards. The Meeting might therefore infer the beneficial results which would accrue from that amount of excavation, and from the still greater improvements which were yet likely to take place. He would not now occupy the time by entering further into particulars, which he should otherwise have been happy to give; but would express the great gratification which this Paper had afforded him. He

was sure the Institution never had had a Paper containing more valuable information, and especially on the subject of dredging. He believed there was scarcely an instance in which the cost of dredging, according to the character of the material excavated, including the expense of repairs, had been more economically performed, ranging as it did from about 12*d.* or 14*d.* per cubic yard for gravel and till, to 2½*d.* and 3*d.* per cubic yard for sand and silt; nor, he believed, had the material ever been carried in hopper barges a distance of twenty-seven miles, and disposed of at so small an expense as that of 5½*d.* per cubic yard. The whole management of the Trust had been characterised by similar economy. The engineering works had been carried out with great skill, and he believed there was no river in the world that had derived more beneficial results from engineering science.

Mr. REDMAN said no river had attracted more attention, none had been more written about, or had engaged a larger amount of engineering talent, or had more readily returned its equivalent in the increased commerce of the metropolis situated upon it, than the River Clyde. He would, in the first place, draw attention to a Paper read before the Institution on March 24, 1846, "On the Estuary of the River Severn."¹ The discussion upon that Paper diverged into a discussion upon the Clyde, and a number of material facts were given connected with that river which had been placed succinctly before them in the present Paper. The Author correctly stated that as far back as the reign of Queen Mary, in 1550, the first attempt was made to improve the river, from its lower parts to Glasgow, by means of statute labour; but the means were inadequate to the end. In 1759, an Act was obtained for the formation of locks; happily, for Glasgow, never carried out. In 1806, Smeaton proposed a lock across the river. Fortunately, that proposition was also not acted upon; but it was the advice offered by Golborne, Rennie, and other distinguished Engineers, to throw out jetties—which had been subsequently connected together by parallel banks—that had produced the results detailed by the last speaker. Mr. Redman had with him the deposited Parliamentary plans of 1836, and of 1839. The Author had very properly, in his historical Paper, given due credit to those plans. Mr. Redman had marked in pencil, from Glasgow downwards, the widths laid down by Mr. Logan, the then Engineer of the Clyde Trustees, endorsed by Mr. Walker, and afterwards acted upon; and Mr. Redman believed, as the Author stated, if those lines were compared with the lines on

¹ *Vide Minutes of Proceedings Inst. C.E., vol. v., p. 300.*

the Admiralty chart, they would be found to have been acted upon in the improvements of the Clyde in the same way as the lines for the Thames embankment, from the same authority, had been adhered to. The results of the works upon the Clyde had been so extraordinary that he did not think it would be a reiteration to state a few facts which did not appear in the Paper. 3 ft. 3 in. was the depth of water at the time of Telford, and at the Broomielaw there was now the same rise of tide as at Greenock, with 10 ft. or 11 ft. depth of water at low water. Practically, the channel from Greenock to Glasgow was now level. Instead of being a highly inclined slope, and an inclined plane of water diminishing upwards, there was in effect a horizontal bed from Greenock to Glasgow, and there was the same rise of tide at Glasgow as at Greenock. He believed the tidal observations made by the Author, borne out by the experience of other rivers, showed what appeared at first sight an anomaly. There was, in fact, as high a 'back range' of tide at high water at Glasgow as at Greenock, and a lower ebb at Glasgow by 15 in. than at Greenock. The same held good in the Thames; but the zeros of the tide gauges had never been connected by spirit-levels. There was no doubt as great an oscillation of tide at London Bridge as at Gravesend, and at spring tides it was well known there was also a lower ebb. The same phenomena applied to the Clyde between Glasgow and Greenock, and the explanation was simple enough, namely, there was a large tidal estuary flowing out of the upper reaches of the river. The tide was ebbing in the upper river, and the tide of the lower river, rising earlier, met the ebb of the upper river; so that there was a higher oscillation of water at Glasgow than at Greenock. This apparent paradox was pointed out in the discussion upon a Paper read before the Institution, November 20, 1860, "On the River Orwell and the Port of Ipswich."¹ That Paper had created some divergency of opinion. Its Author showed by tidal observations—though they were not connected with spirit-levels—that there was a higher rise at Ipswich, by nearly 2 ft. 3 in., than there was at Harwich. That fact certainly appeared anomalous, and inquiries were made whether low water was higher at Ipswich than at Harwich, and whether the increase of rise was at high water. The same occurred on a large scale in the estuary of the Bristol channel. At the Flat Holmes there was a rise of tide of 36 ft. to 41 ft., and a 'heading-up' of a tidal wave of 60 ft. at Chepstow. It was clear in that case, with deep water and a funnel shape, the

¹ *Vide* Minutes of Proceedings Inst. C.E., vol. xx., p. 4.

lift of water there, must be on the surface, the low water at Chepstow being higher than at the Flat Holmes; and in the same way the high water was elevated at Chepstow. The same argument hardly held good in the case of the Clyde. The Thames had a large outfall, with a great breadth of deep water. That was not the case of the Clyde. Although it had a large estuary at Port Glasgow, where it was two miles to three miles across, yet the navigable channel at low water, opposite Port Glasgow, was proportionably not much larger, so that the tidal wave operated upon a comparatively narrow channel downward as well as upward. The tidal wave was not propagated in the same degree as in the Thames, or in the large estuary of the Severn.

The commercial results at Glasgow were so marvelous, that Mr. Redman simply referred to them as showing the great benefits that were produced by engineering works of the character described. The early reports of Smeaton, Telford, and Rennie showed that the river was navigable only for barges to Glasgow. At the present time the export and import tonnage of Glasgow amounted to the extraordinary sum of 2,500,000 tons; that was to say, the commerce of the port of Glasgow was equivalent to half the foreign tonnage of London or of Liverpool. That result, compared with the early condition of the river, was so remarkable, and so exemplified the effects of the works which had been executed, that Mr. Redman thought it was deserving of notice. With regard to the propagation of the wave, the Author of the Paper now before the Institution stated that, the difference of time between Greenock and Glasgow, at an early period of the history of the river, was from 2 hrs. to 3 hrs. In the report of Mr. David Logan, an old officer of the Clyde Trust, under date October 5th, 1835, the difference at that period was about 1 hr. 45 mins.¹ On the Admiralty chart of 1860, the difference was there defined to be 1 hr. 15 mins.; and now, on the authority of the Author, it was stated to be only 1 hr. Those results were remarkable. In the Thames there had been a corresponding acceleration of the tide due to similar works, but not in the same degree. Then, again, with regard to the height of spring tides—in evidence on the Clyde Navigation Bill of 1836, the spring tide at Port Glasgow was stated to be 10 ft. 10 in., while at the Broomielaw it was 6 ft. The Admiralty chart of 1860 showed that at Glasgow it was then 12 ft., and at Greenock 11 ft. The Author stated it was now somewhat

¹ *Vide* "Tidal Harbours Commission. Appendix (C.) to Second Report of the Commissioners, with supplement and index," page 450.

increased. A large body of evidence was taken by the Tidal Harbours Commission on the state of the river in 1845, and Mr. Redman had an extract from their report which he thought was worth referring to. Speaking of the great development of Glasgow, the Commissioners said :—" But engineering skill being not only slow in its development, but having often to struggle with prejudice and self-interest, it has now been discovered that many of the plans of the Clyde Trustees were short-sighted; that in order to continue their improvements in deepening their river, they must now submit to a large outlay for rebuilding bridges, the foundations of which were not laid deep enough; that weirs have been permitted across the river, nay, sanctioned by Act of Parliament [49 Geo. III. cap. 74], so as to prevent the flow of the tide above the city, and stop all navigation above the bridges; that a considerable expense for dredging might have been saved if the natural flow of the tidal water had been properly directed; the harbour space might have been enlarged, and the general depth of water throughout the river increased; and that, with all these improvements, the dues on shipping might have been lightened, and the ports of Greenock and Port Glasgow, at the mouth of the Clyde, might have been spared a large expenditure in the construction of docks, made in expectation of traffic which it is not probable will ever now be realised."¹ It was obvious that the preceding strictures of the Tidal Harbours Commission were not tenable. The works referred to were now in course of extension. The present tonnage of Glasgow and its insignificant amount at Greenock and Port Glasgow sufficiently stultified them. They were as follows :—

	Tons.
Glasgow	2,378,961
Port Glasgow	82,611
Greenock	769,202

The large works recently constructed and still being carried out at the two latter ports also showed forcibly enough the development of steam shipping; and the yet continuing increase to the maritime supremacy of Glasgow, was remarkably and entirely the result of the works which had been described in the Paper.

The following details as regarded the cost of dredging might possibly be of interest :—

¹ *Vide* "Tidal Harbours Commission. First Report of the Commissioners," page vi.

[1872-73. N.S.]

	Per cubic yd. s. d.		Per cubic yd. s. d.
1835. RIVER THAMES. Black-		RIVER CLYDE—1841 . . .	1 6
friars, below low water;		Do. 1842 . . .	0 10½
mud, sand, and gravel .	1 11	Do. 1843 . . .	0 8
Do., Whiting shoal, con-		Do. 1844 . . .	0 8
creted mass, to 15 ft.		ABERDEEN HARBOUR . . .	0 4
below low water . . .	1 0	AYR . . .	0 5
Do., above bridge, gravel		LEITH . . .	1 0
into barges, 5d. . . .	1 2	PERTH . . .	0 3
Additional, for lighterage		Do., Clay . . .	0 3½
below, 9d. to 1s. . . .	1 5	YARMOUTH . . .	0 5

Lord BLANTYRE, through the Secretary, said, he had never been able to understand the boasting there was about the improvement of the river Clyde. His estate ran 5 miles along the southern shore, and 2 miles on the northern shore of that river. The state of the river throughout those 5 miles was most humiliating. In effect it was treated as Scotch farms were formerly—the lands near the houses got all the manure, and were fair to look upon; the outlying lands got little or none, and became poorer every year. So that middle section of the Clyde seemed to go back, compared with the improvements nearer Glasgow.

He would offer a few remarks as regarded the unimproved state of a considerable portion of the river, and having been a ‘residenter’ upon the Clyde for the best part of his life, he submitted the following propositions:—1. That the river Clyde had not been improved to an extent at all commensurate with the length of time the work had been in hand, or the mechanical appliances and funds the Clyde Trustees had possessed. The time had been 103 years—the appliances, 53 years of dredging without steam, and 50 years of dredging with steam (1824-1873). The amount of money he could not give. 2. That the river was not likely to be adequately improved so long as the Trust was exclusively in the hands of the inhabitants of Glasgow.

When the Magistrates of Glasgow, a hundred years ago, applied to Civil Engineers to give the town a better connection with the sea, the Magistrates received the reply, that, if a certain principle was followed out, the sea would be brought up to the town. That principle was to bring the river into the best form for transmitting the tidal wave, or, in other words, to give the bottom and sides of the river such a form as would cause the sea tides to rise to the greatest height, and in the shortest time, in the harbour of Glasgow. Where that principle had been carried out the success had been very marked, but how far it had been carried out might be brought to a crucial test by any one. The following data as

regarded the tides were taken from the chart of the Clyde prepared by Captain E. K. Calver, F.R.S., Assoc. Inst. C.E., in 1860, and showed the velocity of the tides in different stages of the river:—

	h.	m.
High water, Full and Change, at Greenock	12	8
„ at Dumbarton rock	12	20
Tide rose about 7 miles in	0	12
<hr/>		
High water, Full and Change, at Dumbarton rock	12	20
„ at Yoker	1	15
Nearly 8 miles in	0	55
<hr/>		
High water, Full and Change, at Yoker	1	15
„ at Glasgow	1	25
About $5\frac{1}{2}$ miles in	0	10
<hr/>		
High water, Full and Change, at Glasgow	1	25
„ at Greenock	12	8
Total distance traversed in	1	17
<hr/>		

It appeared, therefore, that high water occurred at Greenock at full and change of the moon at 12 h. 8 m., and at Glasgow at the same periods, at 1 h. 25 m., or high water at Glasgow was 1 hr. 17 mins. later than high water at Greenock, but the progress of the tidal wave along the river was not uniform. That was the test by which Lord Blantyre proposed to prove the backward state of the river improvement.

In its first stage, the tidal wave reached Dumbarton rock at 12 h. 20 m., or only 12 mins. later than it reached Greenock, though the distance was about 7 miles. In the second stage, it reached Yoker at 1 h. 15 m., and, therefore, took 55 mins. to pass over about 8 miles. In the third stage, it reached Glasgow at 1 h. 25 m., thus overcoming the last $5\frac{1}{2}$ miles in 10 mins., or at about the same speed as from Greenock to Dumbarton, which was not a little remarkable. The last stage nearest to Glasgow represented the improved portion of the river. The middle stage, the unimproved portion, where the wave took 55 mins. to overcome 8 miles. The first stage nearest the sea had more advantages by nature, though he readily admitted it had been greatly improved by dredging a deeper and straighter channel.

It was some time since the chart of 1860 was prepared; the tide took then 1 hr. 17 mins. to pass from Greenock to Glasgow.

Mr. Bateman had stated that it now only took 1 hr. 5 mins. That showed a difference of only 12 mins. ; but Lord Blantyre happened to know that that was much less acceleration than the tide was capable of, because he lived opposite to a part of the river which was still a wilderness of waters—a chaos—a negation of all engineering principles.

The jetties recommended by John Golborne had been removed. The longitudinal, or parallel, or connecting, dyke of John Rennie—which had never been completed—had been left for years standing, for a length of more than 3 miles, much above half-tide high, in the middle of the river—though on one side of the channel—unconnected anywhere with the land—inviting the tides to pass up on one side of it and return by the other, a result which probably only extensive dredging in the channel had hitherto prevented taking place. The works of the late James Walker had not been commenced. The dredging of the old channel, planned by John Rennie in 1807—but executed narrower at Dunglas Castle than he advised, for the channel was only 400 ft. wide there at present—was all that had been done for some miles above Dumbarton rock; but so long as the trade could make its way to Glasgow the inhabitants of that city need not to care.

The great trade of Glasgow was no more proof that the river had been improved than the overland trade from China to Russia was a proof that Central Asia afforded good and peaceable roads for caravans. It might be noticed every day that trade overcame all obstacles; nothing could prevent it going where it was wanted.

Lord Blantyre would now turn to the second proposition which he had adduced. In 1840, the late James Walker was asked the following question in Committee:—"How long would it take to carry out the widening and deepening of the River Clyde according to his plans?" He answered:—"It would take fifteen years with our present plant." More than twice fifteen years had passed; the plant had been greatly increased, and yet a considerable part of Mr. Walker's plans had not even been commenced, and there was no certainty that they would soon, or, indeed, ever be carried out. The Trust, composed exclusively of inhabitants of Glasgow, expended the funds in works in and near Glasgow. Lord Blantyre considered that the river dues should be separated from the harbour dues, and spent exclusively on the river, and that the Trust should be opened to representatives from the adjoining counties and the nation. The consumer really paid the rates of river and harbour; so a great part of Scotland was a contributor to those funds, and might take part in seeing them properly applied. It was not the

general interest of the country that was now studied, but the particular interest of Glasgow. The inhabitants of Glasgow seemed to grudge everything spent upon the river, but nothing which was spent upon their harbour and dock works; and as the monies levied from the public might be expended upon those works to any extent, it was obvious that the river would never be likely to be improved throughout its entire course by trustees chosen as at present.

Mr. JAMES ABERNETHY said, the subject brought forward in the Paper was one which he considered to be of Imperial importance, inasmuch as it referred to the improvement of one of those great public water highways—the tidal and navigable rivers of the United Kingdom. He used the term ‘public highways,’ because he had long been of opinion that all works tending to impede the free tidal flow of navigable river currents, and which were often constructed to serve mere private ends, were most serious interferences with the public interests.

Amongst the various navigable tidal rivers of Great Britain the Clyde stood prominently forward as an example of a river improved by following out—what he considered—a sound engineering principle, namely, that of bringing the river into a state of equilibrium by the construction of works to create a current proportionate to the size and form of the channel, and the nature of its bed. All the engineers employed on the Clyde—Smeaton, Golborne, Watt, Telford, Rennie, and Walker—had acted upon the principle of increasing the tidal volume, and prolonging its flow into the upper reaches of the river, by dredging and by filling up indents which tended to create eddies and arrest the free flow of the current. In the first instance jetties were projected from the foreshore, with a view to equalise the sectional area of the river. Although by accretion between those jetties the parallelism of the river banks was to a certain extent insured, yet the flowing and ebbing currents, impinging upon the ends and sides of the jetties, created great irregularities in the bed of the river; and consequently, more recently, the system of parallel training walls had been adopted. That, with the addition of dredging, had to a great extent improved the river Clyde. He thought the result in the case of that river, and also of the Tyne, demonstrated most clearly that the formation and conservation of the navigable channels of tidal rivers were dependent upon the tidal ebb and flow, and not upon the natural fresh water stream of the river or the occasional effects of floods or freshes. That theory was borne out in the case of rivers where an opposite system had been pursued, such as the

Dee and the Nene, where works had been carried out by which the quantity of tidal water had been diminished—the natural discharge remaining in its normal state dependent on the water-sheds, which were defined and constant. He was quite aware that, for some years past, the theory had been broached that the maintenance of the channels of navigable rivers was to a great extent dependent upon the action of freshes, and that it was possible to maintain their depth by occasional discharges, through sluices in dams near their entrances, at or near the period of low water. Now, he contended that it was impossible to maintain the entrance channels of rivers by a stream, whatever its velocity might be, which did not possess the hydrostatic element of weight, or an equivalent to the ebb and flow of a tidal column constantly passing up and down, with a scouring power due to its velocity and depth. Even supposing that by such a system, under certain peculiar circumstances, it was possible to maintain an entrance channel of a certain capacity, still, at the same time, it would entirely bar all future improvement of the river generally. The bed of the river would inevitably gradually rise by the deposit brought down from the upper reaches of the river by floods or freshes, which could not be removed from the lower reaches without a sufficient tidal volume on the ebb to carry it out to sea. He would advert to some remarks made by Mr. Bateman. One was that the Clyde had been improved more than any other river, and that the dredging had been carried out to an extent unparalleled, and at less cost for labour than in the case of any other river in the United Kingdom. Mr. Abernethy was not prepared to admit that. As regarded the Tyne, the improvements within a comparatively short period had been much greater. It must be borne in mind that the active operations in the Clyde had occupied a period of twenty-eight years, during which 14,000,000 cubic yards of material had been removed by dredging. In the case of the Tyne, in nine years, or less than one-third of the time, 15,000,000 cubic yards had been removed, and there was now a gradually inclined bed from Newcastle to the sea; the bar which formerly existed was gone, and in all probability would not again be formed. He could not help thinking that there was some truth in Lord Blantyre's statements as to delay.

The Clyde Trustees were about to commence the construction of the Stobcross Dock. Mr. Abernethy recollected visiting the site of that dock twenty years ago, when it was first projected by Mr. Walker. If it was to cost the sum stated, namely, £1,163,000 for a water area of 30 acres, it would certainly be a very expensive and unremunerative dock.

Captain E. K. CALVER, R.N., F.R.S., said, the Author introduced his Paper with the following words:—"Probably for no river in the kingdom has so much been done 'by art and man's device' as for the river Clyde, above Port Glasgow." Captain Calver thought, however, there was an exception to that statement to be made in favour of the Tyne. He would give one or two facts in support of that view. In the Clyde, between the years 1837 and 1873, the high water interval between Port Glasgow and Glasgow had been reduced from 1 hr. 23 mins. to 1 hr. 5 mins., a gain in time of 18 mins. in thirty-six years; whereas in the Tyne, between 1860 and 1872, the interval had been shortened between Shields and Newcastle from 1 hr. 3 mins. to 23 mins., or a gain in time of 40 mins. in twelve years. Again, in the Clyde, between 1758 and 1873, an interval of one hundred and fifteen years, the low-water level at Glasgow had been lowered 8 ft.; whereas in the Tyne, from 1860 to 1872, an interval of twelve years only, the level at Newcastle had been lowered 3 ft. 6 in., being now 4 in. below the level of low water at Shields. The points of comparison were 18 miles apart on the Clyde, and 10 miles apart on the Tyne. He brought forward those several facts in order to put in an appearance on behalf of the Tyne, and that credit might be given where credit was due.

It was mentioned in the Paper that Mr. Walker found spring tides at Glasgow to rise 7 ft. or 8 ft., and neap tides at the same place to rise 4 ft.; while at the present time springs rose 10 ft. 6 in., and neaps 9 ft. 3 in.; but those were at periods long after the river was put into a state of improvement. It had been progressively acted upon for one hundred years at least, but no clue whatever was given as to a comparison of the level of high water at Glasgow with the river in its natural state and in its improved state. It was no unusual thing to find that, while lowering the low-water bed by improvement works, the high-water surface was lowered also. Several examples of that might be given, but Captain Calver would only refer to one within his late experience; and that was the case of the Ouse at Lynn. Those present would be aware that the old channel of the Ouse had been forsaken, and that for it had been substituted a cut 3 miles long across Bentineck Marshes, below the town of Lynn. It was originally intended to have a cut 10 miles long, but only 3 miles of it had been carried out. In 1853, while writing a treatise on the conservation and improvement of tidal rivers,¹ and while considering the probable friction of the proposed narrow channel, he predicted that the tide would not rise so

¹ "The Conservation and Improvement of Tidal Rivers, considered principally with reference to their tidal and fluvial powers." 8vo. London, 1853.

high in the upper reaches of the Ouse when the proposed cut was carried out, and that opinion has been sustained by the result. He made a survey of Lynn Deep in 1871, and he included the rivers to as far as the towns of Lynn and Boston, and to the towers of Wisbeach channel. From the want of reliable data, he had no means of determining how far the high-water level had been affected by the improvement; but, even as far back as 1855, he received information that the tide did not rise so high. He also made it his business five years ago to make further inquiries, and the universal testimony was that the tide did not rise so high as formerly. Though he could not ascertain what was the exact lowering of the surface, he had made some observations which went far to confirm the general fact of reduction in height. In 1871, for instance, in dead neaps, the tide rose 9 ft. 1 in. in Lynn Road, and 9 ft. 5 in. at Lynn Dock, or 4 in. higher at Lynn than it did at the sea; whereas at high springs in Lynn Road it rose 23 ft. 3 in., and at Lynn Dock 22 ft. 5 in., or 10 in. less at Lynn than at the sea. It would, therefore, be perceived that, whereas the high-water level of neaps was 4 in. higher at Lynn than at the sea, the spring high-water level, owing to the short high-water interval, was 10 in. lower; showing clearly that the friction of the narrow cut had a retardative effect in conveying the culminating level of the tide upwards. As a similar effect may have followed on the Clyde from similar works, it was desirable that the Author should supply the Institution with a comparison between the level of high water at Glasgow in the natural state of the river and what it now was. The point was essentially a practical one, and important as well; for, however much the low-water surface might have been lowered for improvement, it was clear that, if the high-water surface was lowered at the same time, it would, to that extent, be a reduction in the whole navigable gain.

Mr. W. A. Brooks said, the last survey of the mouth of the Tyne made by Captain Calver showed a depth of only 17 ft. at low water of spring tides. Mr. Brooks understood Mr. Abernethy to say that the bar was removed. If that was the case it was a happy circumstance; but Mr. Brooks doubted the fact. He would ask Captain Calver to state what was the actual depth, and whether there was no bar?

Captain CALVER replied that, he made a survey of the Tyne last year, in preparation for a contest with which the Commissioners were threatened, and he found that there was, literally, no bar, there being a depth of 27 ft. right in from the sea into nearly as far as Shields Narrows. In fact there was deeper

water about the region of the bar than there was in the fair river channel.

Sir JOHN COODE said, it had been critically remarked that the Paper was too historical. To his mind if it had not been historical it would have been nothing; for he failed to see how it would have been possible to convey the facts contained in it without reference to history and dates. The history was like a chain binding the whole of the material facts into one connected whole. The proposition of the late Mr. Rennie, made in 1799, to join up the ends of the several jetties, was the first instance of the adoption of the system of longitudinal training walls, recently carried out with so much success on the Tyne and elsewhere. The Author had remarked that the disappearance of the salmon from the river Clyde was mainly due to the great amount of the traffic; but, above all, he said, to the sewage and other matters poured into the river. With regard to the traffic, Sir John Coode was inclined to question that it had that effect, for he believed he was right in saying in the Tyne the salmon had increased with the river improvements and the remarkable growth of traffic. He mentioned that because, in some rivers, where the value of the salmon fisheries formed an important element of consideration, opposition might be raised to river improvements on the ground of injury to the salmon. Such an opposition had occurred in his own experience, and therefore he should like to know whether it was capable of being shown that the "whirl" of the paddle, the "churn" of the screw" had exercised an injurious effect upon the salmon in the Clyde? With regard to the sewage, he did not know whether the salmon was a dainty-feeding fish; but at Richmond they might see fishermen congregated in considerable numbers around the sewer outlets; from which it might safely be concluded that there were some fish which certainly did not object to sewage. He thought the disappearance of salmon from this river was principally owing to the deleterious matters discharged into it from the various manufactories on the Clyde.

In his opinion the Appendix to the Paper constituted the most valuable part of the document. There were no less than fifteen tables contained in it, comprising a great amount of valuable practical information. The details as regards the dredging would be more valuable if the Author would furnish the average distance to which the material was conveyed, as also the cost of removing the boulders per cubic yard, and that of the blasting of the rock per cubic yard. Those were facts which Sir John Coode confessed he should like to see introduced, in order that they might be

placed on record. In future operations of that kind, on the rocky portions of beds of rivers, great progress was to be looked for from the use of the steam drill and dynamite, or some one of the other compounds of nitro-glycerine. He had used the steam drill, but not dynamite, because he had been unable to obtain it on account of the stringent restrictions by which its conveyance was surrounded. He considered that they were on the eve of a great change in respect to the cost of submarine blasting operations, and he concurred with the Author that much would hereafter be effected by the use of the drill and by blasting with dynamite. But Sir John Coode would go further, and would say a great deal might, and he believed would, be done without the drill. He had tried experiments with gun-cotton, and he had succeeded in removing 4 tons of hard rock by each 1 lb. of compressed gun-cotton exploded. That would be a good result with drilling, but on the occasion alluded to the gun-cotton was simply placed in canisters upon the surface of the rock, and was exploded with a head of water over it of 8 ft. or 10 ft. He hoped the Author would supplement his Paper by adding a few facts with regard to the cost of the blasting operations on the Clyde.

Mr. J. T. HARRISON said, he did not come prepared to take part in the discussion, but he was induced to say a word or two in reference to what had fallen from Mr. Abernethy, who had said the improvement of the river Clyde was a favourable specimen of the effect of giving free action to the tide, for the purpose of scouring and keeping the river clear from shoals. If Mr. Harrison read the Paper rightly, the Author had stated that a great portion of the material dredged was due, not simply to effecting the deepening of the river, but to removing the accumulation which took place in the river after it had been dredged. Mr. Harrison did not find that in the statistics of the Paper any separation had been made of this accumulation from the material excavated for the purpose of deepening. That was rather an important matter in considering the question from the point of view which Lord Blantyre had taken. His lordship stated that, beyond the part so much improved, there was a considerable length of the river over which the tide flowed at comparatively slow velocity. If there was an accumulation of sand there, the effect of the tidal action would be constantly to remove some of that sand, and to deposit it in the upper reach of the river; hence the tidal action would have the effect of constantly silting up the river. If the dredging was discontinued, in course of time the river would return to its former normal condition. This seemed to point to the desirability of improving the river lower down, toward

Dumbarton, where the depth and width required for the navigation were maintained by nature, without any assistance from art, and of removing the materials which the tidal action would carry up the river. Mr. Harrison would be glad if the Author would state what was the quantity of material which the Clyde Trustees had yearly to excavate, in order to maintain the depth which had been obtained. Mr. Harrison had no doubt as to the desirability of deepening, straightening, and confining within river walls or embankments the channel of the Clyde, as described in the Paper, but in his opinion the training walls should be carried above high-water mark; nor did he doubt the advantage of extending the navigable channel above Glasgow Bridge, by the removal of the dam as proposed. Considering the large proportion of deposit to new material dredged out of the Clyde in 1870-71, namely, 345,209 cubic yards deposit, to 558,895 cubic yards of new material—it seemed that very much was required to be done before the Clyde could be considered a satisfactory instance of engineering skill assisting nature to improve a navigable river. The object of the Engineer should be, not merely to form a deep, regular, navigable channel, the result of a large expenditure in rude excavation, and the erection of river walls judiciously directed, but to minimise the deposit in the channel after it was so formed.

There were two sources from which the material forming this deposit might be derived. The first source was the denudation of the river basin, the *débris* from which was carried down by the river proper during floods. The second source was from sand banks formed at the lower part of the navigable channel—derived partly from the *débris* from the river basin, and partly, it might be, from the shingle beaches of the adjacent estuary—material from which was carried upward by the tidal action. There was no information given in the Paper as to the relative supply from those sources. Something might be done to arrest the silting up, by trapping the material brought down before it reached the tidal portion of the river, and, if so trapped, it might be removed at probably less cost than it could be dredged from the navigable channel. The river, in its natural state, was just able to carry all the land detritus to the deep water of the estuary. If left to itself, it would gradually silt up and return to its normal condition. He did not think that the tidal river, as improved, was more able to carry detritus to the sea than it was before its improvement was effected; very probably it was less able to do so. At the same time, such works as had been carried out on the Clyde were well calculated to improve the channel in the lower part of the

river, and to deepen the water over the bar, when such an obstruction existed. The sand banks above Dumbarton were essentially similar in character to the Hurd sand at the mouth of the Tyne, and it would be necessary to construct piers to the deep water, or to continue the deep artificial channel to the naturally deep water, before the quantity of material annually dredged was minimised, or the utmost assistance was given to nature by the art of man.

The velocity of the tidal wave was dependent on the depth of water through which it was transmitted—the greater the depth the greater would be the velocity of the wave, or the shorter the interval of time of high water from point to point. But the greater the depth of water, the less also would be the velocity of the water which transmitted a given wave. When the water was very shallow, a bore was formed, as in the Severn and other rivers, and the velocity of the water was nearly as great as that of the wave. He had little doubt but the tidal wave of the Clyde, checked in its progress by the sand banks above Dumbarton, made those sand banks quick, and carried with it a considerable quantity of sand in suspension, and that when the flood tidal water reached the deep-water channel, whilst the velocity of the wave was greatly increased, the velocity of the water transmitting it was much less than it was below, across the sand banks. With such diminished velocity there must be a tendency to deposit the material in suspension some little distance above the shoals, and onward, with an intervening deep. If those views were correct, then there would probably be in the Clyde two points of maximum deposit; one at a short distance below the dam at Glasgow, with an intervening deep, and the other in the part of the channel he had previously suggested.

Mr. SHELFORD said, the Author had given the observations taken upon one spring tide, when there was no fresh in the river. Those showed that high-water mark reached a level at Glasgow 14 in. higher than at Port Glasgow, while the low-water level was about the same at both places. One circumstance had been omitted in the Paper, namely, there was in the upper part of the tidal stream, above Glasgow, a masonry dam across the river—placed there to keep back the fresh water—which prevented the tide from ascending the river channel beyond that point. From his experience and observation, Mr. Shelford considered that dam caused to a great extent, if not entirely, the super-elevation of high-water mark at that part above sea level, and it also accounted for the fact that, when there was no fresh in the river, there was a low level of the low-water mark. He was induced to form that opinion,

because when many years ago he was engaged with Mr. John Fowler, Past-President Inst. C.E., on the Nene, a tidal dam was placed across the river, twelve miles above the mouth, and the effect of that was just what Mr. Shelford had described in the case of the Clyde. The high water was raised by the dam 2 ft. above sea level, and there was a considerable depression of low water. When the dam was subsequently removed, and the tide had free 'swing,' the high-water mark was lowered nearly 2 ft., and the low-water level was considerably elevated, though he could not give the exact amount.

Mr. G. R. STEPHENSON said, some points had been mentioned which were not in accordance with his views. Having had considerable experience of the Clyde, he had no hesitation in saying that it had been improved more than any other river in the country. He agreed that great credit was due to the Trustees and Engineers who, from time to time, had had charge of the improvements. They had converted it from a ditch into a magnificent channel which would admit any sized vessels trading in Great Britain. Ironclads of the largest calibre and merchant ships of the largest class had been built and launched from its banks. Persons going there at the present time would see ships passing each other at nearly full speed, with ample depth of water, where, twenty years ago, the river was only 1 ft. or 2 ft. deep. He therefore maintained that no river in this country had been so well dealt with or so much improved as the Clyde.

In his comparisons between the Tyne and the Clyde, Captain Calver had forgotten one point: he had omitted to state that it was a much easier matter to convey the sea level 9 miles inland, as in the case of the Tyne, than to take it 25 miles or 30 miles inland, as in the case of the Clyde. With regard to the Tyne, Mr. Stephenson had no hesitation in saying its engineering treatment had been one of the greatest mistakes ever made upon any river in Great Britain. He would briefly state his reasons for that assertion, and in illustration would refer to certain circumstances connected with the river Nene. Many years ago, he recollected a gentleman came to him and asked him to take charge of some works for the improvement of the upland section of that river. The works were a few miles below Northampton, and they had been undertaken with the object of draining that part of the country. Having heard the views of the projectors, Mr. Stephenson expressed his opinion "that it would be best to begin below before they attempted to throw the flood land water towards Wisbeach, where the river was very contracted; and that, if the works were begun above that town—

as they wanted to do—Wisbeach Harbour and its shipping might be washed away by land floods." The period to which he referred was long before the improvement of the lower Nene had been attempted. As he found they did not wish the necessary works to be executed in the lower portion of the river, the matter rested in abeyance. Some years afterwards the work of improving the river was commenced at Wisbeach and carried upwards, and the upland improvement had also been executed. It had proved beneficial both to drainage and navigation.

The mode of dealing with the Tyne was wrong, inasmuch as the works had been begun above the stricture at 'The Narrows,' and consequently a sufficient volume of tide could not be got up the river to keep it scoured; hence the great cost for dredging. With regard to Lynn, he did not know whether Captain Calver meant that the new cut was a success or a failure; because, if regarded as a failure, it was inconsistent with the facts. The late Mr. Robert Stephenson, Past-President Inst. C.E., and himself were the responsible engineers of that work; and during the time he was there—which was from the commencement to the conclusion—the sea level of high water was brought to Lynn, the low-water level was lowered 6 ft., and the bed of the river deepened, so that vessels floated there at low water, with about 12 ft. of water under them. Previously to that work being carried out vessels grounded in the harbour. It was an admitted fact that the works at Lynn to which he referred had been one of the greatest successes obtained in a fen country.

With reference to the bar at Shields, so long as the dredging was kept up the bar would be kept under. In his remarks on the Tyne, Captain Calver had not mentioned 'The Narrows.' Mr. Stephenson would say that was one of the great mistakes in the Tyne. There were, in fact, two great mistakes. The first was the sea-walls or piers. The second was in the order of beginning the work above 'The Narrows.' The Tyne authorities had been spending enormous sums in dredging the channel, to contain a volume of water which could not be got up the river. He meant that, so long as 'The Narrows' existed, the tidal flow could not get up the river to fill the channel. The improvement should have been commenced at 'The Narrows,' and the channel widened upwards. Sea-walls or piers had been built at the sea, and what was called a 'harbour of refuge' had been made, but it might more correctly be termed a 'harbour of destruction,' for it had its opening to the strongest winds that came from the sea. So long as those walls existed so long would that fault remain; and, further, the dredging would always have to be continued, as the river would never maintain itself.

Mr. R. C. RAPIER wished to ask the Author his opinion with regard to the weir above Glasgow Bridge. The Clyde authorities by retaining it were preventing the tide rising in the river above it. They were thus shutting up a large tidal area and, consequently, losing a volume of water, which might have swept out the river, at every ebb and flow of the tide. Mr. Rapier had had that point brought before his notice lately with reference to the Orwell at Ipswich—a magnificent estuary, for which nature had done everything, and man had done very little. The greatest facilities existed for increasing its very modest depth of 18 ft. to 24 ft., and that was the utmost he thought could be obtained. Mr. J. F. Bateman, V.P. Inst. C.E., in a report on that subject, had taken into consideration the probable loss of the tidal water which would result from shutting off what was called the ‘upper river’ at a point where the estuary ceased. Part of the project was to use the ‘upper river’ as a feeder to keep the upper dock full. The area proposed to be cut off from tidal influence was little as compared with that of the whole estuary. As regarded the dam on the Clyde, Mr. Rapier would ask the Author what amount of water area there was above the dam, and whether the level of Glasgow Green was sufficiently above that part of the river to be secure from inundation from high tides—and what would be the probable additional tidal area there if that dam were removed? If that area was great, the increased scour of the river by the natural efflux and reflux of the tide would be greatly better than the occasional watershed of a heavy rain. Mr. Rapier would add, that Hydronomical Engineers had an immense field before them. Within a recent period, he had had brought prominently to his notice the fact, that several of the magnificent rivers of China required but a small expenditure to obtain the most splendid results from their great natural capabilities.

Mr. D. T. FENDER, through the Secretary, said that, having been employed under Mr. J. G. C. C. Godsmen, M. Inst. C.E., in observing and discussing the levels, tides, and soundings of the estuary of the river Nene, he had been led to consider the failure of recent attempts to improve the upper portion of that estuary, as a striking example of the necessity which existed for maintaining a proper and symmetrical co-relation between the form of the upper and lower portions of any tidal estuary, or channel proposed to be improved. General investigations as regarded other tidal rivers had also induced him to believe that any abnormal depth for the convenience of navigation or for the berthage of shipping could only be maintained by a costly expenditure for excavation.

The progressive development of the derivative tidal wave of the Clyde presented certain features of interest to the Hydronomical Engineer. Entering the Irish Channel between Rathlin Island and the Mull of Cantyre, the tidal wave turned round the Mull toward Ailsa Craig, thence up the Firth of Clyde to the Cumbray Islands, where it divided into two main branches, one flowing in conjunction with the tidal stream eastward of the Island of Arran up Loch Fyne, the other continuing its course past the Cumbray Islands toward Cloch Point, where it again subdivided, turning eastward up the estuary of the Clyde and northward up Loch Long. At the Mull of Cantyre the range of ordinary spring tides was 4 ft.; at the Cumbray Islands, it was 10 ft., and at Greenock, it was $9\frac{3}{4}$ ft. In Loch Long the range was 12 ft., and at Inverary (Loch Fyne), it was 10 ft.¹ The velocity of the tidal wave, to the Cumbray Islands, was about 55 miles per hour, and from thence to Greenock, 70 miles per hour. To Inverary it was at least 70 miles per hour; and measuring the distance round the western side of the Island of Arran—that being the direction of the main stream—it was 80 miles per hour. The mean velocity in the upper portion of Loch Fyne between East Loch Tarbert and Inverary was increased to more than three times that rate, or to about 250 miles per hour.

He had bestowed much study upon the question “as to the best theoretical form for the self-conservation of a tidal channel,” and he believed it to be that in which the cross-sectional area uniformly decreased in the inverse ratio of the square of the distance from the tidal mouth or entrance. In estuaries approximating to that shape, if a capacity diagram was constructed, in which the several cross-sectional areas were represented by ordinates, and the respective distances by abscissæ, it would be found that the outline of the curve joining the ordinates would resemble a half-parabola. Where that form of channel existed, there was uniformity of development both in the flux and reflux of the tidal wave.

The entrance section or mouth of the tidal channel of the Clyde might be described to be between Garvel Point, about a mile above Greenock, and the southernmost point of Ardmore Head, and its natural termination—under existing conditions—somewhere about the west end of Newshot Isle. From thence to Glasgow the river might be considered as a tidal canal. It was therefore below the west end of Newshot Isle that the form of channel he had alluded to as theoretically the best might be expected to be found. To

¹ “Tide Tables for the British and Irish Ports, for the year 1873.” Published by order of the Lords Commissioners of the Admiralty. Page 151.

ascertain how far such a form existed, he had plotted a few cross sections from the Admiralty charts,¹ and had compiled an approximate capacity diagram. At the entrance the sectional area was about 17,000 square yards at high water, ordinary springs. At the west end of Newshot Isle, the sectional area was 800 square yards, also at high water, ordinary springs. At Dumbarton rock, situated nearly midway between those two sections, there was a cross-sectional area of about 4,400 square yards at high water, ordinary springs. The sectional areas at other points along the channel were also nearly in inverse ratio to the square of the distance from the tidal entrance. So far as the capacity of that portion of the Clyde at high water was concerned—and excepting the irregularity of cross-sectional profile occasioned by the parallel dykes—its channel might be considered to be in a fair condition for the rapid flux and reflux of the tidal wave.

From the tide observations furnished by the Author, it appeared that high water traveled from Port Glasgow to Garmoyle Light at a velocity of little more than 11 miles per hour. Between Garmoyle Light and Dumbuck Light the velocity was increased to 24 miles per hour; and between Dumbuck Light and Bowling to $78\frac{3}{4}$ miles per hour. Between Bowling and Dalmuir the velocity was suddenly reduced to about $6\frac{3}{4}$ miles per hour; thence to Renfrew the wave traveled at the rate of 30 miles per hour, and from Renfrew to Glasgow at the rate of nearly 26 miles per hour. The mean velocity with which high water traveled from Port Glasgow to Glasgow was only a little more than 16 miles per hour. Mr. Fender had previously stated that seaward of Greenock, the velocity was about 70 miles per hour. The reduction of the rate to less than a fourth of that velocity would indicate the retardative effect of the sand banks and other obstructions to the free tidal flow. The remarkable increase in the velocity between Port Glasgow and Bowling afforded an example of the general law of increase of velocity in the upper portions of tapering estuaries. It might be worth while to draw attention to the fact that that increase was closely in proportion to the square of the distances of the several stations above Port Glasgow. The observations further showed that between Port Glasgow and Garmoyle Light the velocities at quarter-flood, half-flood, and three-quarter-flood, were respectively 22 miles, 13·4 miles, and 10·3 miles per hour. While thus there was a decrease of velocity towards high water between those two stations, there was an increase of from 5·5 miles to 6 miles to

¹ These charts are partly corrected to 1871.—D. T. F.
[1872-73. N.S.]

7·7 miles per hour between Garmoyle Light and Dumbuck Light, at quarter-flood, half-flood, and three-quarter-flood respectively, and from 5·5 miles to 8·9 miles to 20·9 miles per hour between Dumbuck Light and Bowling at the same times. It was also deserving of notice that half-flood occurred at Glasgow about 20 mins. before it did at Renfrew.

The general conclusions which might be drawn from the previously stated facts were as follows :—1, that not only was there a tendency to augment the range but also to increase the velocity with which high water traveled along the upper portions of gradually tapering estuaries; 2, that when the bed of the channel was very steep, and the narrowing took place rapidly, that increase of range and velocity might be rather attributed to the reduplication of the tidal wave from obstructed momentum, than from any suitability of the configuration of the channel for its upward propagation; 3, that the more nearly the gradual lessening of the cross-sectional area approached to an uniform curve the greater would be the possible range and the actual velocity.

It was usually found that when the form of an estuary decreased uniformly in sectional area from its entrance to its tidal limit, a line joining the summit level of the successive high waters would slope seawards; that where obstructions existed suddenly diminishing the sectional area, that slope would be diminished above the obstructions; until, in extreme cases—as that of the Nene—a considerable landward inclination might take place. Such, he believed, would, to a certain extent, be the case in the Clyde were it not for the existence of the weir at Glasgow. At present it was probable that it heaped up the tidal water, and thus augmented the range of tide in its immediate vicinity. If he was correct in that surmise, its removal, in the present state of the channel below Bowling, would probably occasion a depression of the high-water level in the harbour of Glasgow.

Mr. DEAS, in reply, said, he thought he could explain in a few words how the allegations which had been made by Lord Blantyre had been brought about. His lordship was very desirous that, instead of the dredgings being carried out to sea, which was done at a cost of $5\frac{1}{2}d.$ per cubic yard, they should be put upon his land, at a cost to the Clyde Trustees varying from $10d.$ to $1s. 6d.$ per cubic yard. The Trustees very wisely resolved to continue to carry the material out to sea instead of putting it upon his lordship's land. Lord Blantyre then took legal proceedings to enforce his request. The case came before the Court of Session, who decided in favour of the Trustees. Lord

Blantyre appealed to the House of Lords, where he was again unsuccessful in securing legal support to his demand, and that circumstance, to a certain extent, accounted for his lordship's communication to the Institution. With reference to the remark that the portion of the river referred to was not so well improved as it was higher up, to a certain extent that was true; but the stream was much larger and much deeper there than it was higher up, and the object the Trustees had in view was to get it as deep high up as they possibly could—in fact it would be better if it was deeper at Glasgow than it was in the vicinity of his lordship's property, in consequence of the difference in time of tide. Another difficulty there, was a hard patch of gravel concreted together which was very tedious to dredge.

With reference to the remarks of Captain Calver as to the acceleration of tide on the Tyne as compared with the Clyde, Mr. Deas thought Mr. Robert Stephenson's observations had disposed of them. The Clyde was really a hundred years ago a ditch. He did not know that the Tyne was ever a ditch six miles above the sea, but Glasgow was twenty-two miles from deep water.¹

With regard to the Stobercross Docks, on which some reflections had been made, he had mentioned in his Paper the reasons why those docks were only now being carried out. Until very lately the Trustees were able to obtain ground along both margins of the river for quay extension, and the river was a dock made to their hands. It was only when that ground was exhausted that they turned their attention to making docks out of dry land.

Reference had been made by Sir John Coode to the cost of conveying the dredged material by punts. Mr. Deas would state that the cost of conveyance was so small an item in the total cost of dredging that it was scarcely appreciable. In Table XI. of the Appendix he had given the detailed cost of towing the punts by tug steamer. In 1870–71 there were three places to which the material was carried, and the cost of towing was 2·88*d.*, 1·76*d.*, and 2·34*d.* per cubic yard. The distance which the material was conveyed did not much affect the cost. In some cases the distance the material was carried was 1 mile to 2 miles, in others 7 miles to 8 miles. None of it was taken 27 miles; 6 miles would be a fair average distance.

With regard to the remarks which had been made about the weir at Glasgow, it would be satisfactory, no doubt, to the Members to be informed that it was doomed, and the Clyde Trustees were only waiting for a supply of water to be brought from a higher

reach of the river—for the use of those manufacturers who at present pumped their supplies direct from the river immediately above the weir—to have it removed. He might remark that it was maintained for the water supply of Glasgow before the present supply was brought to Glasgow by the works designed by Mr. Bateman. In fact, the Trustees had a Bill at present before Parliament to get the time within which the weir must be removed fixed at not exceeding four years. By that time it was hoped it would be removed, and that the Clyde would have the benefit of the additional tidal water, which would wash down the river, and add to its velocity.

As to the comparative quantity of deposit and new material dredged, it was stated in the Paper that it varied from year to year. The rainy weather of last year brought down a very large amount of deposit, and it was easily distinguished by the masters of the dredgers from new material. Last year the total quantity dredged was 992,354 cubic yards, of which 300,000 cubic yards were considered to be deposit from the higher reaches of the river and from the city sewers. With regard to the Tyne, he complimented its Engineer, Mr. J. F. Ure, M. Inst. C.E., on the amount of dredging done in that river. They were enabled to excavate more, but there were not the same interruptions to the work that there were in the narrower channel of the Clyde.

In answer to questions as regarded the successive levels of the flood, and of the ebb, of the spring tide of the 11th of April, 1872—given in the tidal diagrams (Plates 22 and 23), and in Table I. of the Appendix—Mr. Deas stated that, previously to the tide observations being made from which the diagrams and tables were compiled, the levels of the zeros of the tide gauges had been determined by a careful series of levels which could be depended upon as correct. The relative depression of the successive surface levels of the ebb tide at the Renfrew gauge—as shown by the diagram (Plate 23)—agreed with the tide observer's book, and the gauge had since been checked with the Ordnance bench mark, and found to be in accordance with the diagram. Mr. Deas had no means of connecting the tide observations taken under his orders with those which had been formerly observed under the directions of Mr. J. Scott Russell, M. Inst. C.E.

The following computations—from the data given in the Appendix¹—showed the velocity of the tide in the different portions of the river on the 11th of April, 1872; and they might be con-

¹ *Vide ante*, p. 154.

trasted with the computations of the tidal velocity which had been previously given by Lord Blantyre and Mr. D. T. Fender :—

	h. m.
High water at Port Glasgow	2 35
„ „ at Garmoyle	2 55
Tide rose about $3\frac{3}{4}$ miles in	<u>0 20</u>

or at the rate of $11\frac{1}{4}$ miles per hour.

High water at Garmoyle	2 55
„ „ at Dumbuck	3 00
Tide rose about 2 miles in	<u>0 05</u>

or at the rate of 24 miles per hour.

High water at Dumbuck	3 00
„ „ at Bowling	3 02
Tide rose about $2\frac{1}{2}$ miles in	<u>0 02</u>

or at the rate of 70 miles per hour.

High water at Bowling	3 02
„ „ at Dalmuir	3 25
Tide rose about $2\frac{1}{2}$ miles in	<u>0 23</u>

or at the rate of $6\frac{1}{2}$ miles per hour.

High water at Dalmuir	3 25
„ „ at Renfrew Ferry	3 30
Tide rose about $2\frac{1}{2}$ miles in	<u>0 05</u>

or at the rate of 30 miles per hour.

High water at Renfrew Ferry	3 30
„ „ at Glasgow	3 40
Tide rose about $4\frac{1}{4}$ miles in	<u>0 10</u>

or at the rate of $25\frac{1}{2}$ miles per hour.

High water at Port Glasgow	2 35
„ „ at Glasgow	3 40
Tide rose about $17\frac{1}{2}$ miles in	<u>1 05</u>

or at the rate of 16·15 miles per hour.

On the 10th of September, 1835, according to observations made by Mr. Logan:—

	h. m.
High water at Port Glasgow was at	2 02
„ „ at Garmoyle	2 30
Tide rose about $3\frac{1}{4}$ miles in	<u>0 28</u>

or at the rate of 8 miles per hour.

High water at Garmoyle	2 30
„ „ at Bowling	2 43
Tide rose $4\frac{1}{2}$ miles in	<u>0 13</u>

or at the rate of $41\frac{1}{2}$ miles per hour.

High water at Bowling	2 43
„ „ at Renfrew Ferry	3 12
Tide rose 5 miles in	<u>0 29</u>

or at the rate of $10\frac{1}{3}$ miles per hour.

High water at Renfrew Ferry	3 12
„ „ at the Broomielaw	3 50
Tide rose 5 miles in	<u>0 38</u>

or at the rate of 7·9 miles per hour.

High water at Port Glasgow	2 02
„ „ at the Broomielaw	3 50
Tide rose $18\frac{1}{4}$ miles in	<u>1 48</u>

or at the rate of 10·14 miles per hour.

The longitudinal section (Plate 20) would supply the means of comparison between the high water level at Glasgow before and since the river had been improved. It had been prepared from the most reliable data that Mr. Deas could obtain in the archives of the Clyde Trust, and the portion of it relating to the last thirty-five years might be thoroughly depended upon.

Since the Paper had been prepared, a series of cross sections had been carefully taken under his direction—at intervals of about 400 ft. apart—from Port Glasgow to Glasgow. The datum line of those cross sections had been fixed by levelings carried along both banks

of the river continuously from Glasgow Bridge to Port Glasgow, and those levelings had been verified on all the Ordnance bench marks within reach. The following sectional areas in square feet at different points in the river, which had been prepared from those cross sections, would show clearly the character of the channel, and help to illustrate—and it might be to qualify—several of the remarks made in the course of the discussion :—

SECTIONAL AREAS.

Distance in Miles from Glasgow Bridge.	Area in Square Feet at Low Water.	Area in Square Feet at High Water.	Distance in Miles from Glasgow Bridge.	Area in Square Feet at Low Water.	Area in Square Feet at High Water.
3	3,900	7,500	9	7,700	14,300
4	3,900	7,500	10	5,900	16,700
5	4,200	8,000	11	5,600	17,200
6	4,300	8,200	12	5,300	22,600
7	4,700	9,400	13	7,300	35,400
8	6,900	14,200	14	10,700	55,000

The distance in miles from Glasgow Bridge was shown in Plate 19. At Dumbarton Castle, 14 miles from Glasgow, the narrow channel might be said to terminate, and the estuary of the Clyde to commence.

In answer to the inquiry of Sir John Coode, Mr. Deas stated that he had no data as to the cost of removing boulders. Searching for them by sweeping and by diving-bell occupied much time—varying according to the strata in which they were found—and the time occupied in lifting and disposing of them varied also so much according to the localities in which they were found, that any data that he could give on that point would be apt to be fallacious. Not much rock had been removed since he had entered upon the charge of the works. His immediate predecessor, Mr. Duncan, had given the cost as 44s. per cubic yard.

In reply to Mr. J. T. Harrison, Mr. Deas stated that all the training walls lately constructed had been carried several feet above high water mark, and in answer to the questions which had been put by Members in reference to the weir across the river above the harbour of Glasgow, he would state that the height of the crest of the weir was about 2 ft. below average high water of spring tides, and when the river was unaffected by freshes, the depth of water passing over the coping was about 11 in.

From observations made in 1865, by Messrs. Leslie and Duncan, during equinoctial spring tides—with the weather calm, and the river unaffected by freshes—it appeared that the tide rose 2 ft. 10 in. above the cope of the weir, and it was found that the level of the water was raised or affected as far as Eastfield Dye Works, about $4\frac{1}{2}$ miles above the weir; high water there occurring at 4 h. 15 m. P.M. The high water of the same tide in the harbour of Glasgow was at 3 h. 10 m. P.M.; and high water rose 18 in. higher at the Eastfield Dye Works than in the harbour. The average of the lowest neap tides rose to about 12 in. above the crest of the weir.

In a report “On the proposed removal of the weir,” presented to the Clyde Trustees on the 24th of February, 1865, by Messrs. Leslie and Duncan, they stated that by measurements of cross sections of the river above the weir taken under their directions, the probable quantity of additional water that would pass up and down each tide, were the weir removed, would amount to rather less than 15,000,000 cubic feet—a quantity equivalent to an area of 42 acres covered with 8 ft. depth of water, that being the average rise of the tide in the harbour at that period. They further stated that that additional tidal water would be obtained with the river bed as it then existed, and that the quantity would go on increasing as the bed deepened and the low water level fell. The level of Glasgow Green was sufficiently high to be secure against inundations from high tides.