Discussion.

Mr. E. Woods, President, said that Mr. Webster's Paper had given a concise *resumé* of much that had appeared scattered throughout various periodicals, and especially in the Minutes of Proceedings of the Institution. By the kindness of the inventors and appliers of the different systems, the members had had the opportunity of seeing a number of interesting models, on the table, on the landing, and in the library. They also had the benefit of the experience of the Author with regard to the cost of executing work by the different systems, and the time within which such work could be effected.

Mr. JOHN J. WEBSTER desired, before the discussion commenced, to direct attention to one or two points. In the first part of the Paper there were two important considerations which were only casually mentioned. The first was, how far, in the case of a bar at the mouth of a river or estuary, the operation of dredging alone would be successful, the bar of the Mersey being suggested as an illustration; and the second was the question of the disposal of the dredgings—what would be the effect of discharging the dredged material in the tideway of an estuary or river, such as the Mersey or the Humber. He wished also to mention that there were several machines and dredging apparatus which he had not described in the Paper, but as they were arrangements of one type, he did not think it necessary to do so; and as some of these were among the models exhibited, the members would have an opportunity of seeing the special features of each machine.

Mr. L. F. VERNON-HARCOURT said that the Author in his Paper had dealt with two distinct subjects: firstly, where dredging should be applied; and secondly, what kind of dredger should be used for different kinds of work. He had opened the subject with the question of scour, as compared with dredging, and Mr. Vernon-Harcourt supposed every one would acknowledge that, where scour could be obtained, dredging ought not to be used. The Author had also referred to the case of the River Mississippi, at the mouth of which (though it was not mentioned in the Paper) dredging was first attempted and proved a perfect failure, but afterwards, as was well known, training-walls or jetties were put in, which enabled the bar to be swept away by the natural scour of the

[THE INST. C.E. VOL. LXXXIX.]

D

Mr. Vernon-
Harcourt.

river. The Author had alluded to Dublin Harbour, where the South and North Walls were built for removing the bar; but in that case dredging was to a certain extent employed inside those walls, thereby increasing the natural tidal capacity there, and therefore improving the scour at their extremities. One instance in which dredging had been very little used was the improvement of the tidal Seine. There training-walls had been almost exclusively used, and dredging was only employed here and there where there were very hard shoals. In fact, where there was silt, it was very rarely that dredging could be employed to any great extent alone, and training by banks became necessary. But in the case of very hard shoals, it was quite possible that no natural scour would remove them, and then the dredger came in as an important auxiliary. Still there were some cases where fine sand and even silt had been removed from tidal rivers by dredgers. He referred to the well-known instances of the Tyne and the Clyde, and also the Tees. In these cases, however, dredging would always be required for maintaining the depth. At the present time, on the Clyde, more than 700,000 cubic yards of material had to be dredged out of the channel annually to maintain the existing depth; and this quantity would increase rapidly with every increase in depth. Accordingly, these rivers could only be regarded as artificially deepened and maintained by dredging though their channels had been fixed and partially scoured, on the Clyde and the Tees, by aid of training-walls, and carried across the bars at the mouths of the Tyne and the Tees by converging breakwaters. There were, however, two cases where it might have seemed more hopeless to dredge than those, namely, at the entrances of Dunkirk and Calais harbours, where dredging was carried on practically on the seashore beyond the mouth of the harbour and beyond the jetties, which continued the harbour entrance across the foreshore, and greatly improved the depth, and consequently the access to these ports for vessels of greater draught. He had an opportunity three or four years ago of going on board one of those dredgers outside Calais Harbour. The entrance outside was being deepened by means of sand-pump dredgers; and, as the Author mentioned, a great deal of water was brought up with sand; but the lift was small. It was impossible to quite fill the hopper itself; but there, by raising the doors or flaps on the top at each side of the hopper, the sides of the hopper could be raised above the deck of the vessel, and the water escaped through the interstices between the flaps, whilst the sand settled in the hopper. The Author had then mentioned a matter which was a very disputed point, with refer

ence to the Liverpool bar, whether dredging could possibly be of any use in improving that bar. Hitherto, fortunately, that bar had not been sufficiently an impediment to vessels to require any work to be undertaken; but it was possible that in lapse of time the bar might rise to a higher level, and in that case it would be a question whether dredging or training-works should be employed for lowering it. He believed it had been suggested to attempt dredging upon it; but it was a long way out in the bay towards the sea, and he knew that in the opinion of many of the best judges it was impracticable to dredge there. It might almost have been considered that this was so if it were not for the cases of Dunkirk and Calais, where dredging was really successfully carried on out in the sea itself; therefore, it might be worth trying, if the means were at hand, whether it would be possible, not perhaps to lower the bar to any great extent, but at least to direct the channel, or the changes of the channel across the bar by dredging upon it. But he should think that for any very marked improvement in that respect, it would also be necessary to execute training-works. With regard to the bucket-ladder dredger, the Author mentioned that it was the best machine for regular work, and he thought the experience on the Tyne, the Clyde, and the Tees, showed that that was correct. He felt more convinced of that by knowing that bucket-ladders had been used, not merely in water, but also on the land, in the form of excavators. He recollected seeing, on one of his visits to Havre, the Tancarville Canal being excavated by one of these bucket-ladder excavators. The disadvantage of that type of dredger was that it could not excavate in a very great depth of water, and that it was not very convenient for excavating in ground with boulders in it, or where there was a considerable variation in depth. In such cases, some of the other forms which the Author had described seemed more suitable for the purpose; but certainly for continuous dredging where it was straightforward, as in deepening a river like the Clyde or the Tyne, the bucket-ladder seemed to have the chief advantage. Priestman's, Coles', and Fouracres' dredgers were convenient types for excavating in docks, where the available space was limited, and the dredger could not be frequently shifting its position. These dip, or grapple dredgers, were also very advantageous for lifting masses of rock in varying depths of water, such as the *débris* left by the Hell Gate explosions; but, with the exception of Gatmell's, and Bruce and Batho's dredgers, they were not well suited for excavating in stiff material. The sand-pump dredger was especially advantageous out in the sea, where the waves would prevent

Mr. Vernon-Harcourt.

Mr. Vernon-Harcourt. a bucket-ladder dredger being used, but where the sand-pump dredger was able to work without inconvenience when there was a swell of 2 or 3 feet. Towards the close of the Paper, the Author had given a variety of prices for dredging operations, and mentioned some with regard to the price per ton, and others per cubic yard. He thought it would be a great advantage always to give both the price per ton and per cubic yard, because the work to be executed depended on the weight to be raised, whereas the excavation effected had naturally to be measured by cubic yards; and it was very desirable therefore in every case that the comparison should be known between the tons and the cubic yards in these dredging operations, and that every item of cost should be included in the prices given.

Mr. Campbell-Thompson. **Mr. J. CAMPBELL-THOMPSON** remarked that the Author had stated, with regard to grab and bucket dredgers, that they were practically entirely "dependent upon the force of the blow in falling, and the weight of the apparatus, for the penetration and grip of the material." His firm, in undertaking the construction of that class of machinery, had been struck by that fact. In the present system of grab and bucket dredgers originated by Messrs. Priestman, the opening chain was actuated by block-gear, that was by a varying weight upon a vertical frame taking up the slack of the opening chain. Of course the efficiency of the grab in regard to its fall upon the material was not exactly the same as in the case of the use of hydraulic power, but that efficiency must be minus the amount of the weight in the block-gear. The Author had also referred to the wear and tear of the opening chains and mouthpiece. The wear and tear of the opening chains was somewhat dependent upon that peculiar form of block-gear. The chain was of the open-link kind, and it was gripped by a sprocket-wheel. His firm, instead of using the block-gear, used an auxiliary winch, by means of which the whole power of the crane and engine could be brought upon the opening chain in case of the grab being fast under water. With regard to the Ball sand-pump, his firm had constructed one some years ago, and it was tested in his works upon gravel taken from outside Spurn Point, of which the gauge was between 2 inches and 4 inches; it was also tested with $\frac{5}{8}$ -inch nuts, and some pieces of galvanized iron. It lifted them all satisfactorily to a height of 4 feet, and ejected them at a height of 7 feet above the level of the tank in which they were placed.

Mr. Priestman. **Mr. W. D. PRIESTMAN** observed that he had not intended to compare one particular class of dredger with another had not **Mr.**

Campbell-Thompson found fault with one or two details of the Priestman dredger. That was not the place to discuss details, but rather the general principles of the machines, leaving inventors to prove the advantage of their own special machines in the dock, in the harbour, or in the canal. It was only fair to say that Messrs. Rose, Downs and Thompson had just printed a catalogue, in which they had given a description of the Priestman dredger, which, to say the least, was misleading. They had given a drawing of the weight and had put upon it "1 ton." There certainly had been weights of 1 ton and more, and there had also been weights vastly less. To an ordinary reader it would appear that in lifting the grab it was necessary to have the energy of 1 ton against the closing of the grab, but practically it was the reverse of that. There had been that weight, and larger weights in some cases, but with four, six, eight, and in some cases ten strands of chain, it was as four, six, eight or ten to one, or whatever it might be and thus the force exerted against the closing of the grab was brought to a minimum. But it was not even actually as bad as that, because with every machine sent away a working instruction book was supplied, and if the machine was worked as the book directed there was no difficulty whatever about it. There was not 1 lb. weight against the closing of the grab, inasmuch as a certain amount of slack chain was provided, so that the grab never felt the opening chain until it was completely closed. The Author had at first a little misled him, because he had stated that the closing chain and the bucket lips were subjected to considerable wear. Feeling rather sensitive on the point, owing to what had appeared in the above-mentioned catalogue, he had thought that the Author was referring to the opening chain. Mr. Campbell-Thompson had referred to the closing chain as working with a sprocket-wheel and therefore having wear and tear upon it. The closing chain, however, did not work with a sprocket-wheel. Messrs. Rose, Downs and Thompson were in the habit of putting upon their buckets and grabs closing chains similar to those used in the Priestman dredger, upon which the Author said there was a good deal of wear and tear. He hoped that makers of dredging apparatus would accept the Author's suggestions, and endeavour to devise a contrivance which would prevent some of the wear and tear upon the closing chains. One of the difficulties mentioned in connection with the use of buckets and grabs was the hardness of the material. Messrs. Priestman Brothers had some arrangements for making the grab penetrate in a way that it would not do in ordinary working, but whether any object was to be gained

Mr. Priestman.

Mr. Priestman. in putting on what were termed poles with a clasp to keep the grab down until it was completely closed, was a question that he was not then prepared to argue. He did not think it had been tested sufficiently to affirm that much good was to be got from it. The Author had suggested that with Priestman buckets hard material could not be lifted. He had the Author's permission to say that he was not referring to the grabs, but strictly to the buckets. The machines with which he had been connected, one in Liverpool and one in Hull, were bucket dredgers, not grab dredgers. Of course they did not expect bucket dredgers to lift hard material. He had permission to read a short paragraph in a communication from Mr. Marillier to the Author of the Paper, as to the recent working of the Hull dredger previously mentioned in a communication from Mr. Marillier to the Institution.¹ Referring to that particular dredger to which he had since added a grab, he said, "The efficiency of these grabs is not at all dependent upon the force of the blow in falling for the penetration and grip in the material, as they do their work very satisfactorily, even when lowered quite gently on to the material to be dug out, the jaws being so framed as to draw down and penetrate the material as soon as an upward strain is put on the lifting chain. Even in hard material the jaws penetrate so thoroughly as to cause the bucket to be well filled. The grab is found to work successfully in excavating hard clay from its natural bed on dry land." There had been many cases in which they had had to lift hard material, at Sunderland, Portrush, Sligo, Girvan Harbour, the new Tower Bridge, and Blackfriars Bridge, and the Priestman dredger had been employed by the Thames Conservancy in lifting Thames ballast. It had also been used in many other places where the material had been described as "stiff clay," "exceedingly hard sand," "hard ground," "hard gravel and clay." It was evident that hard material could be worked when the right tool was used. No reference had been made in the Paper to the advantages of the grab dredger for lifting blasted rock. Messrs. Priestman Brothers had employed two or three machines, at the London and St. Katharine Docks, for lifting material that approached blasted rock—very strong concrete—and they had performed the work very successfully. In places like Blythe Harbour, Limerick, and other harbours, a good deal had been done in that kind of work, and during the last few days they had received an order from the representative of Count De Lesseps for the Panama Canal—an

¹ Minutes of Proceedings Inst. C.E. vol. lxy. p. 310.

order that had been given in consequence of the successful lifting Mr. Priestman, of material at the new gateway to the London and St. Katharine Dock. With regard to water there could be no doubt that bucket dredgers lifted a much smaller proportion than other kinds of dredgers. When they first set their machines to work in the Hull Docks, one complaint which was made was, "We have got the mud into the hopper-barges, but it will not run out." The engineer said that was a good fault, and he would soon put it right. Of course by adopting a more acute angle the mud was soon made to run out. That, he thought, was a practical proof that the dip-bucket type of dredger lifted material with a smaller percentage of water than many other dredgers.

Mr. A. BROWN said while he did not wish to go into the merits Mr. Brown. of the older type of the bucket-ladder dredger, he would direct attention to two modern types illustrated by Plate 3, Figs. 1, 2, 3 and 4. One was the dredger "Melbourne" (Plate 3, Figs. 1 and 2), built for the Melbourne Harbour Trust. He believed it was the most powerful ladder barge-loading dredger afloat, and it had done a great deal of work in cutting the new entrance to Melbourne Harbour. It lifted about 800 tons of material an hour, and on one occasion raised 400 tons in twenty minutes. It was, therefore, a tool that he thought the dip-bucket maker would be rather astonished to see working. Each of the buckets held 22 cubic feet of soil, and twenty of them could be run per minute. The gearing was very strong. Steel was extensively used in those modern dredgers. Thirty years ago, when cast-iron gearing was used, there were many breakdowns. In the first six months of a new dredger, it was sometimes stopped for many days with wheels breaking and gearing going adrift. That was the case no longer. The "Melbourne" had several important improvements, including very powerful mooring-winches. It was most essential for a dredger of this kind to have a powerful feed. It was like the case of a large lathe or slotting-machine; unless there was a sufficient feed to fill the buckets and pull them up to the face, the machine would not do its work efficiently. In early years on the Clyde mooring-winches were very small, and the dredgers did not do much work. In the case of the "Melbourne," for the first six months there was not a single breakage, everything went on smoothly. It had two sets of engines with which it steamed out to Australia. The other dredger, the "Dolphin" (Plate 3, Figs. 3 and 4), was built for the Crown Agents of the Colonies for work at Castries Harbour, St. Lucia. Besides cutting its own way, it could dredge to a depth of 32 feet of water. The "Melbourne" could dredge to

Mr. Brown. a depth of 37 feet. The buckets of the "Dolphin" had a capacity of 8 cubic feet, and were all made of steel. Buckets were formerly riveted to a great extent, which was very costly, but that practice was now almost done away with. Steel backs with the links cast and bushed with plenty of bearing-surface to rest upon the tumbler, lasted a long time. He thought that the Melbourne Harbour Trust and the Crown Agents were to be congratulated on having such good tools, which had been built under the direction of Sir John Coode. The tumblers were all steel or chilled cast-iron. There was a five-sided tumbler on the top, and a hexagon tumbler on the bottom. Reference had been made by the Author to the weight of the bucket-chain. No doubt it appeared cumbersome and slow, but a bucket-chain like the one illustrated was nearly in equilibrium, the hang on the lower side of the ladder ought to counterbalance the range on the upper side, so that, in reality, the soil was the principal weight to be lifted to the top. Another machine mentioned by the Author was the hopper-dredger, belonging to the Mersey Dock Board, constructed by Messrs. Simons and Co., which had four Priestman cranes. It was, he believed, a good vessel, and did its work very well while dredging inside the docks. Formerly the exhaust steam escaped into the air, but in the machine in question it was led by copper pipes down to the surface-condenser of the main engine. In that way the decks were kept clear of water from condensed steam. He thought that an improvement had also been made on the main pillar of the cranes, by extending them down to catch the bottom of the boat and the side of the hopper. The vessel was complete, and fit to go anywhere. The crew, consisting of twenty-one men, worked night and day, taking out a load each tide. The next type mentioned by the Author was a bucket-ladder hopper-dredger, in which the soil was discharged into a hopper in the vessel itself. There had been over two dozen vessels of this kind built, of from 200 to 1,400 tons capacity. The first two were built for the Canadian Government. A small one of 200 tons steamed from the Clyde to Halifax in eighteen days. The Government kept these vessels employed at various ports in the Gulf of St. Lawrence, on the coast of Nova Scotia, and in the Bay of Fundy. One large combined vessel went to Otago, New Zealand, to cut the bar there (Plate 3, Fig. 5). It dredged to 35 feet depth of water, and did its work at 25 per cent. less per ton than the work done by a large double-ladder dredger attended by steam hoppers. It conveyed the stuff 13 or 14 miles down the river, while the spoil of the double-ladder dredger was taken 2 or 3 miles off.

The cost with the stationary ladder dredger was 1s. 7d. per cubic Mr. Brown. yard, and with the combined vessel 1s. 2d., notwithstanding the greater distance the material was transported by the latter vessel. Recently a somewhat similar vessel was made for the Corporation of Bristol. It was a stern-well hopper-dredger. It had four screws, two at each end, and was driven by a line of shafting extending through the ship. There were two sets of triple expansion engines working at 150 lbs. The vessel was steered at either end, and the captain (an old hand on some of the passenger boats) said that he had never been on a boat that steered better. The Author had stated that these vessels could not carry the soil a long distance; but the vessel at Bristol took the material from Cumberland Basin, 30 miles down the Bristol Channel, and came back again, within ten hours. Of course there was detention in getting into the docks and down the river, the channel being very narrow. This vessel was now working at the Portishead docks; it took out a load every tide, or eleven loads in a week. The working crew was thirteen men during the day and six men extra at night. The vessel was wholly made of steel of the highest quality, something like that used for locomotive fire-boxes, and all the gearing had been most conveniently arranged. As showing the efficiency and power of the modern bucket-ladder dredger, it might be mentioned that while one was employed deepening a channel at Cardiff, under the direction of Mr. John McConnochie, M. Inst. C.E., it raised from the bed of the River Taff several large oak trees without receiving the slightest damage, and at Hartlepool another dredger of this type cut its way through a breastwork of oak piles. As an instance of the cost of dredging operations by the bucket-ladder type, the case of the hopper-dredger "Forth" might be given. This vessel was owned by the Caledonian Railway Company, and was employed on the River Forth at Grangemouth. It loaded its hoppers with 800 tons of spoil in two and a half hours, conveyed and discharged the same 18 miles off in two and a half hours, then returned to Grangemouth, where it had to wait three hours on the tide, Grangemouth being a tidal harbour. When working double tides with six additional hands to the usual day crew, or nineteen hands in all, it could dredge and transport eleven loads, or 8,800 tons at a cost of 1·3d. per ton for wages and stores. Again, as another instance of efficiency as well as economy, he might cite the hopper-dredgers "No. 3" and "No. 4" (Plate 3, Fig. 6), which during the past summer and winter had been engaged cutting a new channel in Belfast Lough. These vessels while working night and day, from

Mr. Brown. 6 A.M. on Monday till noon on Saturday, had each dredged, and transported 10 miles to sea, twenty-five to twenty-six loads of material, or a total quantity by both dredgers of about 40,000 tons in one week. The consumption of coal while dredging was about $\frac{1}{2}$ ton for every 1,000 tons of material raised. Fourteen hands in all formed the usual day crew of each vessel. In connection with dredgers of this type, an important improvement was the "traversing bucket ladder," which enabled the dredgers to cut their own flotation through shoals and banks. The ladder was supported on a fore-and-aft horizontal framing, upon which it was moved to project in advance of the dredger and make the necessary excavations. In conclusion, as economy and expedition were the chief points to be aimed at in connection with dredging operations, it was necessary, in order to come under the former heading, that the machine employed should be capable of working in any kind of ground, and not a specialty that could work in a certain kind of soil only, for this would be likely to prove other than an economical tool.

Sir John
Coode.

Sir JOHN COODE, K.C.M.G., Vice-President, said that the "Melbourne" worked in very stiff material, and was altogether a very satisfactory craft. The smaller vessel "Dolphin" at St. Lucia, was dredging in coral, and doing very good work indeed. He wished, however, to call attention to another kind of dredger. He thought that engineers would continue to use different kinds of dredgers, according to the material to be dealt with and the surrounding conditions. The craft to which he wished to refer was, he thought, the most perfect sand-pump dredger that had yet been made. He first saw a little vessel of this kind at the mouth of the Maas. It obviated one great difficulty in regard to the delivery into the hopper, and the prevention of the material running overboard. There was a suction-pipe long enough to enable sand to be raised from a depth of 30 feet. The connection was by a flexible joint formed of a steel coil and leather. But the great peculiarity was that by means of a centrifugal pump, placed against the bulkhead in the after part of the vessel, the sand and water were delivered together into a horizontal "breeches" piece leading into two pipes running along the full length of the hopper. The difficulty in preventing the sand from running overboard was entirely obviated by its being propelled by the pump through the pipes, the bottoms of which were perforated by a series of holes. Not only were there holes in the bottoms of the pipes, but here and there there were a few small flap-doors, by means of which the men were able to regulate

the discharge. On being tested, the craft, which had been specially built under his direction, had pumped what he thought he might call the extraordinary quantity of 400 tons of sand in twenty-two minutes. Two trials were made. In one instance, the hopper which contained 400 tons was filled with sand in nineteen minutes, and in the second trial in twenty-five minutes, the mean being twenty-two. If the hopper had had a capacity of 1,000 tons, or rather more, it would have been filled within an hour. That was an amount of work which no sand-pump dredger that he had ever met with had been able to accomplish. There were several of a smaller class, ten or a dozen of them having been working successfully at the mouth of the Maas for the last seven or eight years. They worked there with an undulation of from 2 to 3 feet. The rapidity with which the whole thing was done was marvellous. The vessel was scarcely made fast to her moorings before the engine was at work, and the hopper was being filled. As a very perfect machine of its kind, it was he thought well worthy the attention of any member who had sand-dredging on a large scale to perform. There was a dip in the coamings around the well-hopper, and when the hopper was full the water ran overboard in a steady stream on either side. The proportion of sand was about 20 per cent., but it varied very much, as the men could not regulate the suction-pipe with absolute uniformity. All the vessels of that kind were made by Messrs. Smit of Kinderdijk, near Rotterdam, who had performed their contract as faithfully as Mr. Brown and his firm had performed theirs, giving entire satisfaction. The vessel, the model of which he had placed on the table, had steamed to South Africa, and was now at work there. It was only right to explain that the "Melbourne" dredger, built for the Melbourne Harbour Commissioners, and the "Dolphin," for the Government of St. Lucia, to the order of the Crown Agents for the Colonies, both referred to by Mr. Brown, as also the sand-pump hopper dredger "Lucy," the model of which he had just exhibited, built for the Cape Government by Messrs. Smit, to the order of the Agent-General for that Colony, were constructed in accordance with drawings and detailed specifications prepared for him by Mr. W. Matthews, M. Inst. C.E., and Mr. W. Wingate, under whose supervision they were severally built and tested.

Mr. HARRISON HAYTER, Vice-President, said the present appliances for raising material from under water, referred to in the Paper, were of three kinds, the bucket-ladder dredger, the sand-pump, and the grab-dredger. Each of these had its own special

Sir John
Coode.

Mr. Hayter.

Mr. Hayter. uses. The bucket-ladder dredger was adapted for dredging on an extensive scale in open situations, and where there was full scope for operating. The sand-pump was adapted for lifting sand only and depositing it directly on shore or in barges, and was an economical machine when so employed. It could not be used for raising silt to be deposited in barges, as this material when pumped, mixed as it would be with water, and therefore held in suspension, took too long a time to settle in the barge. The sand-pump also was not suited to shape ground to accurate forms, levels, and slopes. The grab dredger, which was now extensively employed, would not dredge clay of any tenacity. Neither would it dredge gravel unless very loose, and the sand and stones uncemented, which was seldom the case under water; nor, he believed, was it as a rule adapted to dredge sand difficult of penetration. It was not suited for dredging on a large scale. Its average performance, instead of being about one lift in one minute was, in practice, more nearly one lift in two minutes; it should not work at a more rapid rate, otherwise there would be excessive wear and tear. The grab machine would, however, dredge very soft clay, silt, mud, also shingle and loose gravel. Thus, in the Inventions Exhibition of 1885, at South Kensington, a grab dredger was to be seen working experimentally in lifting loose gravel from a heap and depositing it on an adjoining heap. It was specially applicable for removing deposits arising from silting in confined situations, such as docks, also at the foot of and close against vertical walls, in lock or passage chambers, and in excavating from the inside of cylinders when sinking them, provided the material was of the nature he had described. Mr. William Matthews, M. Inst. C.E., had recently superimposed upon the grab a cast-iron cylindrical weight that would fit into the cylinder to be sunk, and from which the material had to be removed; iron arms were attached to the grab to scrape the material from the side of the cylinder. In this way the penetrating power of the grab would be increased, and all the material would be excavated by the grab itself. The greater weight would render it necessary to employ a more powerful crane; but he believed, if the contrivance answered, the utility of the grab machine would be enhanced.

The Author had given some very low rates of the cost of dredging; but when it was said that dredging could be done at prices equivalent to from 1*d.* to 3*d.* a cubic yard, it must mean that the material could be taken up and placed in barges or deposited direct on to adjoining land at such rates. The grab

machine could not raise material at so low a rate as either the Mr. Hayter bucket-ladder dredger or the sand-pump; for whilst the action of the latter two was continuous, and the quantity raised large, that of the former was intermittent, and the quantity comparatively small. Some of the other prices appeared insufficient. Thus, the Author, obtaining his information from evidence given at an inquiry, said, "On the Tees, at Stockton and Middlesbrough, the cost of dredging sand, gravel, and occasionally boulders, including the conveyance of the deposit out to sea, a distance of about 12 miles, is 4·96*d.* a cubic yard," and that "this amount includes everything except interest of capital expended on dredging plant." Mr. Hayter could not accept such a statement without explanation. In dredging or removing by sand-pumps the sand between the North Sea piers of the Amsterdam Ship Canal, called Ymuiden Harbour,¹ the average prime cost of the plant alone was three times the rate of 4·96*d.* a cubic yard. He admitted that this was a high figure for plant, and that in dredging in the River Tees, the operation being spread over many years, the cost of plant would be reduced to a minimum. But the dredging in Holland extended over a considerable period of time, and the material was conveyed to sea a distance of not much more than 1 mile, instead of 12 miles, partly by river and partly by sea, in the case of the Tees. To this price per cubic yard for plant alone had to be added the cost of dredging, transport, superintendence, risk, insurance, depreciation, profit (if done by a contractor) and interest. The cost at Ymuiden Harbour could not have amounted in the aggregate to less than from 2*s.* 9*d.* to 3*s.* a cubic yard. In both cases mentioned, the material raised having to be deposited in the open sea, the number of working days would be about the same, namely, some one hundred and fifty days a year. This necessarily added materially to the expense of dredging, and when conditions were more favourable, the cost of dredging would be less than at Ymuiden Harbour. Messrs. Hawkshaw Son and Hayter had just let dredging, by competitive tenders, at 1*s.* 6*d.* per cubic yard, the material being silt, to be conveyed to sea about 1 mile; but within a sheltered area, so that the dredging could be carried on uninterruptedly. Under not dissimilar conditions, dredging, let also by competitive tenders, but where the material was harder, had been done at 2*s.* a cubic

¹ Minutes of Proceedings Inst. C.E. vol. lxii. p. 23.

Mr. Hayter. yard. They had arranged with a contractor to execute a large quantity of dredging at 1s. 8d. a cubic yard, the material being favourable, but which had to be filled into and conveyed in barges, and removed therefrom on to land on the frontage. In fact, the price of dredging would, as a rule, fluctuate from somewhat under 1s. 6d. to 3s. a cubic yard according to circumstances, if the material was not rock. Hence such a price as 4·96d. a cubic yard, the rate at which it was alleged dredging was done in the Tees, including all items of expenditure excepting interest on the outlay for plant, and similar rates referred to, could not, he believed, embrace all the charges he had enumerated. He would draw attention to a contrivance by Mr. Whitaker, of Horsforth, near Leeds, having for its object the conversion of an ordinary steam-crane into a steam-excavator, by attaching a bucket fitted with arms, by a pin to near the centre, or to the lower part of the jib of the crane, and using the crane itself to operate the bucket. This machine could, if placed on a barge, be employed as a dredger for shallow depths. By taking out the pin and releasing the bucket, the crane was left to be used as such. Thus a crane could, for a trifling sum of money, be utilized as a machine for raising material.

Mr. Stothert. Mr. J. L. STOTHERT said that four years ago it became his duty, as one of the judges at the Tynemouth Exhibition, to examine the dredging appliances, and the unanimous conclusion was that Messrs. Priestman Brothers' apparatus was much in advance of the others. It did more work, and it seemed in every respect a very desirable tool. Since then nothing had occurred to alter his opinion. He stated this notwithstanding that he was a member of a firm that had a special dredger of its own. There was, however, he considered, one defect in the Priestman apparatus, which was that it demanded a specially constructed crane to work it, so that contractors, unless they purchased the entire apparatus, could not employ the Priestman system. Now, all contractors had steam-cranes, and hence efforts had been lately directed to scheming a grab, which could be worked by an ordinary steam-crane, with a single chain (Fig. 1). This had been successfully accomplished by a Mr. Wild who patented his invention, which had been purchased by Messrs. Stothert and Pitt, and had been largely manufactured. This grab worked entirely with a single chain. He would not say it was quite as good as the Priestman, but it was not far behind it. Some comparisons had been instituted between bucket-ladder dredging-machines and grabs; but he did not think that such comparisons ought to be made. The functions of the two machines

were essentially different. No engineer would attempt to remove Mr. Stothert. the bar of a river by means of grabs; neither would he endeavour to deepen its bed with such a tool. He would naturally use a bucket-ladder dredger. There were, however, many places in which grabs could be used with great advantage; in positions, for example, where it would be impossible to employ a large dredger, such as in small docks, in pockets close to banks, and especially in

FIG. 1.

WILD'S SINGLE-CHAIN HALF-TINE GRAB.

Capacity $\frac{1}{2}$ cubic yard.

Scale $\frac{1}{4}$ inch = 1 foot.

cylinder-sinking. Mr. Hayter had referred to the method adopted by Mr. W. Matthews for sinking cylinders, or rather for clearing out the material inside. The machine to which Mr. Hayter referred had been made by Messrs. Stothert and Pitt, forming a part of a plant ordered by Sir John Coode for Castries Harbour. Upon experimenting with an ordinary grab, a rather curious condition of things was observed with respect to sinking. On penetrating the soil to a certain depth the ground was found as it were "nested,"

Mr. Stothert.

FIG. 2.

FIG. 3.

FIG. 4.

and nothing would induce the grab to sink lower, and Mr. Matthews Mr. Stothert. thought that an additional set of external tines might possibly get over this difficulty. A new grab having been made with this modification, and also with a large increase of weight, all the parts being of steel, it descended to any required depth with ease, the outside tines loosening the ground effectually, whilst the inside bucket or tines picked up the material (Figs. 2, 3 and 4). The grabs thus made were set to work at Castries Harbour, no difficulties were experienced, and the cylinders were found to descend with the greatest ease. This class of machine would certainly not compare in respect to work done with large dredgers, but still they did a very considerable amount. They had been employed, for example, at Felixstowe Harbour, where two of them of $\frac{1}{2}$ -cubic yard capacity had removed 140,000 cubic yards of material. The excavation was from 8 to 24 feet below low-water, and the cost small. In that position it would have been impossible to use any other apparatus, as there was no room to work a large dredger. This form of grab had also proved extremely valuable as an adjunct to large block-setting titans, in preparing the foundation for the blocks themselves, and had a range equal to the overhang of the main machine. He thought a large advance was now being made in their use. Messrs. Stothert and Pitt had just supplied two cranes and grabs to a steam hopper-barge. This vessel was designed by Mr. James McConnochie for the Bombay Harbour Trust, and was fitted with the most modern machinery, twin screws, high- and low-pressure steam-engines and all the usual working appliances. In the centre of the boat was a hopper with a capacity of 500 tons; fore and aft of this were two 10-ton steam-cranes, each operating on a grab having a capacity of 40 cubic feet. In practice Mr. McConnochie had found they brought up 50 per cent. more than the stipulated quantity, so that each of the grabs would lift rather more than 3 tons at a time. An expert driver, it was stated, would be able to make sixty lifts per hour under favourable conditions; this would give 180 tons for each crane, or 360 tons per hour for both, which was certainly very good work; and in less than two hours the hopper would be filled and the vessel ready to go to sea. He thought this particular form of grab would come more largely into operation, and that its size would be increased. Though they might never, possibly, approach bucket-ladder dredgers in amount of work done, still he believed these machines would be more extensively used day by day.

Mr. JOHN LAWSON thought that the members might be interested Mr. Lawson. in knowing what was being done on the River Garonne. The

[THE INST. C.E. VOL. LXXXIX.]

E

Mr. Lawson. French Government decided some time ago to improve the river at Bordeaux and below. At Bordeaux sand had to be removed, and for the purpose ordinary bucket dredgers, and a dredger like that used on the Suez Canal, and on the Danube Regulation Works in Vienna, were employed, as shown by Plate 2, Fig. 8. At the Bec d'Ambès, the junction of the Dordogne and the Garonne, it had been decided to remove part of the island of Cazeaux on a length of about $4\frac{1}{2}$ kilometres, and a width of from 300 to 400 metres. To carry the material excavated out to sea, or below the river, a distance of 50 to 60 kilometres, would, on account of the expense, have been impossible, and it was decided to put it on the left hand side of the river on the site of the new bank. Two systems were adopted for this purpose. First, the centrifugal-pump dredger, called the Dutch dredger, as used on the Amsterdam Canal. Two dredgers of this type were employed, both of which had been built in Holland, and which were fitted with centrifugal pumps made by Mr. John Gwynne of Hammer-smith. The dredger was provided with a 120-HP. engine, a centrifugal pump, a suction pipe, and a delivery pipe. The centrifugal pump drew up through the suction-pipe the stuff excavated with a certain quantity of water, and delivered it through a pipe 20 inches in diameter, and 300 metres long, to a height of 5 metres on the bank of the river. The principal apparatus was fitted at the opening of the suction-pipe on the bed of the river, and consisted of two disks with steel blades, which revolved at the rate of 50 turns per minute. These disks cut and diluted in the water the material to be excavated, which was drawn up through the centrifugal pump. At the Bec d'Ambès it dredged to a depth of 8 metres. The second machine adopted (Plate 3, Fig. 7) was in three parts; First, an excavator running on rails, which worked itself along, and in doing so scooped up the river bank to about a slope of 1 to 1; second, a staging, 350 metres long, which extended from the excavator to the site of the new bank. It consisted of two wrought-iron girders, divided in spans of 40 metres, supported on wrought-iron piers running on rails. On the top of the girders was an endless band 1 metre 20 centimetres wide, carried by rollers placed 1 metre apart; third, an engine on rails placed between the excavator and the staging, which by means of a wire-rope transmission running the whole length of the staging, and of a spur-wheel and worm-gear fitted on each pier, worked the endless band, and pulled the staging and itself along at the same speed as the excavator was doing its work. The excavator scooped up the stuff in buckets, which, when they arrived at the top of the tumbler,

emptied themselves on the endless band; and this, being worked Mr. Lawson. by the engine before mentioned, carried the stuff excavated away, and threw it to spoil 350 metres from where it was taken up. The length of rails under each pier, under the engine and excavator was 300 metres, and as the apparatus worked along, a gang of men behind displaced the rails a little towards the new bank. The excavation was done in lengths of 300 metres; it took four hours to complete one length. On arriving at the end of a length the forward gear was reversed and the whole apparatus worked back again. By this means the engineers had been able to do away with locomotives, trucks, and permanent way, for carrying the excavated material away, and also with labour, which would otherwise have been required for unloading the trucks at the spoil bank. Nothing more was required than to shift the permanent way behind, as the machine was going forward. The works at the Island of Cazeaux were begun in the autumn of 1886, and would occupy the next three or four years.

Mr. WALTER HUNTER considered that the Author had given a Mr. Hunter. very good general account of various descriptions of dredging machinery in use at the present day. He had not expressed very definite opinions with reference to them, and that rendered it difficult to criticise the Paper. He had truly said that if Nature would do the work of natural scouring in the rivers, engineers would never be so foolish as to employ expensive machinery for that class of work. But, fortunately, Nature was not always so kind, and hence the skill and ability of the mechanical engineer were required to bring other forces to bear in carrying out the desired operations. Reference had been made to spoon barges. Some time ago two of them were fitted for the East and West India Docks, and they had done very good work, lifting the material at a cost of about 1*d.* per ton. He had seen the Bazin dredger at work at Lowestoft. It did remarkably good work, delivering sand at a distance of 400 or 500 feet from the dredger. Reference had likewise been made to Duckham's dredger. Any one going by the railway from Millwall Junction to Greenwich, would see, on the left-hand side of the railway, the result of the working of a Duckham dredger in the shape of an immense bank of mud which had been delivered from the docks. The dredger did its work cheaply. To Mr. Duckham also should be given the credit of having first introduced the traversing ladder in dredgers. It was designed in 1875, and constructed under Mr. Duckham's superintendence for the Millwall Dock Company. With regard to bucket-ladder dredgers and the

Mr. Hunter. comparison of the work done by them with that done by the grabs, he thought that Mr. Stothert had put the case very fairly when he said that different kinds of dredgers had their special use in different localities. There was one advantage which it had always seemed to him the bucket dredger had over the usual grab system. The grab system was apt to pit the bottom into a number of holes, whereas the bucket dredger had the advantage, at any rate, of making a perfectly smooth bottom, if it was used properly. In regard to the comparison between the double- and single-ladder dredgers, his experience went to prove that the single-ladder dredgers were more economical in the first cost for a certain amount of material raised. If a single-ladder dredger would lift 500 tons of material per hour, it would cost less than a double dredger, each ladder of which could lift 250 tons per hour. The wear and tear would be less in the single-ladder than in the double-ladder dredger. At the same time with a double-ladder dredger, there was sometimes the advantage in the case of one ladder breaking down, of being able to carry on part of the work with the other. With regard to dredgers generally, he thought that sometimes the gear was overdone in weight; that they had more weight than was absolutely required for the work to be done. A dredger which Messrs. Hunter and English had made for Sir John Coode for Yarmouth, with moderate scantlings, had cost less for repairs than any of which he had ever heard. It had lifted 100,000 tons of material in two seasons, and the total cost for repairs was £20. With regard to hoisting-gear, it had been found during a great many years that the best arrangement was the frictional gearing of Mr. Robertson. It could be put in and out of gear without any trouble. A single lever or screw did it, and if the friction-wheels were not given too much to do, they would wear for a very long time. One thing to be guarded against was that the driving of the wheels should tend to throw the eccentric out of gear, and not draw it in; otherwise there might be a tendency for the shaft to seize in the bearing and cause fracture. With reference to anchors and chains, his opinion was that it was best for the head and stern chains to be worked by separate engines, but the bow and quarter chains were best connected with the main engines. It then resembled a regular self-acting feed like a lathe or slotting-machine. In regard to lifting the materials to an unnecessary height, as suggested by the Author, he had stated that a screw might be placed in a trough a few feet above the deck by which the material might be led from the buckets to any part of the vessel. No doubt that

was true, but a screw working along a shoot in that way imported Mr. Hunter. a vast amount of extra friction. He thought, from experiments he had made, that the advantage gained by lifting to a less height was more than counterbalanced by the extra friction and the extra wear and tear. Reference had been made to the necessity of making dredgers narrow enough to pass through locks. In the "Rother" dredger Messrs. Hunter and English had introduced a novel method of construction. There were two supplemental pieces of hull, which were bolted on to the main hull. When these supplemental pieces were removed the dredger could pass through a lock 13 feet in width. The method adopted gave great stability, and at the same time carried out the requirements of the Rother Level Commissioners. Allusion had been made to the fact that a bucket-ladder dredger would not work easily in shallow water. A dredger made by his firm last year for Spain (Plate 3a, Figs. 1 and 2), floated in 18 inches of water. In order to meet the requirements, the vessel was made of steel plates $\frac{1}{8}$ inch thick; there were longitudinal girders running from end to end of the vessel, and the upward strain of flotation was borne by the transverse bulkheads which ran from side to side. The dredger was 94 feet long by 25 feet beam, and the height of the top tumbler above the water was 25 feet. When it was finished the dredger drew 17 inches. The material was deposited by buckets upon an endless leathern belt which ran over pulleys. The supporting pulleys were somewhat dished in order to keep the material in the middle. That dredger had proved a great success. The dredger was fitted with 12 HP. compound surface-condensing engines, and it took 46 indicated HP. to work it in lifting and delivering 96 cubic metres of compact clay per hour. The contract was that it should excavate 500 cubic metres per day. The working expenses were very small, and upon trial it actually lifted from 80 to 100 cubic metres per hour. Basing the cost upon 500 cubic metres per day, the cost of delivering the material on the bank came to about 1.5*d.* per cubic metre, or 1.16*d.* per cubic yard, or 0.86*d.* per ton, for wages, coals and stores. He thought that was about as economical a result as had ever been obtained in any dredger, especially a small one. He had no doubt that engineers had sometimes found a difficulty in getting rid of some of the material which they had dredged up of the nature of sticky clay. In the case of a bucket which was used at Harwich in 1847, as great difficulty had been experienced in getting rid of the material, the backs of the buckets were made movable in such a way that the material was actually thrown out. He thought that

Mr. Hunter. an arrangement of that sort would be found advantageous when sticky material such as clay gave trouble. Four or five years ago he designed and constructed for Messrs. Lucas and Aird, for the Royal Albert Docks, a land-dredger which worked upon piles—a sort of traveller, in which the method he had mentioned was adopted, and was found to act very well. The dredger delivered about 2 cubic yards of material per minute into the trucks, which were brought along a line of rails. The only difficulty which Messrs. Lucas and Aird had found was that of arranging the rails so that the trucks could be brought in sufficient numbers to take the material raised by the dredger. Allusion had been made to the depth which could be reached by dredging. With the “Tilbury” dredger, constructed for the East and West India Docks Company, it was possible to work to a depth of 46 feet. The dredger was to lift 150 cubic yards per hour, but as a matter of fact it had lifted 1,400 tons in five hours, or 280 tons or 210 cubic yards per hour. The dredger was fitted with a dial-indicator to show the depth at which the buckets were working. In reference to the question of deep dredging, he might mention that Mr. Samuel Williams, one of the Conservators of the Thames, had a dredger named “The Diver,” which he had himself suggested, but the details of which were designed by Messrs. Hunter and English, and which had worked in 60 feet of water. An ingenious arrangement was adopted by which part of the weight of the ladder was balanced. Mr. Williams was also enabled to draw up the ladder, which was a very long one, through the well, and place it upon the deck, so that he was able with a long ladder to use a comparatively short vessel. The unloading machine used by the East and West India Docks Company had been designed by Mr. Manning, their Engineer. There were three rows of piles running along the river, embracing a series of barge beds, and the unloading dredger ran from end to end. The material was lifted by the machine and deposited on the banks at the cost of 1*d.* per cubic yard. The Company had a very complete plant for getting rid of the dredged material.

Mr. Giles. Mr. A. GILES, M.P., said that the Author's statement with regard to the angle of the shoots was contrary to his experience of dredging, namely, “for soft mud, 1 in 10; soft clay, 1 in 12 to 14; hard clay, 1 in 14 to 16, and fine sand in water, 1 in 20 to 25.” He could not conceive it possible that material could run down shoots of such slopes. 1 in 20 was the gradient of a road over a railway-bridge according to Parliamentary practice, and he did not think that even sand with water would run down such

an inclination. According to his own experience, he should say *Mr. Giles*, that a slope varying from 1 to 1 to 1 to 4 would be a more usual one for shoots used in connection with dredging. He thought, too, that there must be some difficulty in arriving at the exact cost of dredging. The cost was so different in different situations that he doubted many of the statements in the Paper. The only safe guide in estimating dredging was to ascertain at what price a contractor would do the work. When there were dredgers belonging to Dock Companies worked by their own staff, it was very natural that the staff should try and make the cost appear as small as possible, but as a rule this cost did not include the purchase nor the depreciation of the plant. *Mr. Hayter* had given a very good example of the cost of plant in the case of the Amsterdam Canal, and when statements were put forward varying from $1\frac{3}{4}d.$ to $24d.$ or $30d.$ per cubic yard in different situations, engineers had not very much guidance in regard to cost. He had some dredging to do forty years ago where the contractor found the plant, and had to dredge silt, gravel, and clay, with a good deal of timber in it, and the contract price for 250,000 cubic yards was $10\frac{1}{4}d.$ per yard, including everything. He believed that the contractor made money out of it. *Mr. Giles* was now carrying out dredging in a similar soil. The material had to be taken 2 miles, and the price, he believed, was $1s. 1d.$ per cubic yard. He would caution engineers generally against adopting, in any Parliamentary estimates, the prices that were put down in the Paper for dredging, because he thought that the evidence given in Parliament would upset them altogether.

Sir Douglas Fox observed that engineers who had to design, and contractors who had to carry out, deep and difficult foundations, could bear testimony to the great assistance which they had received in consequence of the rapid strides made in the inventions described in the Paper. Even within his own experience, the advance had been very great. The facilities now given for carrying down deep and difficult foundations were immense. With reference to sinking cylinders, especially brick cylinders, through sand, he had found the use of a centrifugal pump, like that of Messrs. Gwynne and Co., to be the simplest and most practical mode that could be adopted. A short time ago he had to sink brick cylinders, with wrought-iron cutting edges, of a considerable size to a depth of 45 feet below the bed of a river. The soil was composed of silt, sand, and gravel, with numerous small boulders. In the first instance a Priestman grab like that described in the Paper was tried, and it was found to work exceed-

Sir Douglas
Fox.

ingly well until it came amongst the small boulders, when the stones got between the teeth of the grab, and allowed the silt to escape, so that great difficulty was experienced in lifting the material. Another grab of a different form, but closing in the same way as the Priestman grab, was then tried, and the same difficulty arose, the stones getting between the edges, so that the softer material could not be kept inside the grab. The Gattmell excavator was then adopted, and in that particular class of material it answered admirably. The stones had no chance of impeding its action, and the material was brought up both rapidly and safely. It was necessary, however, to employ a diver from time to time to prevent nesting. If anything of the kind described by Mr. Stothert could be applied to a grab of that sort, it would be a great advantage, because it occasioned great delay and expense to have to put in a diver in the middle of the work. He had lately had some experience in sinking cylinders to a depth of 67 feet through very soft silt, and could confirm what Mr. Hayter had said as to the difficulty of using a grab under those circumstances. Where the silt was very soft, and especially where the cylinders were of comparatively small diameter, it was cheaper to have an air-lock at the top, and to put a man into the cylinder to excavate direct. In that, as in everything else, it was necessary to suit the tool to the practical operation, and certainly where the cylinders had to be sunk through clay, or where the material was free from stones, nothing could exceed the efficiency of the Priestman system. Even in the case of the Gattmell excavator it had been found better when the material was at all hard to substitute teeth for the plain edge at the bottom of the grab.

Mr. Airy. Mr. W. AIRY wished to make a few remarks on the centrifugal sand-pump mentioned by the Author. He had lately had the opportunity, through the courtesy of the Engineer of the Great Eastern Railway Company, of seeing the sand-pump at Lowestoft at work, and he had been much struck by its efficiency in dredging shingle in a sea-way, and also by the skill and judgment with which the pumps and the hopper in the vessel were arranged. The vessel would contain about 300 tons of shingle, and as soon as the charge was taken in, the engine which had driven the pumps was disconnected from them, and coupled on to the screw-shaft, and the vessel was run into deep water, where the shingle was discharged and the vessel returned, the whole operation occupying perhaps two hours. He understood that inside the pump there was india-rubber, or some equivalent yielding material, and he should think that very much of its efficiency was due to that cause. This

principle, he believed, was first applied by Mr. Ball, and had been Mr. Airy's patented by him; and it was certainly a very valuable invention, for it would be obvious that where a stream of large stones and shingle was passing with high velocity between the hard casing of the pump and the hard fan blades, there would be a considerable grinding action, and consequent wear of the casing; but where some yielding material could be introduced into the pump, the wear of the hard parts would be much reduced; and the yielding parts, which would of course wear out in time, could be easily replaced. The nozzle of the inlet pipe was grated with a 3-inch square mesh, which would of course prevent large stones from passing into the pump. It was to be remarked that when dredging in a place where there was abundance of large stones, those stones accumulated on the nozzle of the pipe, and were retained there by the suction of the pump; and then, in order to free the nozzle, it was necessary to stop the engine and let them drop off. For the proper action of the pump it was necessary, as stated in the Paper, for a large proportion of water to shingle to be introduced. What the best proportion was he could not tell. The Paper stated 5 to 1, but he thought it ought to be much larger. Constant manipulation of the nozzle end of the pipe was required in order to ensure a proper proportion of shingle entering, and not more than enough. The Author had stated that the pump was not well adapted for lifting soft silt, because, being diluted with water, it would not settle in time, and would run in suspension over the sides of the hopper-barges. That was true, but there were plenty of cases—he might instance the dredging of the canals in Egypt—where there was no question of putting silt into hopper-barges, but where the silt would be discharged on to the land alongside the canal banks, so that there would be plenty of time for the silt to settle and the clear water to run off. He thought that the conditions in the Egyptian canals were well suited for the action of centrifugal dredgers. The Author had stated that the pump would work in any depth of water from 7 to 25 feet. Of course it would, but he did not think there was any necessity for that limitation. He believed that the pump would work perfectly well in any depth of water where dredging was required.

MR. HENRY J. COLES said that one form of dredging-apparatus Mr. Coles had not been mentioned in the Paper, namely, Captain Eads' sand-pump. It was an excellent instrument, and had been used for sinking caissons at the St. Louis Bridge.¹ The great advantage of

¹ "A History of the St. Louis Bridge." By C. M. Woodward. 4to. Plate xii. St. Louis. 1881.

Mr. Coles. that kind of sand-pump was that it needed only two pipes in the cylinder, one pipe passing down to the sand-pump from the water-pressure pump, and the other to bring the materials to the surface. Thus no obstruction to the use of air-locks, &c., are caused in the cylinder. He had constructed one of these pumps for the Minas and Rio Railway, with the sanction of Sir James Brunlees, Past-President, but no account of its working had reached this country. A pump of the same size (3-inch) at the St. Louis Bridge discharged 20 cubic yards an hour, 120 feet high with a water-pressure of 150 lbs. The "Gatmell" excavator had this great advantage in working in cylinders in silt, that owing to the buckets turning outwards and standing level, there was no tendency for the silt to run away as it would in most other dredgers, if not exactly closed, through the crack which generally existed at the centre where the two halves joined. He had constructed dredgers of that kind, and they worked extremely well. There was, however, a slight disadvantage in their use, as they were small in capacity for their size, and the area they occupied in the cylinder. A cylinder that would admit a dredger with a capacity of $\frac{3}{4}$ cubic yard of the type closing inwardly would only take one with a capacity of $\frac{1}{2}$ cubic yard of the "Gatmell" type. As at present made it was also necessary to land it on a platform before it could be discharged, and the discharge had to be effected by an attendant. No mention had been made of the side-cutting tool designed by Mr. Gatmell, which was of the greatest possible use in sinking brick and concrete cylinders where the edge ran under a considerable distance.¹ The dredger which Mr. Coles had designed (Figs. 5, 6, 7) was a simple tool, fit for the heavy work of contractors. It had been largely used for cylinder-sinking. On the River Thames, for instance, it would readily penetrate the ballast, and would in most cases enter the London Clay sufficiently to seal the cylinder, so that a diver would only occasionally be required. For sinking cylinders at the extension of the Cannon Street Bridge it was the only kind employed, and there divers had been entirely dispensed with. At Rochester Bridge it had worked in the chalk rubble very satisfactorily. One of these dredgers had been selected for use on the Buenos Ayres and Ensenada Port Railway by Mr. Edward Woods, President Inst. C.E. With regard to cylinder-sinking he thought the square dredgers were less likely than circular ones to form a nest for themselves. The corners were not likely to come down in the same position. As to their holding spoil in

¹ Minutes of Proceedings Inst. C.E. vol. lxx. p. 248.

passing through water, in one case one of these dredgers had been Mr. Coles. used for clearing out a well 300 feet deep that had been filled with bricks and all sorts of rubbish from a large works. The dredger was put to work under 5 feet depth of water, and excavating was carried on to a depth of 300 feet. The last part of the time the dredger came up through 150 feet of water, but the amount of

FIG. 5.

COLES' SINGLE-CHAIN GRAB DREDGER.

material brought up was not perceptibly different from that which it brought from under 5 feet of water. Of course he did not maintain that the mud that would pass out through an opening in two seconds was as little as what would pass out in one second; but, in the case of ordinary dredging, he thought it made little difference what was the depth of water through which the bucket passed.

Mr. Coles. Reference had been made to dredgers constructed to run on rails on the banks of canals. Plate 3a, Fig. 4, showed the kind of dredger used for the Suez Canal. It would either work in water

FIG. 6.

FIG. 7.

Scale, $\frac{1}{8}$ Inch = 1 Foot.

COLES' SINGLE-CHAIN GRAB DREDGER.

or for excavating new canals. A ladder dipped down from it to the side of the canal. At the back was a discharge shoot, and carriers were also fitted to the dredgers that would convey the spoil any distance required. They were first manufactured for

Messrs. Couvreux and Hersent,¹ the Contractors, who had paid great attention to their design and construction, so that they were now a first-class instrument for the work for which they were adapted. The form represented could either discharge into wagons, or have a carrier attached of any desired length.

Mr. J. G. MAHOOD remarked that the Author had clearly shown Mr. Mahood. that there was a loss of power of about 50 per cent. due to friction alone in the bucket-ladder type of dredger. In addition to this, there was a further loss to be taken into account, due to the great cost of repairs. In a Paper read before this Institution² in 1873, Mr. Deas stated the cost of dredging on the Clyde to have been, for dredging only, 1·31*d.* per cubic yard; and for dredging and repairs, 2·54*d.* From this it would be seen that the cost due to repairs practically doubled the cost of dredging, and that ought to be considered in conjunction with the loss of power from friction which the Author had found to exist in the bucket-ladder type of dredger; this, however, had been the only machine that, until recently, had been available for executing continuous work in hard material. But little improvement could be hoped for in the motive power of any description of dredging plant, and any reduction of cost must, he considered, be looked for in a resolute attack on the unwieldy chain of buckets and the ponderous gearing for actuating them; to these could be traced the great loss by friction, and the additional cost due to repairs. In the dredger designed by Messrs. Bruce and Batho, to overcome some of the disadvantages incidental to the bucket-and-ladder type (Plate 2, Fig. 9), all the operations were performed by hydraulic power derived from pumping-engines placed in any suitable part of the vessel. As would be noticed, there was a total absence of gearing, tumblers and toothed wheels being entirely abolished; in place of a heavy chain of buckets and links there was substituted a single bucket-excavator, having a capacity of perhaps ten or twelve ordinary buckets employed by the old system, and attached to one end of an oscillating beam working through a well in the vessel. This beam was raised and lowered by means of two direct-acting rams, placed one on each side of the fulcrum. The blades of the excavator were forced into the soil by a closing-ram, which formed part of the excavator itself, and the excavator was prevented from rising, and could be even compelled to follow its work, by means of the lowering-ram at the after-end of the beam. It was impos-

¹ "Le Canal de Terneuzen. Gand et ses Installations Maritimes." Par O. Brunel et E. Braun. Gand, 1881. Inst. C.E. Tracts. Folio. Vol. 30.

² Minutes of Proceedings Inst. C.E. vol. xxxvi. p. 124.

Mr. Mahood. sible to attach too much importance to this action of forcing the excavator into the soil. The same result was attained in the bucket-ladder dredger, but at the cost of pulling the heavy chain of buckets, links and pins, through the soil, with all the consequent wear and tear; whereas in the hydraulic dredger the number of working parts in contact with the soil were a minimum, and it was obvious that the cost of repairs was considerably reduced. As the beam and excavator could be perfectly balanced, the work done was simply to overcome the friction of the rams and centre gudgeon, or fulcrum of the beam, which was comparatively small, and to raise the weight of excavated material, which of course was absolutely necessary, and was here accomplished in a most economical manner. Another point that deserved consideration was that, in the bucket-ladder dredger, almost the same amount of power was expended whether the dredging was performed in 15 feet or in 30 feet depth of water; in the hydraulic dredger the power was exactly proportional to the depth at which the operation was carried on; as, if a dredger capable of working down to, say, a depth of 30 feet, was required to dredge in 15 feet, the stroke of the lowering and of the lifting rams was proportionally reduced, and only one-half the amount of water would be required. The Author had referred to the waste of power in raising the dredged material to a height of about 24 feet above water-level. In a dredger constructed on the hydraulic principle that difficulty had been obviated. The material was raised in an excavator, as he had described, and deposited in a horizontal shoot, which was then revolved over the hopper-barge, or hopper in the dredger, and the contents were tipped out by means of a small hydraulic ram at the back of the shoot. In this case the material was raised no higher than the bulwarks of the barge. The horizontal shoot was carried by a crane, somewhat similar to that used in Bessemer plant.

Reference had been made to the use of excavators for sinking cylinders; for this purpose those of the type shown by Plate 1, Fig. 13, had been very successful, and he considered that the hemispherical shape was better adapted to this purpose than the semi-cylindrical, or clam-shell type of excavator; being circular in plan, it could be made nearly the same size as the internal diameter of the cylinder, and would cut out the material close to the edge of the curb, and avoid the necessity of what was termed undercutting. These excavators could be worked by a single chain from any crane or winch, and could be provided with automatic clip-gear, so that the excavator could be opened or closed at pleasure; they had also been combined with a pole or tube, which

with a suitable brake or clip-gear, applied at the end of the jib of Mr. Mahood. the crane, retained the centre, or fulcrum on which the blades worked, in a fixed position, and forced the blades to penetrate hard material. This pole also kept the excavator in a vertical position, which was very advantageous when dredging on the sloping bank of a river or canal. As regarded the attachment of tines to excavators of the clam-shell type, he was of opinion that the sharp points of the blades in excavators of the type shown (Plate 1, Figs. 12, 13), would have even more penetrating power, and he considered the V-shaped blades were admirably adapted for cutting into heavy material. As an illustration of the work that had been done by this class of machine, he wished to mention the bridge over the Ganges at Benares, where massive brick piers, of elliptical section, had been sunk to a depth of 130 feet below water-level entirely by their aid.

Mr. F. E. DUCKHAM said that the Author had, at the beginning of the Paper, referred to the advisability of filling up or, at all events, replenishing dock water from some cleaner source than the river or the sea adjoining. Accidentally at Millwall Docks some advantage had been derived from pumping in a way resembling that suggested by the Author. Millwall Docks was one of the smallest on the Thames; but he was glad to say for the sake of the shareholders that it was not one of the least profitable, nor where the least amount of work was done; but as the lock was 450 feet long and 80 feet wide, and the whole area of the dock only 35 acres, it followed that the lock represented the large proportion of about one-fortieth compared with the whole dock. When, therefore, the depth of water was reduced in the lock 5 feet it made a difference of $1\frac{1}{2}$ inch over the whole area. That being repeated several times, in varying degree during each tide's work, the water in the dock came down to the level of the river, so that at neap-tides with say 22 feet head of water over the outer sill there was only a depth of 22 feet of water in the dock minus whatever mud there was, and the allowance to be made for the *débris* of various sorts. Apart from the danger to navigation, there was an inconvenience in not being able to get ships alongside the quay; it was, therefore, decided to have some means of raising the water or replenishing it to make good that which was lost by locking. Having in view the advantage to be derived from clean water in the dock instead of dirty, one scheme was to sink a well and raise water from it to replenish the dock; but when it was found that something like 140,000 tons of water a day would be necessary to put into the dock, the conclusion naturally followed that a large

Mr. Duckham. well to give that amount would be required. Then, upon taking samples of water in the river, it was found that whereas a column of water, equal in depth to the range of the tide, would give a deposit of something like $\frac{3}{8}$ inch of mud, the water at the bottom contained by far the greater percentage of mud, while that at the top was comparatively clear; it was therefore decided to obtain the water from the river, and as nearly as possible from the surface. To get the water into the dock was the next consideration, and he adopted a modification of the old scoop-wheel as being the best appliance for raising so large a quantity of water the low average lift of 3 feet. Two such wheels were set up, one wheel 32 feet and the other 36 feet in diameter, each worked by a compound engine of the type generally adopted for screw-steamers; but instead of having the screw on the shaft there were two pinions working in two racks, a rack on each side of each scoop-wheel. The wheels were worked for about two hours on the top of every tide, skimming the water as nearly as possible from the surface. It was intended at first to put a movable weir at the inlet, but it was afterwards found that by fixing it at 7 feet below Trinity high water comparatively clear water could be obtained without an adjustable weir. During the six months ending the 31st of December, 1886, the total number of tides was three hundred and fifty-six, and the wheels were worked at high-water of one hundred and twenty-six tides. The average amount of net increase of depth in the dock per tide was 1 foot $2\frac{1}{2}$ inches, which represented 54,000 tons. In addition to that net increase, the fact had to be taken into consideration that while the pumping was going on, the locking was also going on, and water was being lost thereby and by natural leakage. The average loss during the time the pumps were at work was 3 inches, and adding this depth to the 1 foot $2\frac{1}{2}$ inches gave a gross average of work per tide of 65,000 tons. The cost of working during the half year was: for coals, £141; stores, oil, waste, &c., £9; wages, £74; being a total of £224, or $6\frac{1}{2}$ d. per 1,000 tons lifted. That amount was not based upon the bare cost of two hours' work, but by taking the whole outlay during the half year, including getting up steam and ordinary items of maintenance. The result was not only the obtaining the effect wanted, but the deposit of mud in the dock had been considerably diminished. Though the dredger had not been doing so much lately, it had not only cleared up the current deposit of mud, but had cut well into that which had been deposited in the dock for some years. It was, he thought, an example confirming what the Author had stated as to cleaner

water being put into the dock, and so reducing the amount of Mr. Duckham. mud-deposit. With regard to the dredger with which his name had been connected, it had done good work at the Millwall Docks since 1875. The cost had been correctly stated as $1\frac{3}{4}d.$ per cubic yard of mud lifted, conveyed, and then deposited on land at a distance of 450 feet from the water-side. The traversing ladder referred to in the Paper as being the invention of Messrs. Simons and Co., and Messrs. Fleming and Ferguson, and attributed by Mr. Hunter to himself (Mr. Duckham), was in reality a suggestion of the late Captain Gibson, while dockmaster of Millwall Docks.

Mr. GILES said he assumed that $1\frac{3}{4}d.$ per cubic yard did not Mr. Giles. include the cost of the dredger.

Mr. DUCKHAM replied that it simply included the working Mr. Duckham. expenses. He might mention that, as supplementary to his process for discharging, he had adopted a scheme for raising spoil by suction. Instead of working a centrifugal or other pump direct from the sand, and submitting it to damage by stones and so on, he interposed a spoil-tank between the suction-pipe and the pump. The sand and the stone were deposited in the tank, and the clear water was pumped overboard. That process of lifting spoil resembled one which he had suggested to the Metropolitan Board of Works for taking in and carrying away sludge; and although the decision was against him, he thought, with all due deference to the arbitrators, that the scheme would have proved a good one.

Mr. JOHN J. WEBSTER, in reply to the discussion, said he had a some- Mr. Webster. what easy task, as the tendency had been not so much to criticise the Paper adversely, as to extend its scope; and it was gratifying to find that so much valuable information had been elicited. It had been suggested that the cost of dredging should have been given per cubic yard; but as there was some little doubt about what was meant by a cubic yard of dredging, the cost so expressed might be misleading. In parliamentary estimates such prices for dredging as $1d.$ or $2d.$ per cubic yard were never heard of, they were seldom if ever less than $8d.$ or $9d.$; but when the works were executed, the above low prices were often given as the actual cost; and although there was apparently such an enormous difference in the two prices, he maintained that it was possible for both to be correct. The engineer, in preparing estimates, calculated the cost from the cross-sections; he knew to a yard or two how much had to be excavated, and from the contractor how much per cubic yard he would require to undertake the work. When, however, the

Mr. Webster. work was in hand, the dredger-master had nothing to do with cross-sections, and estimated the work by what the machine lifted. Supposing, for instance, it was found from the cross-sections that 1,000 cubic yards were required to be excavated, probably when the work was completed, 1,500 or 2,000 cubic yards would have been actually raised; the silting, which took place more or less in all estuaries or rivers, having caused the work to be done several times over. Again, there was a difficulty about the measurement of the cubic yard excavated; it might be measured from the capacity of the hopper; the result, however, would not represent the actual amount excavated, but simply the amount of silt and water in an indefinite proportion. Taking all these points into consideration, he thought it was better to give the cost per ton, for that would represent the work actually done by the dredger. In designing a dredger, the space to be excavated according to the cross-section would be of no use; and it would be absolutely necessary in proportioning the engines, boilers and other machinery, to know how many tons were to be raised a given height in a given time. It would of course be of great advantage to know the cost of dredging per cubic yard according to plans, per cubic yard according to measurement in hopper, and per ton actually raised; but this information would be very difficult to obtain. It had been said that the costs given in the Paper wanted revising; but he wished to say that he was not responsible for them, as they had, with one or two exceptions, been supplied by the engineers of the different works; and he had stated distinctly in the Paper how, and in what manner, many of the published results of costs of dredging were misleading. When, in referring to the Priestman dredger, Mr. Webster had said that it would not dredge hard, stiff material, he was simply referring to the ordinary bucket-dredger; but he was aware that Mr. Priestman had since designed a grab-bucket—a very useful tool which would work even in virgin soil. Mr. Hunter had noticed his suggestion for a helical creeper to discharge the dredged material, and thought from his experiments that the increased friction would outweigh any advantage. He should be glad to have some more information about the experiment referred to by Mr. Hunter. The bucket with a loose bottom, to be tilted in passing over the tumbler so as to assist the discharge of the bucket in case of stiff material, described by Mr. Hunter as having been used in excavating the Victoria Dock, was an ingenious device, but he thought that with a well-designed ordinary bucket such an arrangement was not necessary. When he stated that bucket-ladder dredgers would not dredge in shallow

water, he was referring to the dredgers as ordinarily made; Mr. Webster, special machines could of course be designed for special purposes, and if necessary for places where there was no water. With regard to the slopes of the shoots, the figures he had given were correct, when the material had assistance from pumps and was, as it were, water-borne; but without this assistance, the angles would be required to be from 1 in $2\frac{1}{2}$ to 1 in 3 as mentioned by Mr. Giles. From experiments made with the long shoots used in the Suez Canal, it was found that fine sand, mixed with equal quantities of water, would flow down a slope of from 1 in 20, to 1 in 25, but at a flatter slope than these, no matter how much water was used, the sand would separate from the water and form a hard cake on the bottom of the shoot.

Correspondence.

Mr. RUSSEL AITKEN said that he was somewhat astonished that Mr. Aitken. the Author had not given Mr. (now Sir) Bradford Leslie's dredger in his list of excavators. This rotary pump dredger was used with great effect and cheapness in putting in the foundations of the Gorai Bridge, in Bengal. When he was at the bridge, he saw plugs of stiff fire-clay which had been forced up the suction-pipe of the full size of the pipe itself; also iron hammer-heads which had fallen into the cylinders, were drawn up from a depth of 120 feet. He had examined the dredging operations going on at Calais some years ago; and the engineer in charge had explained what was being done. The sand dredged from the bar in front of the harbour was being removed for 91 centimes per cubic metre, or rather under 7*d.* per cubic yard; but this was no test of the cost of the work to the contractor, as he, having a monopoly of the dredging plant, could dictate his own terms. These dredgers were Bazin sand-pump hopper-dredgers of 160 tons; and they were able, on an average, to work fifteen tides during each winter month. He thought it was but right that, in a Paper on dredging, the services of the late Mr. John Ure, M. Inst. C.E., should be acknowledged; although Mr. Ure did not originally propose to deepen the River Clyde by dredging instead of making a ship canal from Glasgow to Bowling, yet by designing and working large dredgers, both on the Clyde and on the Tyne, he did more for dredging than any man of his time. The dredging contractors went from the Clyde to the Suez Canal, taking their dredging plant with them, and the French copied their machines, thus

DREDGING APPLIANCES.

PLATE 3.

Fig : 1.

Fig : 2.

TWIN SCREW DREDGER "MELBOURNE."

Fig : 6.

850 TON HOPPER-DREDGERS, TO DREDGE THEIR OWN FLOTATION BY PATENT TRAVERSING LADDER.

Fig : 3.

Fig : 4.

TWIN SCREW DREDGER "DOLPHIN."

Fig : 5.

1400 TON HOPPER-DREDGER.

Feet 10 5 0 10 20 30 40 50 100 150 Feet.
Scale of Feet.

Fig : 7.

COMBINED EXCAVATOR AND CARRIER, RIVER GARONNE.

Fig : 8.

CROSS SECTION.

LONGITUDINAL SECTION.

SINGLE BUCKET-LADDER DREDGER, RIVER DANUBE.

Fig : 9.

DIMENSIONS.

Length between perpendiculars. 145.0'
Breadth moulded. 30.0'
Depth moulded amidships. 11.5'

LONGITUDINAL SECTION.

Fig : 10.

PLAN.

STEAM-PUMP HOPPER-DREDGER, EAST LONDON HARBOUR, SOUTH AFRICA.

Fig : 11.

SIDE VIEW.

Fig : 13.

GENERAL PLAN.

Nº 2 SIDE DREDGER, RIVER WEAVER.

Fig : 15.

PLAN.

Fig : 16.

HALF PLAN OF FRICTION RINGS.

With Internal and External Lugs.

FRICTION GEARING Nºs 3 AND 4 DREDGERS.

Scale: 1/2 inch = 1 Foot.
Feet 10 5 0 10 20 30 40 50 100 150 Feet.

Fig : 12.

SECTIONAL ELEVATION AT A.A.

Fig : 14.

SECTIONAL ELEVATION AT B.B.

Fig : 17.

SECTION AT A.B.

Fig: 1.

Fig: 2.

LIGHT DRAUGHT SELF DELIVERING DREDGER.

Fig: 3.

Fig: 4.

MACHINE FOR UNLOADING DREDGINGS FROM BARGES.

EXCAVATOR. (COUVREUX SYSTEM.)

Scale 16 Feet = 1 Inch.
Feet 10 5 0 10 20 30 40 50 Feet.