Discussion.

Mr. Wolfe Barry. Mr. J. WOLFE BARRY, C.B., President, was sure he should be doing only what the members wished if he proposed that a vote of thanks be accorded to Mr. Cruttwell and Mr. Homfray, for their Papers. Before proceeding to the discussion of the details of the Tower Bridge, as to which, much would perhaps be said, it might be relevant to lay before the Institution some of the preliminary history of the various steps that had led to the building of that structure. This was, perhaps, not strictly an engineering matter, but it would probably be interesting to the members, and be convenient to place it on the Minutes. The want of some communication lower down the river than London Bridge had been felt for very many years, and since the middle of this century rapidly became urgent. Gradually a town—in fact, two towns—had grown up on the sides of the Thames below London Bridge, which had been compared in magnitude with Manchester on the one side and Liverpool on the other, but London Bridge still remained the only means of crossing for all this large population, with the exception of ferries, steamboats, the Thames Tunnel and a small subway, to which he would allude. In fact, it was reported in 1879 that 39 per cent. of the whole population of London lived east of London Bridge, and the want of some better means of communication lower down the river was evidently a pressing matter. Illustrating his remarks by lantern-views thrown upon the screen, he showed the extraordinary extent to which those great districts had been developed in the course of 100 years. He had recently come upon an old print,¹ which showed the condition of the south side of the river at the site of the present Tower Bridge a century ago. The ruins of Bermondsey Abbey, which stood almost at the southern end of the Tower Bridge, were there depicted as surrounded by hedgerows and fields, and remains of the abbey were still to be found among the present buildings, and reminders of it in the names of some of the crowded streets which now occupied the site of the ancient building. A most startling metamorphosis had certainly taken place since that period, which was well shown by a glance at the map of the present district as

¹ See "The Tower Bridge," a Lecture; by John Wolfe Barry, M. Inst. C.E., London, 1894, p. 13, a copy of which is in the Library of the Institution.

compared with the old print referred to. Nothing had been done in the way of intercommunication between the two sides of the river from the earliest times until 1824, when Brunel conceived his Thames Tunnel, which was opened for pedestrian traffic in 1843; and things remained in that condition for nearly thirty years, the tunnel being, in consequence of difficulties of finance, only available for foot passengers, although it was designed for vehicular traffic. In 1871, the little Tower Subway was initiated by Mr. Peter Barlow, and was carried out with great ingenuity and cleverness by their departed member Mr. Greathead, whose loss the Institution so greatly regretted. Then came, in 1879, an application to Parliament from the Metropolitan Board of Works, who, under the advice of Sir Joseph Bazalgette, proposed a bridge¹ of one span across the Thames almost at the site of the Tower Bridge. It was striking and beautiful in itself, but failed, in certain important particulars, to fulfil the requirements of the situation. The headway was only 65 feet above high-water level, but even with that comparatively small height the gradients, on the south side especially, were very long; and it was necessary, taking the two gradients together, of which the south side was spiral, to employ a gradient of 1 in 40 for upwards of 1 mile. The headway was greatly objected to by those interested in the wharves and warehouses above the site of the bridge, and after a long enquiry it was rejected by Parliament. The cost of the bridge was estimated to be £1,400,000. So things remained till 1883, when certain subways for vehicular traffic were proposed, to be served entirely by lifts, and to run from Tower Hill on the north side of the river to Rotherhithe on the other side. There were difficulties in the approaches to the hydraulic lifts, particularly on the north side, and although the whole design had been carefully thought out and was supported by the advice and assistance of the eminent firm of Sir William Armstrong & Co., the proposal was, on the opposition of the Metropolitan Board of Works, rejected. In 1884 the Metropolitan Board of Works propounded a scheme for a subway beneath the Thames for vehicular and pedestrian traffic, about a mile east of the site of the Tower Bridge. That also was open to great objections. There were very long gradients in the road approaches, especially on the north side, because the north side of the Thames rose sharply from the north bank of the river. The gradients were worse than 1 in 40, and the cost was considerable, he believed from recollection about £1,750,000. That

Mr. Wolfe
Barry.

¹ "The Tower Bridge," p. 14.

Mr. Wolfe Barry. scheme, like the others, was rejected by Parliament. In the same year an independent body of promoters proposed a duplex bridge, something on the principle of an ordinary lock, served, however, by two pairs of bridges instead of two pairs of gates, one at each end, and the idea was that when one bridge was opened the other bridge should be shut against vessels, and therefore open for vehicular and foot traffic. There were grave objections to that scheme also, as such a bridge would have occupied a very large space in the river, and the difficulty of managing ships inwards and outwards between the two bridges was shown by the Thames Conservancy and other persons to be so great in a tideway like that of the Thames, that that also had been rejected. Both the last-mentioned schemes were before Parliament in the same year, and Parliament, in rejecting them, invited the Corporation of London to come forward with a Bill for a low-level opening bridge at or near the Tower. The Corporation, with great public spirit, although neither the bridge nor its approaches were strictly within the City boundaries, accepted the invitation, and propounded the scheme of the Tower Bridge in the following session. He should have said that, prior to the dates mentioned, there had been various other proposals to cross the river at or near the Tower, and amongst the authors he might mention Colonel Haywood, who was Engineer to the Commissioners of Sewers for the City of London, Sir Douglas Galton, Sir John Hawkshaw, Sir George Bruce, and, lastly, Sir Horace Jones, who had studied the questions involved in a Tower Bridge before Parliament invited the City to undertake the work. From the first, Sir Horace Jones had proposed the bascule system of treating the case—which was what might be called in the vernacular the “see-saw” system, well known in Holland and in many of the canals in Great Britain, where the platform of the bridge was balanced on an ascending and descending beam, so that as one end went up the other went down. The designs¹ which Sir Horace Jones had submitted to the Corporation, and he believed also exhibited to Parliament, when the duplex bridge was under discussion, showed arched girders carrying the suspending-chains across the central opening. The great objection that was felt to exist against the designs first propounded was that anything in the way of an arched form spanning the central opening would be liable to be struck by the masts and rigging of

¹ “The Tower Bridge,” p. 18. Also “History of the Tower Bridge,” by Charles Welch, London, 1894, pp. 202, 203.

ships, and it would be very difficult in a tideway such as that of the Thames to keep vessels in the middle of the river so as to avoid the risk of such collisions. Accordingly, about 1885, Sir Horace Jones began to think that the arched form must be given up. That was about the condition of things when Mr. Wolfe Barry first became connected with the undertaking, and a new design¹ was initiated when he was appointed engineer to assist Sir Horace Jones in carrying out the work of the Tower Bridge. Accordingly in the design submitted to Parliament all idea of an arched form had been given up, and a level soffit for the upper bridge was one of its principles. He believed that was nearly the history of all the preliminary work and of all the designs which had led up to the present Tower Bridge. He did not propose to go at length into any question raised in the Paper, but would reserve what he had to say to a later stage. He would, however, refer to a plan² which showed some of the difficulties experienced in carrying out the work, owing to the wise and proper restrictions of the Thames Conservancy in respect to maintaining a navigable central width of 160 feet during the construction of the works. The result of these restrictions was very considerable delay in executing the foundations, as they prohibited the simultaneous construction of the two piers; so that a year and a half more was spent on them than was originally anticipated. He did not wish to complain of the Thames Conservancy having imposed these conditions, because it was a proper condition that a width of 160 feet should be maintained at all times; but it was a circumstance to be taken into account, when it was remembered how long a time the bridge occupied in building. The Act of Parliament also gave the Conservancy very large powers as to the times of opening the bridge. At one time it was held by the Conservators, who were by the Act of Parliament made absolute masters of the situation in that respect, that it would be necessary to keep the bridge open for vessels for two hours at or near the time of high water; and that circumstance had much influence in the erection of the lifts and staircases for pedestrian traffic across the upper bridge. If it had been known then that the bridge would not require to be opened except for individual vessels, and that the average time for the complete operation would not be more than six, and very often not more than three minutes, he did not think the expense of the hydraulic-lifts to the upper bridge,

¹ "The Tower Bridge," p. 19. Also "History of the Tower Bridge," p. 204.

² "The Tower Bridge," p. 22.

Mr. Wolfe or perhaps even of the staircases, would have been incurred.
Barry.

Before concluding, he would like to place on record his great regret that Sir Horace Jones had not lived to see the realization of his original conception of a bascule bridge across the river. He had taken very great interest in it, and was, he thought, the first to suggest it. His untimely death soon after the commencement of the work was greatly lamented by everybody connected with the undertaking. He also wished to express his acknowledgments to many who had assisted in the work, especially his partner, Mr. Brunel; Mr. Fyson, who undertook much of the preparation of the detailed drawings; Mr. Stevenson, who had been his assistant with the architectural work; and—he was going to say most of all, but he did not like to make any invidious comparisons, so would say very largely to the Authors, Mr. Cruttwell, the Resident Engineer, and Mr. Homfray, who superintended the machinery on behalf of Sir William Armstrong and Company. He did not lose sight of the great assistance rendered to him by the other contractors who were mentioned in Mr. Cruttwell's Paper; but amongst those who did yeoman's work in a rather difficult undertaking, he was sure all would recognise the great ability of the firm of Sir William Armstrong and Company, and the conspicuous success of the hydraulic machinery for which they were so largely responsible. He also wished to bear witness to the broad-minded way in which the work was assisted by the Thames Conservancy. He had had much to do with that body during his lifetime, and of all the public departments with which he had dealt, he had never found any who had been so desirous of facilitating any work once authorised by Parliament, as that body, or more free from anything like red tape or obstruction.

Mr. Liversidge. Mr. W. H. LIVERSIDGE, Chairman of the Bridge House Estates Committee, with which he had been connected for the past three years, had had an opportunity of witnessing the working of the bridge, and felt how much indebted the people of London were to the engineering skill of the President of the Institution. It had been a great satisfaction to the Corporation of London to be able to provide such a bridge for the use of the public. During a long course of years it had been the privilege of the Corporation to husband the resources that had been left to it for that purpose; and at the present time they were in a condition to maintain not only the Tower Bridge, but also the other bridges entrusted to the care of the Committee. He could only hope that in the course of time, as the income from those estates increased, if further

accommodation should be required by the public, it might be the privilege of the Corporation of London to give it to the public without cost to the ratepayers. Mr. Liversidge.

Mr. EWING MATHESON was impressed by the very large and massive character of the mid-river piers, and wondered whether it would not be possible to obtain all the services required of them with a smaller width than 70 feet each. It required great justification to plant down in the middle of the fair-way of the River Thames two impediments which bore such a large ratio to the total width of the stream. He might go further and ask whether it would not have been possible to dispense with the piers. In speaking of the earlier designs which had been submitted for the bridge, the President had alluded to the high-level bridge, and to the other projects which had been put forward; but the whole difficulty appeared to centre round two or three points: both the high-level bridge and the tunnel had Mr. Matheson.

Fig. 1.

impracticable gradients, and the river conservators insisted upon a certain headway; and after the various designs had been put forward, it had been deemed impossible to satisfy all the requirements without having a low-level bridge for the road traffic head-way, and piers in the middle of the river to allow of an opening span. He had during the past twenty-five years taken an interest in all these projects, and had carefully investigated them. About twelve years ago, Mr. R. M. Ordish and he had propounded a scheme, *Fig. 1*, for satisfying those somewhat incompatible needs. The need for a railway bridge would soon arise; the northern railways that converged near the Minories on the Middlesex shore, and those coming to London Bridge on the other side, must sooner or later be connected; and the cost of a railway bridge would not lie in so many tons of steel or masses of masonry, but in the right of way or the easement across the river. Therefore it seemed a most important point that any crossing of the river which gained that right of way, and which, as did the Tower Bridge, opened up the approaches, should be

Mr. Matheson. utilized as far as possible for a railway bridge hereafter. The trade of the Port of London, at any rate in regard to sea-going vessels, tended down the river, and an opening span became less and less necessary every year; and as that need became less, the compensation to wharfingers and others would also become less. Concurrently the need of the railways was growing, and, sooner or later, that need would overcome the opposition of the wharfingers. A railway bridge would then have to be built, and the cost would amount to one or two millions sterling; of which a considerable portion would be spent, not in purely engineering work, but in clearing a way for the approaches of an entirely new bridge, in making expensive foundations, and in obtaining the right to cross the river. He thought therefore, if the foundations of the Tower Bridge could have been made sufficient to bear a railway, it would have been a wise provision. The bridge proposed by Sir Joseph

Fig. 2.

Bazalgette had been designed with that view. The London clay presented as good a foundation for abutments as it did for vertical piers; a single arch was proposed, *Fig. 2*, with an opening bascule span in the suspended roadway to allow vessels to go through. Any injury that vessels might sustain from contact with the bascules would be prevented by two temporary guiding dolphins, which could be removed. An additional weight of about 3,000 tons or 4,000 tons of steel was necessary in the arches to make them strong enough to bear the railway afterwards. Ample width, rather more than in the present bridge, was provided; and when the time came for a railway it would only become necessary to close the bascule opening and remove the bracing above the upper deck, to give room for four lines. The extra strength of the structure to make it capable of carrying such a railway would cost £230,000, to which would have to be added £50,000 for the platforms for the permanent way. Whether a separate railway bridge could be made for £1,000,000 was extremely doubtful. Numerous examples existed of the kind of bridge he proposed, *e.g.*, that over the Rhine at Cologne, the

high-level bridge at Newcastle, the St. Louis Bridge over the Mississippi; and he believed the bridge at Berne had a double-deck on the same principle. Not only did the piers of the Tower Bridge as constructed obstruct the fair-way in a manner which was harmful to the river; but, during the three years it was in course of erection, great obstruction had been caused by the staging, which was apparently necessary for erecting that type of bridge, not only round the towers but under the shore-spans. Single-span bridges were now so easily constructed that a bridge 850 feet wide between the abutments could easily have been made on a system which would admit of erection from the shore. One of the great difficulties in launching bridges forward—he was speaking of a matter in which he had considerable experience—was that there was often no space on the shore for building such a big structure. In the present case there was ample space as, at great cost, the approaches had been cleared. With the existing width of the river, it would have been possible to have

Fig. 3.

half the arch erected on timber-staging, on the river bank; and when so erected, trussed back and made into a temporary suspension bridge or cantilever; then the staging could be removed and the bridge brought forward. In *Fig. 3* were shown one half erected on the staging and the half that had been brought forward. The joining in the middle would not be so troublesome a task as that of the Forth Bridge. There were bridges of the cantilever kind built forward without any launching, and that might have been done. He thought, in looking at the early future of London, in regard to the great necessity for railway-crossing, that some such provision as he had described should have been made. He did not wish to depreciate the magnificent monument which the bridge formed, but it was a question whether in erecting that gateway into London it should have been planted down in the middle of the Thames. Temple Bar was an interesting monument, but it had to be taken away as an obstruction, and he could not help thinking the day would come when the present Tower Bridge would likewise be removed.

Mr. Thomson. Mr. T. FRAME THOMSON observed that it was a matter of regret to some members who attended the meetings regularly, that so many Papers were of a purely descriptive character. In regard, for example, to the work described in the Papers before the meeting, it appeared to him that the outline was distinctly peculiar; and some indication by way of stress diagrams of the manner in which the various parts performed the functions for which they were intended, would give the first communication an interest which at present it did not possess. The object of such a structure as the Tower Bridge was undoubtedly to perform certain functions by directing forces in certain ways; and he understood that the aim of Civil Engineers was to direct such forces. Of the nineteen pages of which the first Paper consisted, about two pages would represent the aggregate of the space allotted to indication of the manner in which the functions of the various parts of the structure under consideration were performed. The result was that he had listened to a Paper which left but a small impression on his mind, and certainly no definite intelligent idea of the manner in which the functions of the structure operated. In the President's recent Address, there had been some insistence on the necessity for a higher standard of scientific attainment among engineers; and it would be without doubt advantageous that the results of such attainment should find expression in the Papers published by the Institution.

Mr. Rigg. Mr. ARTHUR RIGG had recently visited the bridge and had found that the hydraulic lifts were not in use; so that in order to cross while the bascules were open, pedestrians had to ascend and descend 205 steps. The reason for this appeared to be the advocacy by the Thames Conservancy of a two-hours' opening of the bridge, which experience had shown to be unnecessary. In the original design of the bridge, a beautiful Tudor arch was represented, but that seemed to have been replaced by the existing high-level foot-bridge, which formed an ugly straight line. He was astonished that it had been considered necessary to provide two engines, each of 360 HP., to move the two bascules, which he understood were on live rollers and weighed 1,070 tons each. He had calculated that it required about 66 revolutions of the hydraulic engine to raise the bascules. About 150 HP. was used whether for lifting or lowering each bascule. He had seen, in 1895, at Ipswich, a sluice, mounted on live rollers weighing 40 tons, moved by a girl; 1,070 tons, therefore, should require an expenditure of power that was not 150 HP., or anything like it. It was stated that glycerine was used only in the inter-

locking gear, not in the main engines; but as the system was self-contained, glycerine as a lubricant might have been used throughout. The first necessity of a hydraulic engine was a certain amount of lubrication. If the water could contain a small amount of soap or other greasy substance it would suffice; but as hydraulic engines were usually run, without the slightest lubrication, it was no wonder that they did not last. The spur pinion on the hydraulic-engine shaft seemed very small; there appeared to be about $17\frac{1}{2}$ tons on each tooth, which was rather heavy, provided always full pressure was required. Hydraulic engines running at a uniform stroke were the most extravagant motors in existence. At the *conversazione* recently held at the Institution he had shown a model of one of his hydraulic engines, which had a stroke varying in accordance with the load. One of those engines had been for some time working a draw-bridge at the London Docks. Its stroke could be regulated or reversed, and no more water was used than was required. It drew the bridge over 72 feet and back again by moving a handle, like the old-fashioned reversing gear of a locomotive, and the amount of water used was very small. It was worthy of notice that the tension required to start the bridge was 3 tons, but the tension to keep it going was 35 cwt., more or less. With regard to the bascules, the force required to keep them going depended more upon exceptional resistance due to wind than to any unbalanced portion of their weight, and while they were moving there was a good deal more water used than there was any necessity for, if the bridge were properly balanced and worked well. In the present instance about half the water in the hydraulic engines was generally thrown away, and between 70 per cent. and 80 per cent. in many other cases.

Mr. MAX AM ENDE was not sure whether the straight line was not æsthetically more correct than the arch in combination with the inverted arches on each side of the bridge. They were very fully developed, and required a strongly marked tie between them. The load on the tie, real or suggested, was insignificant, and therefore it was not necessary to show a deflection in the tie, much less an upright arch under it, as had been proposed. He would not further discuss the architectural merits of the bridge, but would address himself to the system upon which it was constructed. He supposed he was right in describing it as a suspension bridge of five spans, two of which were loaded and one had a stiffening girder. It was also necessary to say that all the saddles were movable. If that stiffening girder had a hinge under the hinge of the chains, then

Mr. Rigg.

Mr. Max am Ende.

Mr. Max am
Ende.

if the Middlesex span was loaded, the middle hinge would rise till the three hinges of the same span were in a straight line, or if the loads were unequal in a ratio of three to four, the hinge would go up about one-eighth of that distance, the hinge in the opposite span going down about as much. A stiffening girder preventing this would have a very great bending moment under the hinge, about six times as great as the greatest moment from inequality of the load if only one loaded suspension span existed in the bridge instead of two. Why, therefore, could not all moments be dealt with by stiffening girders, and the bracing between the chains be omitted? He saw the reason why there was only one continuous stiffening girder; because otherwise the whole structure would be undetermined, whereas now it was determined. He was, however, informed that the part described in the Paper as a stiffening girder—diminishing the tendency of one of the shore spans to affect the vertical movement of the other span—was not a stiffening girder in the ordinary sense of the term, but a strut or a tie according to the position of the load; and that the dotted lines shown with the temporary staging in Fig. 1, Plate 1, were intended to represent this part. He considered the description to be misleading, inasmuch as, whatever that part might be, it did not reduce that tendency which was due to the load; but its function was to resist the tendency completely, because if its strength or that of its anchorage were insufficient, the whole structure would be in danger of being destroyed by the tendency in question. In a Paper read before the Institution he thought it justifiable to look for a discussion of the stresses in the most important parts of the structure, either by diagram or otherwise, and for a statement of the sectional areas, and of the fixed load. Moreover, considering the notoriety of the work, the illustrations were too scanty; but, such as they were, they might at least contain the dimensions necessary to define the positions of the main parts of the suspension structure. With all deference to the judgment of the Author of the first Paper, he submitted to his consideration whether the information alluded to would not be more acceptable to the majority of members than elaboration of ornamental parts in the illustrations, which were already known from photographs, and the enlargement of comparatively unimportant parts, such as were shown in Fig. 4. He would be grateful to the Author, and he was sure many other members would share that feeling, if he would supply such information.

Mr. Read. Mr. R. J. GIFFORD READ supposed that the reason for the middle span of the bridge being narrower than the side spans, was that room had to be allowed for the traffic to accumulate while the

bridge was open. The heavy loading affected the strength of the whole structure, and he would be interested to learn the maximum load per square foot of the surface of the road that had been used in estimating the bridge. He did not see it given in the Paper, although the tension on the chain in certain points was stated. It seemed that the lower part of the masonry rested on the pier, and the upper part on the various cross-girders in the towers, and space had to be left to allow for the expansion of the iron. He asked if those spaces were allowed to go right through the masonry and to appear on the front. Again, while the masonry of the turrets was built up from the bottom, the panel walls were simply in pieces between the girders at various stages. The tower was composed of four pillars, yet the weight of the bridge seemed to be supported on one pair towards the shore ends; and the line of action of that weight did not seem to be through the centre of the pillar. It occurred to him whether it would not have been possible to use the four pillars of each tower as a pier, as in ordinary suspension bridges, and to apply the weight on a saddle in the centre. It was stated that on account of the footway girders being formed as cantilevers, resting on the inner pillars of the piers, they produced an upward pull at the back which partly counteracted the weight of the chains; but the weight of those footway bridges must be very small in comparison to the weight of the side spans. It had been stated by Mr. Cruttwell that the ties in the cross-bracing of the towers were heated in order to make them fit into their places. He wished to ask how much was allowed for the expansion by heating. Was it, say, the diameter of a rivet-hole or half a rivet-hole? It was stated that the roofing of the foot-bridges was covered with zinc, but he understood that material did not last well in London, being affected by the atmosphere. Would it not have been better to have used lead for the purpose in the Tower Bridge? With reference to the suspension-chains, it was stated that on account of the loading in different ways at one time, the bottom boom of the long braced link and the top boom of the short braced link had the maximum load, and that in other positions of the loads the reverse occurred; therefore each of the booms had to be strong enough to take the whole of the load. He thought if the load had been suspended from the centre of the chains, the top and bottom booms would have assisted each other to sustain the stress, and therefore might have been reduced in section. The masonry of the piers had been criticised, but he thought the result was certainly much more pleasing than it would have been if

Mr. Read. the iron had been left bare. In many engineering structures an attempt at ornament diverted attention from the real use of the structure itself, or the portion of it to which such treatment was applied. In the present case, there was no doubt that the towers were designed to support the weight of the chains, and he thought it of no great consequence whether the outside was encased with stonework or with iron. Another point was that the division into stages broke up the large mass of the tower, and gave a scale which was comparable to other buildings in the immediate neighbourhood. The great fault, from an artistic point of view, in engineering structures, was that they were so frequently out of scale with nature around them, and the more they could be brought into that scale the more harmonious they would appear.

Mr. Walker. Mr. F. W. WALKER thought that if in the discussions questions were asked more briefly and clearly, members would gain a great deal more knowledge. It would be interesting to know shortly the reason why one span had not been adopted, as suggested by a previous speaker. It did seem that there ought not to be a large tower of masonry in the middle of the river. No doubt ample reason could be given for making the two towers, but he would like to know it from those who were capable of explaining the matter. He agreed that the masonry was of immense advantage; it would be as unreasonable to complain of beautifying necessary ironwork by the addition of nicely-designed masonry, as it would be to have the pillars and arches of Westminster Abbey pulled down because it was considered necessary to support them, as was done, by iron bars. In the case of old masonry—that of the Tower Bridge would be old some day, for he did not agree that it would soon be removed—it was reasonable and wise to support it by ironwork. Masonry was artistic, and it was desirable to give structures a good appearance. In regard to hydraulic machinery, he thought it of little consequence, in such a vastly important matter, whether a drop more pressure water was or was not used. Great inconvenience would result if the rams of the hydraulic engine were not large enough to lift the bridge at any particular moment. It should be remembered that in such an installation the pressure water was pumped at a trifling cost. He thought it was wiser to erect economical pumping-engines, and to pump the water at a minimum cost, with full confidence that at any moment there would be enough power to move the bridge, than to adopt any experimental or artificial economy of a small character. Englishmen did not like obstacles in their ordinary daily life; and he thought it would have been a mistake, for the

sake of economising a small amount of coal in the operations of Mr. Walker. opening and closing the bridge, to have risked a grave inconvenience to the public by an accidental failure of the hydraulic machinery.

Mr. W. B. LEWIS was confused by the use of the word "boom" Mr. Lewis. in the Paper. It was said that when the load was at the shore end of the land-spans, the weight was carried by the upper boom of the longer part of the chain and the lower boom of the shorter part. His idea of a boom was something to act under stress. Surely those were chains, and they were in tension, and both the upper and the lower were intended to act as chains, and not otherwise. He would like to hear in greater detail why that system of bracing the chains had been adopted, and what had been its effect. It appeared that on one side there was a rise of $1\frac{1}{2}$ inch from extreme unequal loading, and on the other side there was sometimes a rise of 6 inches from a like cause; still, that was stiff for a suspension chain. Was not that bridge really a suspension bridge with the chains braced? If so, was that a more economical way of securing stiffness than by the ordinary plan of putting the stiffening girder along the parapet? One or two methods had been tried to stiffen suspension bridges, but he was not aware of any other case where the plan had been adopted of putting two chains braced together, and, as he understood, thus kept outside the line of stress wherever the load might be.

Mr. E. P. HILL thought it must be necessary either to stiffen the Mr. Hill. chains or to stiffen the platform, and he assumed that in the present case there was not headroom enough to stiffen the platform, and therefore the chains had been stiffened, which was also a more economical method. He fancied that there was some misunderstanding as to the way in which the chains acted. They performed the double function of beams and chains. As beams, the stresses were compressive in the upper and tensile in the lower flanges; as chains they were tensile in both flanges. The actual stresses in the flanges were obtained by combining the two functions. He calculated that an extra stress was thrown upon each of the high-level ties of about 260 tons when one shore span was loaded with 1 cwt. per square foot. He asked, How was that unbalanced force met? The two spans were in equilibrium when they were both unloaded. How, therefore, was equilibrium maintained when one was loaded and the other unloaded? He did not quite understand the stiffening-girder, and would be glad to have an explanation of it from the Author. He did not wish to be hypercritical, but when walking on the bridge the curve of the

Mr Hill. chains was not quite agreeable to the sight, which did not readily pass from one chain to the other as it should do in a continuous suspension curve. He supposed the chains had to be stiffened in that case; and from a scientific point of view he should say that the way in which they were stiffened was the best. That was the right form of stiffening, but at the same time it did not quite please the eye; and he wondered whether, if the pin at the intersection had been placed behind the parapet, the latter, in fact, covering the lower part of the chains, it would not have prevented that disagreeable break in the curve.

Mr. Cruttwell. MR. CRUTTWELL, in reply to Mr. Matheson, said that the vessels which were constantly moored in the river offered quite as great an obstruction as the piers. He thought that the public would have hardly liked to wait until the railway companies had settled what they wanted. As for the day coming when the bridge would have to be pulled down, he could only say it would be a very good thing for engineers, as it would give them some work to do. Why Mr. Rigg had gone up to the high-level footway and down again on the other side was incomprehensible, unless it was for the reason that influenced other sight-seers, viz., curiosity; because the bridge was seldom kept open for more than six minutes, and very often only three or four minutes. The reason for the footways and lifts had been explained by the President; they were made in order to comply with the requirements of Parliament, that the bridge should be kept open for two hours at the time of high water, if required by the Thames Conservancy. Had the Conservancy required that, the footways and lifts would have been absolutely necessary. Had the high-level footways been arched next the piers, the headway must have been greatly diminished, and he thought the Corporation would have had to pay heavy bills for all the rotten old masts that would have taken an opportunity of colliding with the part next the pier. The primary object of the stiffening-girder was simply to steady the point of intersection of the long and short segments of the Surrey span; that point being steadied by a triangle formed by the short segment of the Surrey span for the hypotenuse, the stiffening-girder for the base, and the column of the side abutment for the vertical. The stiffening of that point rendered it impossible for unequal loading of the Middlesex span to cause any considerable rise or fall either of that or of the Surrey span. With regard to the chains between the point of intersection, Mr. Lewis had suggested that instead of bracing the chains the flooring might have been

stiffened by a girder at the level of the flooring. That, no doubt, Mr. Cruttwell might have been done, but it would have been unsightly. A span of 270 feet would require a stiffening girder of a depth greatly exceeding the height of the parapets, which at the Tower Bridge were only 4 feet above the footways. That would have been insufficient for a stiffening girder extending from the pier to the abutment, and in the absence of a stiffening girder at the level of the floor, he thought the braced chain answered its purpose in the most advantageous manner. The centre-span was not narrower than the shore-spans, on account of the latter being adapted to give room for the accumulation of traffic; but simply because the position of the piers as they were now placed, leaving 200 feet between them, lined in better with the tiers of vessels in the river than they would in any other position, and the span of 200 feet had been fixed by Parliament as the width to be adhered to. The load allowed in the calculations was $1\frac{1}{2}$ cwt. per square foot for the roadway, and 1 cwt. on the footways. The spaces allowed beneath the landing-girders for the unequal settlement of the masonry and ironwork were allowed to go right through when the masonry was built, and were left through the wall beneath each landing-girder until the structure was very nearly completed. When the scaffoldings were lowered for the purpose of touching up the facework of the masonry, the spaces were filled with composition, as it was found that no further settlement was taking place. If a trifle more settlement did occur, the small amount of composition on the face would do no harm; it would easily be squeezed out, as it only extended about an inch from the face. The space for expansion was carried round the columns level with the lower sides of the landing-girders, and the masonry round the columns was not built continuously from bottom to top. Brackets were riveted to the columns level with the lower side of each landing-girder; and on them the masonry, which extended from one landing to another, was carried so that there was the same space beneath the brackets as beneath the landing-girders. The weight of the chains on the shore columns was much greater than the weight of the footways on the columns next the middle of the river; but the excess of weight from the upper structure was fully compensated by the excess of weight lower down, caused by the bascules which rested almost entirely upon the side of the tower next the river. Hence, combining the weights of the bascules and of the upper structure, the centre of the whole weight passed nearly through the centre of the pier. The bracings had been left

Mr. Cruttwell, about $\frac{1}{4}$ inch shorter before they were riveted up; but when the whole weight came upon them, the columns were squeezed down by an amount sufficient to render the holes fair. The stiffening-girder was placed specially for the object of taking the unbalanced force when one span was loaded and the other unloaded. With regard to the curve of the long segmental top boom not appearing satisfactory to the eye when lined in with the bottom boom of the short segment, he was unable to account for it, perspective being a rather curious thing, as had been seen in lantern views of the high-level footway. He could only say that the centre-line of the top boom of the long segment, if produced so as to join the centre-line of the bottom boom of the short segment, cut exactly the pin connecting the segments.

Mr. Homfray. Mr. HOMFRAY, in reply, said that the magnitude of the bridge had largely over-shadowed the importance of the hydraulic machinery; and he could not express his regret at the circumstance because it left him little to say, especially after Mr. Walker had pointed out the folly of cutting down too finely the power for moving important structures. But it was desirable to explain that when the machinery was designed, it had been considered necessary that the hydraulic power should be capable of moving the bascules against a wind-pressure of 56 lbs. per square foot, assuming the worst case—that of the wind acting over the whole surface of the bascules. It was also essential in machinery of that sort, that the parts should be as few and as simple as possible; and it was not advisable to employ too many units, and hence two units were adopted. For the same reason it was not considered advisable to use variable powers. The small engine, as had been mentioned, had always been sufficient, because at the Tower Bridge the force of the wind was not great, and he doubted if anything more than the small engine would ever be necessary. But rather more power had to be developed by a small engine than Mr. Rigg had suggested, to allow for all accidents. When one small engine was running, it had not only to run itself and to turn the bascule up and down, but had also to drive idle the other three engines; so that should the wind spring up or should it become necessary, a second engine could be coupled on, either in substitution for or in addition to the first engine; or the engines at the opposite end of the pier—the duplicate set—could be brought into action in case the first set should happen to fail. On each quadrant there were two racks, and each pinion-shaft carried on it four pinions; so that the power of the engine was really transmitted to the

bridge by means of four pinions gearing into four racks. The indicated HP. of each of the two pumping-engines was 360, and one of them was always in reserve. On one occasion the bridge had been opened twelve times and closed twelve times in two hours. He could not conclude without thanking the President for the way in which he had alluded to the services of Sir William Armstrong and Company and of himself. They could not have executed the work in a satisfactory manner, if it had not been for the very great consideration and attention that the President had always given to them.

Mr. J. WOLFE BARRY, C.B., President, in summing up the discussion, said perhaps the question of one span against three spans had not been quite understood. The dimensions of the Tower Bridge and the position of the central piers had, in point of fact, been settled by the way in which the river traffic was conducted through the upper and lower pool. Anyone acquainted with the Thames would see that the large vessels were moored almost continuously in what were technically called tiers, which is the local expression for a system of fixed moorings placed in two lines about 100 feet or 110 feet distant from the centre-line of the stream and parallel thereto. Sometimes there were two vessels and sometimes three abreast at these moorings, and usually barges were lying alongside as well. It was soon recognised by everybody concerned in the design of the Tower Bridge, including the Thames Conservancy advisers, that piers placed at a distance of 200 feet apart would be no obstruction to the navigation, seeing that they would be in the line of the vessels which were lying at the fixed moorings which had always been their positions, and probably would always remain there; if a central span of about 200 feet were provided, it would be practically as wide as the fair-way was for vessels passing between the rows of moored ships above and below the bridge. Regarded in this way, the position and size of the piers adopted was not a question of impeding the traffic in any way, nor was it a question of obstructing the flow of water, because although the vessels at high tide had water flowing under them, at low tide they were either touching the ground or had very little water below them. Further, the total width of the piers of the Tower Bridge was less than the sum of the widths of the piers of London Bridge. Thus there was no necessity for one span, which would have been much more expensive; and he thought that anybody who tried to put all the machinery of the opening span of the Tower Bridge on the bottom boom of the single-span bridge shown in

Mr. Homfray.

Mr. Wolfe Barry.

Mr. Wolfe *Fig. 2*, p. 66, and referred to in Mr. Matheson's remarks, would find that he had rather a difficult problem, and if there was a counterbalance in the scheme proposed, he imagined that it would come down into the water and obstruct the span. There was in truth no necessity for one span, and nothing to be gained by it; and the more economical plan of having two piers alignable with the ships at their moorings had therefore been adopted. With regard to railways across the river, north and south, he did not think they would come about in that neighbourhood for many years. The experience of the only north and south railway near the site of the Tower Bridge was anything but encouraging. That was the East London Railway, which passed through the Thames Tunnel, the traffic upon which had been very disappointing to those who had embarked their money in it, although it connected together such important systems as the Metropolitan and Great Eastern Railways on the north, and the Brighton, South-Eastern, and London Chatham and Dover Railways on the south. He did not think that there was much demand for a railway north and south across the Thames in this neighbourhood. At any rate, he did not believe that London would have been willing to wait until the extra million of money referred to as required had been subscribed in order that the bridge might be made suitable for some railway of the future. He wished to say a few words about the strength of the hydraulic machinery. Messrs. Sir William Armstrong and Company had been called upon to design machinery adequate for a wind-pressure of 56 lbs. per square foot, but he had appreciated at the time that such a pressure was excessive—that no such pressure was produced by wind on large surfaces in this country—that it never had been and that it never could be realized. They were, however, 'blessed or otherwise, by a department called the "Board of Trade," which had laid down a rule on what he thought must have been insufficient premises that all structures must be adequate to meet a wind-pressure of 56 lbs. per square foot, and he felt sure that there would not have been the smallest chance of Parliament authorizing the construction of a bridge on the bascule system, unless it had been shown that the requirements of the Board of Trade would be amply satisfied. The result, no doubt, was that the machinery under discussion was stronger than was really necessary, and more money had been spent than was really requisite; but for these circumstances, the fall of the Tay Bridge, which had introduced a great scare as to wind-pressure, had to be thanked, as it had been mainly instru-

mental in producing the dictum of the Board of Trade. Until this was altered, any engineer who was rash enough to design bridges without an allowance of 56 lbs. per square foot for wind, would run a great risk of his railway, or whatever structure it might be, being rejected by the Board of Trade as unfit for traffic. The question of wind-pressure upon large surfaces was so interesting, that he had been able to induce the Corporation of London to allow Mr. Cruttwell and himself to institute a series of careful experiments by self-recording wind-gauges; and he hoped that in a short time they would arrive with accuracy at some figures of actual pressures. He could not say that such figures had yet been reached; but they had in the rising and falling leaf of the bascules a wind-gauge such as he supposed had never been heard of before. It was, in fact, a wind-gauge with an area of 5,000 square feet, and they were able, by the gauges in the machinery-houses, which recorded the amount and pressure of the water used in each operation, to know precisely the differences of pressure required to raise and lower that large area against all winds from whatever direction they might come. By having ordinary wind-gauges fixed both on the high parts of the bridge and at the level of the roadway, they would be able to arrive at what was the mean recorded wind-pressure upon small areas; and by comparing the records of the small wind-gauges with the records of the large wind-gauge of the bascule-leaf, he hoped to be able to arrive at some figures which might be published at a future time. At any rate the subject was so extremely interesting that it was well worth much trouble in investigation. He would only say then that the results already arrived at showed that the falling off of pressure as surfaces increased in size, was so marked, that the fallacy of any general principle of providing for a pressure of 56 lbs. per square foot on surfaces independent of their size, would be a matter of proof in a short time. That might comfort some persons who were responsible for structures which ought to have been blown down and carried away like straws long ago, if any such pressure as half a hundred-weight on every square foot could have been exerted upon them by the wind.

Mr. Wolfe
Barry.

Correspondence.

Mr. E. W. ANDERSON asked if any automatic arrangements were provided between the accumulators and the engines, by which the latter were controlled when all the accumulators were full. This

Mr. Anderson.