Discussion.

The PRESIDENT, in moving a vote of thanks to the Authors, said The President.
he was sure the members felt that they were deeply indebted to the Authors for the very interesting descriptions they had given of what was, no doubt, the largest water-power installation in Great Britain. It was a question whether in this country what the French called *l'houille blanche* was being utilized quite as much as was desirable.

The AUTHORS exhibited a number of lantern-slides illustrating The Authors.
the construction and equipment of the works.

Mr. A. W. TAIT, Chairman of the Loch Leven Water and Mr. Tait.
Electric Power Company, observed that much of the matter in the Papers did not convey the same information to a lay mind as it conveyed to engineers, but, speaking on behalf of the Company, he could re-echo the thanks that had been given to the Authors for their Papers. His own connection with the Company did not date back to the inception of the scheme, which was carried out under the late chairman, Mr. John Bonner; but he had been closely connected with the Company for the past 2½ years, and had visited the works at Kinlochleven on several occasions. He could say, from his own observations as a layman, and also from the advice which had been obtained from other persons more qualified than himself to express an opinion, that the works had been carried out in the best possible manner. The thanks of the Company were due to Messrs. Thomas Meik and Sons, the engineers, to Messrs. Kennedy and Jenkin, and to Sir John Jackson, Limited, the contractors; and he would add that the Company desired to record their regret at the death of Mr. P. W. Meik shortly after the works were finished. During the past summer—an exceptional summer in this country—the works at Kinlochleven had been working to their full capacity, and it was believed they would continue so to work, and that the Company would get the utmost benefit from the installation as originally designed. That might be a question of academic interest to The Institution, but to the Company it was a matter of vital importance, because naturally the more power they obtained, the more of the commodity on which the Company's existence depended could be turned out. The works had been laid down in a district where formerly there was practically

Mr. Tait. no habitation at all; and now the Company employed a large number of men and circulated in the district about £50,000 a year in wages. It was, he thought, greatly to the credit of the engineering science of the country that it had been able to do that, and to foster an industry of such importance.

Mr. Meik. Mr. C. S. MEIK remarked that, before the pressure was first put upon the Blackwater dam, cracks appeared, and the water subsequently came through those cracks. That he thought was, as Mr. Roberts pointed out, the effect of contraction, due mainly to the dam having been constructed rather more quickly than it ought to have been. The last time he was on the spot, about 18 months ago, practically no water was coming through the dam; showing that all the cracks had closed up. He thought that was due to the presence of a considerable quantity of sediment in the water, which lodged in the cracks and filled them. A good deal of deposit came through these cracks and appeared on the face of the dam; he presumed it was carbonate of lime, resulting from the free lime combining with the carbonates in the water. It appeared that in the cement used in the dam, which was of the highest quality, there was free lime; and in his view it was impossible to obtain cement which did not contain some free lime. With regard to the overland route, it would be seen from the plan (Fig. 2, Plate 1), that the contractors built first an overhead cableway: this was put up owing to the ground being very uneven and rough, and in the expectation that it would meet the circumstances of the case. The cableway, however, took a long time to erect, and it did not quite meet the conditions, as it could not carry the whole of the material necessary for the dam and the conduit. Before the works were finished the contractor had constructed an overland route for the greater part of the way. That was not contemplated originally, but was found to be necessary; and he thought the work would have been expedited somewhat if the overland route had been adopted at the beginning. Cableways were possibly of advantage in rough, mountainous countries; but if he were a contractor he would not put up a cableway for works of this magnitude, as it could not carry sufficient material to keep them going at the necessary speed. As stated in Mr. Roberts's Paper, the weight of the concrete had not come up to expectations. The anticipated weight was 150 lbs. per cubic foot, and on that basis calculations were made for the profile of the dam, the formula followed being, if he recollected rightly, practically Molesworth's. The first batch of concrete made was found to weigh only a little more than 140 lbs. per cubic foot, and consequently the engineers thought it desirable

to increase the width of the dam at the bottom, in order to make up for the deficiency in weight. There was no reason whatever why concrete should not weigh 150 lbs. per cubic foot with proper care in the grading and the making. He himself had frequently obtained specimens of concrete that weighed more than 150 lbs. per cubic foot. When dealing with a large mass of concrete, as in the case of a dam such as that described in the Paper, it was not easy to get an alteration made in the method of construction after the contract was let, and prices and conditions were fixed. Under the circumstances, he thought the engineers had adopted the wisest course in increasing the width of the dam. If, however, he ever had the fortune to construct another dam similar to that under discussion, he would certainly endeavour to obtain much heavier concrete. The most important factors in the construction of a dam of that kind were the density and crushing-stress of the concrete. The denser the concrete, the higher the crushing-stress, and consequently the more economically the dam could be constructed. In experiments made recently with 4-to-1 concrete of crushed granite and sand, similar to that used on the outside of the Blackwater dam, he had succeeded in getting 158 lbs. per cubic foot. If the dam had been of masonry, possibly there would have been no difficulty in getting 150 lbs. per cubic foot or even more; for where large blocks of heavy stone, such as granite, were used, the weight per cubic foot was naturally greater. The village dam certainly had a much better appearance than the Blackwater dam, and the asphalt joints had not affected the strength of the structure. With regard to Mr. Roberts's suggestion that it might be advisable to use such joints in larger dams, Mr. Meik would have no hesitation in using them in such a case as the Blackwater dam. The foundations there were exceptionally good, and the joints would have done no harm; but had the foundation been less satisfactory, it was a question whether the joints might not have interfered with the homogeneity of the dam. As it turned out, the dam was perfectly watertight, although, perhaps, a little unsightly in appearance. In order to avoid the appearance of defect in a dam of that description, he would suggest that the two fronts should be reinforced, vertical joints made in the facing, and the facing caulked. The parts between the joints might be reinforced, so as to get over the difficulty of the cracks: any expansion would then be taken up by the joints, which might be caulked before the water was let in. Some improvement might possibly have been effected in the Blackwater dam by providing internal drains to take off any leakage-water that

Mr. Meik. came through. The question of expansion-joints also applied to the conduit. Mr. Roberts pointed out that in between the expansion-joints, which were 64 feet apart, cracks appeared, due to the shrinkage of the concrete immediately after construction. Those cracks took up afterwards, and had no effect at all upon the strength; but they would have been avoided, Mr. Meik thought, if longitudinal reinforcement had been put in. The reinforcement used in the concrete was of expanded metal, with the strong part of the mesh in a vertical direction. Expanded metal in a longitudinal direction was of little advantage for reinforcement, but it might have been of advantage to put in some longitudinal reinforcement, as it would have obviated the cracks which appeared between the joints. With regard to the pipe-line, before a decision was come to the question arose whether riveted or welded pipes should be adopted, and the Company decided that it would be well to see what had been done in other places. With Mr. Murray Morrison, at that time the technical adviser of the Company and now the general manager, he went to the Continent to see pipe-lines already erected, and among the places they visited was a water-power station at Gronio in the Serriana Valley, near Milan, where they saw welded pipes made by the firm that afterwards supplied the pipes for Loch Leven. These pipes appeared to be of remarkably good construction, and it was mainly owing to what was seen there that the engineers decided to recommend a welded pipe. The pipe at Gronio was 26 inches in diameter, as against 39 inches at Loch Leven. It was working under a head of 325 metres (1,070 feet), and was absolutely watertight throughout; in fact, nothing could be heard or seen, and there was no indication whatever that any water was passing inside. That pipe had the same "muff" joint as was afterwards adopted at Loch Leven. The muff joint had been perfectly successful; it had given no trouble, and practically required no attention until the pipes were emptied, when the joints required adjustment. Also it had the advantage that it acted both as a pipe-joint and as an expansion-joint, and so saved all trouble with special expansion-joints. After Mr. Morrison and he visited the Continent they saw some experiments made in England in which the muff joint was tested up to 640 lbs. per square inch; and they also saw the "Manchester" joint, which was no doubt familiar to the members, tested to a high pressure. Both joints stood the test remarkably well, but the muff joint, being the simpler of the two, was adopted; and he thought the results had quite justified the engineers' advice. From a patriotic point of view, he wished that the pipes had been made in England, but at

that time the Company had no option but to go abroad for them. Mr. Meik. What was seen at home did not encourage them to place the order with any of the English makers, who had neither the necessary plant nor experience of large welded pipes. Apart from the price—though that was a consideration—he thought the engineers had been justified in recommending the Company to adopt the German pipes, and he believed the Chairman of the Company would bear him out in this view.

Mr. BERNARD M. JENKIN observed that when Mr. Sonnenschein was Mr. Jenkin writing his Paper he suggested to him that it might be interesting to The Institution to record the experience gained in testing and starting the plant, rather than to give only a description of it. It was only fair to the contractors to mention that, as otherwise it might seem on reading the Paper as if there had been a great deal of trouble, when really there had been no more trouble than was usual when starting new plant. It was the experience gained that was of interest to engineers. All the troubles had been dealt with by the contractors in an entirely satisfactory way, so as to reflect credit on them for the manner in which they had finished the work. With regard to the tests, the resistance placed in the tail-race had proved a very good form of load indeed. There was an absolutely steady flow of water at any given load: the water came from the turbines past the resistance to the weir, and therefore kept the current perfectly constant, and in that way the load on the generators was extremely steady and the measurements were rendered simple. It was a much better load than could possibly have been obtained by the ordinary resistance in water that had not that constant cooling effect due to the flow. With regard to the governing-tests, the Paper perhaps did not indicate the difficulties involved. The machines were of fair size (2,000 kilowatts), and throwing the load on and off had to be done with care, particularly before the governors were adjusted. Especial care had to be taken that the water-pressure at no time exceeded the permissible pressure in the pipes. By throwing the load off, the pressure in the pipes was raised, and until the governors were adjusted, the safe pressure might easily be exceeded and disaster result. One or two things had happened that were not mentioned in the Paper. For instance, in connection with the governor, which was driven by a belt, there was a danger that the belt might come off or break, and two belts were actually provided, to make sure that if one broke the governor would at least still control the turbine. But at a very early stage, soon after the plant was erected, the bearing of the pulley-wheel on the governor driven by the belt heated and seized and threw both belts off, so that the turbine

Mr. Jenkin. was no longer under the control of the governor, and naturally it began to race. Luckily the fitter had the presence of mind to press one of the levers, so as to stop the turbine. But for that, the turbine could not have been stopped in time. In consequence of this incident the small valve at the bottom of the controlling cylinder was fitted, so that the turbine could be shut down instantly by hand. As to the actual governing-curves shown in Fig. 7, Plate 3, a condition was met with that he had not anticipated, and which he thought was of interest. Naturally, in throwing off load the worst condition was throwing off full load. That was shown by the curves BB and B'B', which showed the fluctuation in the pressure of water in the pipes when the load was thrown off. But in throwing on load the most difficult condition that had to be dealt with was at about 1,000 kilowatts, or less than half-load. The curves AA and A'A' showed the fluctuation in pressure between maximum and minimum in throwing on load to be even higher at 1,000 kilowatts than with 2,000 kilowatts thrown off. On consideration the reason was obvious. When the load was thrown on the turbine slowed down—it had not a very great fly-wheel effect—and the governor opened the nozzles fully; a rush of water came down the pipe through the fully-opened nozzles, gaining in speed, and the governor cut off the full supply of water when it was coming at the maximum speed in the pipes. Throwing on full load was not so bad, because once the load was put on, the nozzles were opened fully and kept open, and therefore there was no rise in pressure. With reference to the generators and the device shown in Fig. 9, Plate 3, it might be pointed out that under normal conditions the two generators driven by one turbine were running in parallel, and generators were commonly worked in parallel without difficulty. In the present case, however, the two generators were driven by the same shaft—a rigid shaft between the turbine and the two generators—which, of course, was not the usual condition of running generators in parallel. Where they were driven by two turbines or engines, the speeds of the generators could adjust themselves slightly so as to share the load, and when the load was thrown off they could adjust their speeds independently. But when the two generators were on one shaft they could not adjust their speed independently. When running on load one generator might have a slightly heavier load than the other, which would mean that its excitation was slightly stronger. When the load was thrown off, the generators being coupled together, there was no disconnection between the two commutators, and the fact that one generator had a greater excitation than the other meant that, when the load was thrown off, its

voltage would rise slightly higher than that of the other generator, Mr. Jenkin. and consequently the one machine would generate and force current into the other, and would reverse the current in the other machine and make it run as a motor. The generators could not adjust their speeds independently. The one that was acting as a motor had to continue to run at exactly the same speed as the generator, and there was a current through the two machines which could not choke itself down in any way. The result was that the motoring machine naturally sparked, as the brushes had a lead, and trouble might arise in consequence. In order to overcome that difficulty, which had not been foreseen by him, the cut-out device had been put in, and it worked quite satisfactorily. Another method would have been to put big automatic switches in the main circuit, but that was expensive and difficult to do, whereas the little device that cut out the field-circuits acted perfectly well in taking care of the two machines under those conditions. He had since heard that abroad it was common practice, with turbines and generators for similar work, to do without any governor at all. When the main load was thrown off by the furnace-circuit breaking, they simply let the turbine and the generators run away and the voltage go up, and when the circuit was made again the speed and voltage came down again to the normal. It seemed a crude method, but it was said to work admirably, and it certainly overcame the difficulty of a complicated governor.

Mr. M. A. POLLARD-URQUHART remarked that when his firm, Mr. Pollard-Urquhart. Messrs. Thomas Meik and Sons, were consulted regarding the scheme they examined the proposals authorized by the Act of 1901. These provided for a tunnel on the north side of the Blackwater valley from the dam to a point below Loch Eilde Mor at a level of about 1,020 feet above sea-level. Provision was also made for using the water of the Loch Eilde basin about 1,200 feet above sea-level. Having considered all the circumstances obtaining at that date and made careful survey of the ground, they recommended the abandonment of tunnels on the north bank and the substitution of open conduit on the south bank. The position of the conduit had been fixed in reference to the levels of the ground to avoid excessive excavations. The fall of the conduit was 1 in 1,000, but on curves the slope was increased a little to preserve uniformity in the velocity of the water. The latter averaged about 7 feet per second, which was considered to preclude any chance of freezing. On the recommendation of Sir Alexander Binnie it was decided to cover the conduit. This ensured the protection of the water from detritus from the hillside and afforded a further protection against freezing.

Mr. Rutter. Mr. H. F. RUTTER remarked that he took a great interest in the Loch Leven works because he knew the country pretty well and had had the pleasure of visiting the works while they were under construction, and discussing them with his friend Patrick Meik, whose death everyone regretted. In works of such a character, which had admittedly fulfilled the purpose for which they were designed, there was not a great deal of room for criticism. When he first saw the profile of the pipe-line he had a little misgiving with regard to the wisdom of the hump at C, knowing something about the way in which air in water freed itself when the pressure was released, and knowing also something about the vagaries of so-called automatic air-valves. However, no difficulties had been mentioned, and he presumed the difficulties which he had apprehended might arise had not in fact arisen. Perhaps the Author in his reply would be kind enough to say whether the pipe-line had been found to be subject to any of those rhythmic vibrations which in other pipe-lines, both in America and in Italy, had led not merely to trouble, but to actual disruption of the work. Also it would be interesting to know whether the automatic air-valves had fulfilled their functions. With regard to the way in which the steel pipes had been treated, it was stated in Mr. Roberts's Paper that they were originally coated with a solution similar to Dr. Angus Smith's, and that after they were fixed they were painted on the outside with a bitumastic solution. He thought the inside of pipes really deserved as much attention as the outside, and he was a little surprised that no special precautions seemed to have been taken at least to retard the oxidation that would inevitably occur. During transit and fixing the pipes were necessarily subjected to rough treatment, causing extensive abrasion of the original coating; and he would like to know why the pipes had not been repainted with some durable composition before they were fixed. He was the more surprised that some such measures had not been taken because the water, freely charged with atmospheric air and containing necessarily a large amount of vegetable acids, was especially liable to attack steel. He did not make those remarks with the idea of disparaging steel pipes. He had been responsible himself for putting down a good many; and, provided they were properly coated inside, he thought they would be found to be reasonably durable. A short time ago he had to cut out a steel pipe which had been fixed and in constant use for 18 years. He had no record of the material with which the pipe was originally coated, but he had reason to believe that it was some form of tar varnish. When the pipe was cut out no trace of the original

coating was found, and the whole of the interior of the pipe was covered with carbuncles ranging from $\frac{3}{16}$ inch to $\frac{1}{4}$ inch in height, each carbuncle having a complementary pit in the steel below. The pipe was 21 inches in diameter, and the condition found meant a considerable reduction in the cross section of the pipe and probably a quadrupled coefficient of friction. Was it not to be feared that similar effects would arise in the Loch Leven pipes and that the commercial efficiency of the plant would suffer in consequence?

Mr. W. MURRAY MORRISON wished first to add his tribute to the memory of the late Mr. P. W. Meik. To know Mr. Meik professionally was to form a very affectionate feeling for him, and both he and the Company mourned Mr. Meik's loss. He would also like to say, with regard to Mr. Roberts and his excellent staff, that about a year ago he had the privilege of showing over the works a well-known contractor, who had had great experience in all parts of the world. This gentleman was full of praise for the work, and said: "I do not happen to have met Mr. Roberts, but he must be a very good man, and the work speaks volumes for him." Turning to Mr. Roberts's Paper, it might be interesting to give some figures he had compiled as to evaporation. The works were only started in March, 1909, and the figures for that year were rather uncertain, but he had reliable figures for 1910 and 1911. As the whole drainage-area had never been surveyed, the figures might be somewhat variable; but when dealing with many thousand millions of cubic feet the error could not be very large. There were two sources of error, namely, the capacity of the dam and the average rainfall for the whole area. Taking the year 1910, allowing for the actual quantity of water used in driving the plant—a figure which, of course, could be ascertained definitely—allowing for the increase in storage-capacity which took place during the year, and allowing for the loss over the weir, he found that the loss by evaporation, including a certain quantity of water spilling over the side-stream intakes, and a little over the waste weirs at the beginning and end of the conduit, came out at 6 per cent. of the total rainfall during the year. In 1911, up to the end of September, the figure, ascertained in the same manner, was a little more than 10 per cent. Those figures were much smaller than was originally contemplated. He believed that in the first instance Mr. Meik, to be on the safe side, estimated the evaporation alone, without any flood-losses, at 20 to 30 per cent. He was inclined to think that the capacity of the dam was somewhat greater than had been estimated. From curiosity he had taken out figures for a period of 14 days during which only $\frac{1}{4}$ inch of rain fell. Immediately before there had

Mr. Morrison.

Mr. Morrison. been a series of dry days, and for at least a week previously no rain at all had fallen. Working out the balance-sheet in the same way, he found that sufficient water was gained to account for another 0·6 inch of rainfall. It would appear that either the rainfall was greater than the average of the various stations, or else the capacity of the reservoir was somewhat larger. At Kinlochleven there were very few periods without any rain at all. During 1911, for example, there had been only fourteen consecutive days during which no rain fell, and the same remark applied to 1910, while in 1909 there were only ten consecutive days. There were, however, periods of considerable dryness, and two such periods had occurred during 1911. In March and April there was a period of 29 days when only $\frac{1}{4}$ inch of rain fell, and in May and June there were 22 days when slightly less than $\frac{1}{4}$ inch fell. In spite of that, the plant had been working practically at full capacity, and the maximum quantity drawn from the dam at any one time had been rather less than one-third of the calculated capacity. At the Foyers works of the same Company some rather curious results had been found. Only one-third of the total drainage passed through the reservoir, the other two-thirds passing straight into the river, and the flood-losses were very considerable; but in spite of that, during several years 63 per cent. of the available water over the whole drainage-area had been obtained. On p. 32 Mr. Roberts mentioned that the whole of the rainfall was thrown off within 2 days from the cessation of the rain. That time-lag, in Mr. Morrison's experience, was a maximum. It depended very much upon the state of the country—whether the ground was in a wet or a dry condition—but under the most unfavourable conditions it never took longer than 2 days; and sometimes the time-lag was practically absent. He happened to be at Kinlochleven 3 weeks ago, when there was very heavy rain during the week-end, and in 24 hours, in addition to running the plant, sufficient water was stored to run the whole plant for another 3 weeks. To sum up the experience so far, it seemed that the rainfall was probably a little more than the average shown by the gauges; that the evaporation was less than had been calculated upon; and that probably the capacity of the dam was greater. It was hoped, therefore, to find that the power available was somewhat in excess of the original anticipation. The number of gauges was being increased and snow-gauges were being added. The figure (5·59 inches) which Mr. Roberts gave as the heaviest rainfall in any one day during the construction of the works was still a record, the highest since having been about 4 inches. The saving effected by not providing a dressed granite surface to the spillway

was amply warranted, as the water followed exactly the parabolic curve. He regretted that during construction a number of thermocouples were not left in the heart of the dam, as it would have been very interesting to take records of the temperatures during the cooling of the dam. From the work already done upon the subject he believed that the temperature in the interior of a dam remained fairly high for a considerable period. The remarks made as to the weeping of the dam read as though it were considerable. There were certainly a number of very small weeps that disfigured the dam, but as there was no one to look at it except occasional engineers, sportsmen, and deer, he did not think that mattered much. At the worst time he did not think the whole of the water coming through was much more than sufficient to fill a $\frac{1}{2}$ -inch or $\frac{3}{4}$ -inch pipe under a comparatively small head, and there was now no perceptible evidence of weeping. The valve-house was built of Dumfriesshire sandstone, a handsome stone, but one against which he would warn engineers. It was very porous, and although it had been coated a number of times with waterproofing solution, it was not yet thoroughly watertight. The figures given with regard to Kutter's formula were exceedingly interesting, because it was not often that engineers had the opportunity of testing that formula. The results obtained spoke very well for the accuracy of the formula and the construction of the conduit. Adopting the mean value obtained for n , it would be found that the discharge of the conduit was about $2\frac{1}{2}$ per cent. better than had been calculated. In passing he might remark that the same result had been obtained in a scheme which his Company had in Norway. With regard to the side-stream intakes, he believed the regulating device Mr. Roberts referred to was due originally to Mr. L. John Groves, Assoc. M. Inst. C.E., the engineer and manager of the Crinan Canal, who told him some years ago that he had had automatic valves of exactly the same type at work on the Crinan Canal for many years, with entirely satisfactory results. The experience at Loch Leven was similar. The friction-loss in the pipe-line was estimated very carefully at the time when the diameter of the pipes was settled. When more units than were now installed in the power-house were worked off those pipes, the loss would be about 3 per cent.; at the present moment it was a little more than 2 per cent. The friction-loss had been arrived at after estimating very carefully the additional cost of reducing it to so low a figure, the additional profit to be realized from the extra product, and the interest that that additional profit would return upon the capital. The directors of the Loch Leven Company had been

Mr. Morrison. severely criticized for placing the order for the pipes in Germany; but he would endorse all that Mr. Meik had said in defence of that course. It had been a question not of price but purely of experience. The English makers at that date certainly could not have made pipes of the kind required. It should be borne in mind that the total weight of pipe in the pipe-line was about 6,000 tons, and the pressure due to the static head was about 430 lbs. per square inch. There were many intricate bends, and considerable difficulties which could be overcome only by someone who had had much experience in the making of pipes for high-pressure work; and he thought the Company had acted rightly in going abroad for the pipes at that particular period. After having worked them for more than 2 years he was pleased to be able to say that the whole of the maintenance—the patrolling of the pipes, the repairs, the recoating of little bits here and there with composition, and the occasional taking-up of joints—had cost only 0·0002*d.* per unit generated in the power-house. The late Lord Kelvin had been in entire agreement with the course adopted. The movement in the whole pipe-line was about 20 inches in each pipe, due to the range of temperature to which it was subjected. He believed the form of distribution pipework to be entirely novel. It was due to Sir Alexander Kennedy, and had been worked out on the electrical plan; hence the term “bus pipe.” The total expenditure of the Company on the whole of the undertaking was about £1,250,000. Of course, in addition to the works described in the Papers there were very large factories fully equipped, an extensive village, and other buildings, etc. The works were thoroughly satisfactory in every respect, and reflected great credit on the Author, on the engineers who designed and carried them out, and on every one connected with them.

The work described in Mr. Sonnenschein's Paper had been carried out under the direction of an honoured Past-President of The Institution, Sir Alexander Kennedy, ably assisted by his partner, Mr. Jenkin, the Author being their very capable resident engineer, whom he heartily congratulated on the excellence of his Paper. It was not too much to say that the power-house was, in all its details, one of the most efficient to be found in the country, and even Sir Alexander Kennedy, with the many power-houses he had designed, would have no hesitation in accepting that view. The difficulties in starting the plant had been exceedingly small. The curves given by the Author were very useful to water-power engineers. The output of the plant at the present moment was upwards of 150 million units per annum. In order to give some idea of what that meant, he might quote a few figures relating to other electrical installations, taken from public sources. The

London County Council used in a year practically 97 million units; Mr. Morrison. Glasgow, for trams and lighting, 63 millions; Liverpool, 36 millions; Manchester, 83 millions; Dublin, 16 millions. Taking all the local authorities and the companies in London, for both lighting and power, the total figure, as published, was 235 million units per annum. In Mr. Garcke's "Manual of Electrical Undertakings" for 1911 the electrical energy generated for traction and other purposes in the working of electric railways in the United Kingdom during 1909 was given as 253 million units. Kinlochleven, therefore, compared very favourably, with its 150 millions. In November, 1910, Mr. S. Z. de Ferranti, in his Presidential Address to the Institution of Electrical Engineers, gave some idea of what the running-costs might reach in England on a colossal scale. He assumed 25 million kilowatts of plant spread over a hundred stations, each having ten units of 25,000 kilowatts each, and on that basis, assuming a load-factor of 60 per cent., and a return on capital, for both interest and depreciation, at the rate of $8\frac{1}{2}$ per cent., he worked out a figure of 0·0776*d.* per unit. The works-costs he put down at 0·036*d.* per unit, the total being thus 0·1136*d.*, or practically $\frac{1}{8}$ *d.* per unit. Mr. Morrison had taken out the costs of the Kinlochleven undertaking, considered purely as a power-scheme, that was, without any of the subsidiary expenditure, which was very large. Looking at it, of course, from a trading company's point of view, and not from the point of view of a public company who might be governed by the Local Government Board or other authorities, he had taken 5 per cent. as the interest on the whole capital, and depreciation at the following rates:—On the dam, 1 per cent.; on the conduit, 2 per cent.; on the preparation of the pipe-track and the anchorages, 1 per cent.; on the pipes themselves, 3 per cent.; on the power-house buildings, 2 per cent.; and on the whole of the power-plant (turbines, generators, and accessories) $7\frac{1}{2}$ per cent. He found that the total cost, capital charges, running-charges, oil, waste, stores, etc., beginning at the dam and ending at the switchboard, was at the rate of about $\frac{1}{8}$ *d.* per unit. In 1910 it was almost exactly $\frac{1}{8}$ *d.* per unit, because the whole of the plant was not in operation then. The station load-factor was extremely high, approaching unity; in fact, for individual machines it was rather better than unity. Of the $\frac{1}{8}$ *d.*, labour (beginning at the dam and finishing at the switchboard), repairs, oil, waste, stores, and other incidental charges properly attributable to power-house working, accounted for 0·00457*d.* per unit. The brush-renewals included in this accounted for the wonderfully low figure of 0·00012*d.* per unit. The capital charges were by far the largest item.

[THE INST. C.E. VOL. CLXXXVII.]

H

Mr. Morrison. When a further unit was added, he estimated that the total cost should not be more than about $\frac{1}{18}d.$ per unit, and probably when power was developed up to the full capacity of the present pipes they would be within measurable distance of seeing $\frac{1}{20}d.$ per unit cover all expenses. These figures gave some indication of what could be achieved by water-power.

Mr. Binnie. Mr. W. J. E. BINNIE thanked the Author for the kind reference in the Paper to his father. Sir Alexander Binnie had been anxious to take part in the discussion that evening, but he was, unfortunately, laid up with a cold and could not attend. It would be very useful if a Table could be given showing the rainfall, the water passing over the waste-weir, the additions to or deductions from the stock of water in the reservoir, and also the power drawn day by day or week by week, so as to show what the flow off the drainage-area had been, especially during the present year. A large number of records had been obtained in the endeavour to work out the most economical storage-capacity for reservoirs. Originally it had been worked out practically on the data obtained from Midland drainage-areas, but in Scotland and other places the ordinary rules often did not apply. He had had to investigate, for instance, one stream where the variations in flow off a granite drainage-area were extremely small, the decomposed granite on the top acting as a natural storage-vessel. It was obvious that the contents of the reservoir must depend on, among other things, the minimum dry-weather flow. From the records that appeared to have been kept at Kinlochleven it would be possible to determine the minimum dry-weather flow of the drainage-area, and it would be useful if Mr. Morrison would put in a Table which would enable waterworks-engineers to arrive at such figures. There did not appear to him to be sufficient provision for depositing the detritus brought down by the various side streams. With regard to the deterioration of steel pipes, he had had to investigate the corrosion of the Coolgardie pipe-line, 350 miles long. The original Commission (of which Dr. Unwin was a member, together with the late Dr. G. F. Deacon and Mr. J. Carruthers) which reported on the scheme recommended that the pipes should be coated on the ground after they arrived in Australia, because it was realized that in transit and while lying about in Australia the coating would deteriorate a good deal; but that was never done. The pipes, which ultimately were made in Australia, were simply dipped once. Consequently, 4 or 5 years after the main was laid, it was completely perforated in places. When the interior coating—or rather, what was left of it—came to be examined, it was

seen that all the more volatile constituents had been removed, and Mr. Binnie. that the coating was as porous as a sponge. It was therefore essential that steel pipes should have, where possible, another coating on the inside after they were laid. Such pipes were so elastic that the movements which took place in them before they were finally put into position were sufficient to cause the ordinary coating to peel off.

Mr. G. E. L. POULDEN considered that it would be interesting to Mr. Poulden. know what the connection was between the concrete and the surface of the rock beneath the dam. It was stated that the rock was particularly good, with no fissures, but it was to be presumed that some connection had been made between the rock and the concrete, perhaps by a coating of neat cement. The excavation in the rock shown in Fig. 3a, Plate 1, might presumably, except for the natural precaution exercised in taking off the surface of the rock, have been given a slight gradient towards the water-pressure, and part of the excavation might have been saved. With regard to the cracks in the dam, he would like to know whether they appeared on any lines which could be recognized as representing stages of the work; also whether the displacers were in any way responsible for the slight leakage, and whether the cracks were the same size on both sides of the dam. The water conveyed to the village and used by the inhabitants, would, he thought, be of a peaty character, in which case it might affect lead pipes. He also desired to know whether any magnetic disturbances had been observed with a long line of exposed pipes. An article had appeared recently relating to experiments in France, where hail-storms had been entirely done away with in various districts by the erection of lightning-conductors. The theory appeared to be somewhat complicated, but the results had been exceedingly satisfactory, as the hail had apparently been dispersed at distances of 5 kilometres in the direction of the wind and 3 kilometres on either side. Turning to the generators, the kinetic energy appeared to be excessive. It was mentioned that the conductors in the system of distribution about the village, and possibly on the railway, were of aluminium strip. The specific conductivity of aluminium as compared with copper was, roughly speaking, about 1 to 2. It was to be supposed that the aluminium was supplied by the Company at the time when the process of manufacture had not been improved, owing to the works not being completed, so that the comparative bulk of aluminium as used and the system of insulators must have considerably enhanced the cost of distribution as compared with copper conductors. With regard to the wave-diagram shown in

Mr. Poulden. Fig. 1, Plate 3, he ventured to criticize the position of the measuring-staff. The gate was worked apparently by a small capstan, but, as was well known from experiments carried out by Stevenson and others, a wave coming against a solid structure did not go back in a natural manner, but fell back into the trough. When it reached the weir it cushioned into water. So that possibly the heights taken on the measuring-staff, in the position shown in the diagram, would admit of a little criticism.

Mr. Thomson. Mr. T. FRAME THOMSON had read Mr. Roberts's Paper with probably more pleasure than he had ever read any other Paper. The conditions existing for the hydraulic development at Loch Leven seemed to be as nearly as possible ideal in every respect. The rainfall was heavy, the catchment-area was one which yielded the maximum result from the rain which fell upon it, there was a high head, and there was not too great a distance between the reservoir and the station. It was all the more interesting to him because he had been intimately associated for some time past with a hydraulic development in South America, where the conditions were in many respects the converse. He had been particularly interested in pages 29 and 30, where Mr. Roberts dealt with power-schemes contrasted with domestic supply, because that was one of the problems he had had to face in the South American scheme, namely, how to develop some industry which would utilize power with sufficient elasticity to permit of changes in the amount of labour without undue additional expense, and without completely upsetting the market of the industry. So far as he had investigated the matter, he could not say he had come to any satisfactory conclusion yet. Perhaps Mr. Roberts might be able to follow up what he said in the Paper with a few more detailed suggestions resulting from the consideration he had given to the problem. Mr. Thomson concluded, from the figures given by Mr. Roberts, that the actual power developed, in relation to the rainfall, was very high indeed; he inferred, from the way in which the designs had been laid out, that it might be nearly 100 per cent. In the case he had in mind, the water was taken from a large dam impounding about two-and-a-half times as much as that at Loch Leven, and having a drainage-area of 520 square miles. At Loch Leven the average annual rainfall over the whole area was, he understood, about 280 cubic feet per second, whilst in the case he had in mind it was nearly 1,000 cubic feet. But, having regard to the fact that the water had to be subservient in the South American case to the requirements of irrigation, and a domestic-lighting supply had to be given, although 34 per cent. of the entire rainfall over the area went to the river, only about

17 per cent. was available for useful power. Any development of the idea suggested by Mr. Roberts on p. 30 would entirely revolutionize the position of the question of supplying power for manufacturing purposes. There were one or two curious points in common between the two dams. The South American dam he referred to was in Cordoba, in the Argentine Republic, and was built by the Provincial Government about 20 years ago. He thought it was very much to the credit of a South American republic that one of its Provincial Governments should have built, 20 years ago, a dam impounding two and a half times the quantity of water in what was said to be the largest reservoir in Europe. There could hardly be a greater tribute to the progressive nature of South American governments than the fact that Argentine engineers had carried out this work so long ago. The reservoir was situated at exactly the same level above the sea as the dam at Kinlochleven, namely, 1,060 feet at the highest level. In a recent development of the power the designs had followed almost precisely the course Mr. Roberts had indicated. Mr. Roberts began with an estimated flow equivalent to 52 inches of rainfall, which was about 13,000 cubic feet per minute, and ultimately the designs were varied so as to give about 30,000 cubic feet. The South American designs began with about 17,000 feet per minute, and were ultimately varied to 32,000 cubic feet. The size of the conduit was different. At Kinlochleven it was 8 feet by 8 feet, while in the Argentine it was 13 feet by 8 feet; but that was accounted for by the difference in the gradient, which was 1 in 1,000 at Kinlochleven and 1 in 2,000 in the Argentine. There was no doubt about the superiority of the conditions in the former case, as there was everything necessary for developing power at a satisfactory capital cost and for proper working. In connection with the study of the relationship between the rainfall, the discharge, and the quantity of water available for production of power, he had tried to devise a rough formula which would give the contents of a reservoir at different levels. Translating it into English measurements, he found in the case of the Argentine dam that the conditions corresponded fairly closely with calculating the contents in gallons from the expression $220,000 h^{2.6}$, where h was the maximum depth of water at any given surface-level; that formula applied very well to the different levels at which the contents of the reservoir had been ascertained. Acting on the same principle, the coefficient for the Kinlochleven dam would be 264,000, taking the maximum depth as 75 feet. This figure was roughly confirmed by the data given in connection with the rainfall of 3.92 inches at the dam, which was

Mr. Thomson. about 3,000 million gallons over the area, and raised the water-level of the reservoir 36 feet. He would be very much interested to know from Mr. Roberts whether the expression $264,000 h^{2.6}$ conformed to any of his actual figures, as the coefficients seemed rather to indicate the relative efficiency of the two areas as reservoirs. The idea might be a little fanciful, but sometimes such fancies turned out to be of practical value. Mr. E. P. Hill, in his Paper "On the Yield of Catchment-Areas,"¹ had made a plea for the measurements of hydraulic installations being co-ordinated with the rainfall, and Mr. Thomson gathered that that had been done at Kinlochleven. He had always felt that a good deal of the empiricism that still governed the correlation of such data would be removed if some of the large undertakings which had opportunities for observation would make public the figures they had obtained. That remark he would address particularly to Mr. Murray Morrison. With regard to floods, in the Argentine case, on the 10th April, 1903, there was a rainfall, registered at the dam, of $7\frac{1}{2}$ inches over the catchment-area of 520 square miles. On the previous 9 days there was $1\frac{3}{4}$ inch over the whole area, making in all $9\frac{1}{4}$ inches, which was equal to $56\frac{1}{2}$ million gallons. On the 12th and 13th April, two days after the heaviest rainfall, the contents of the reservoir were increased by $21\frac{1}{2}$ million gallons, or 38 per cent. of the gross quantity of water the rainfall would have given over the catchment-area.

Mr. Roberts. Mr. ROBERTS, in reply, observed, with reference to Mr. Meik's remarks about the cracking of the concrete, that the more important cracks took place before the water came against the dam, which seemed to show that they were principally due to the cooling down from the high setting-temperatures. He had made observations of the temperature of concrete in large masses during construction, which indicated that heat was sustained in the mass for periods which amply sufficed for the hardening of the concrete. The result was that when the cooling did eventually take place, there being practically no elasticity left, the contraction caused exceptionally pronounced cracks. In thin walls this initial heat was rapidly dissipated and the cracking was greatly reduced in degree. He was much interested in Mr. Meik's suggestion to reinforce the faces and provide joints in them; but he was of opinion that contraction in the centre mass of the dam would still produce cracks in the body. If contraction-stresses were distributed in the facing (by

¹ Minutes of Proceedings Inst. C.E., vol. clxvii, p. 181.

reinforcement) and not in the hearting he feared there would be a Mr. Roberts. tendency to produce longitudinal hair-cracking between the face-work and the hearting, which appeared to be undesirable. The new Ashokan dam for the New York water-supply was built with expansion-joints about 80 feet apart, consisting of "straight" joints right through the dam but bonded in the interests of longitudinal continuity. The contour of the ground necessitated the presence of the hump at point C (Fig. 10, Plate 2) to which Mr. Rutter had alluded. Three other alternative routes for the pipe-line had been carefully surveyed but found impracticable. Under the conditions existing at Loch Leven there seemed to be little likelihood of trouble now that the plant had been started. But during the process of getting the pipes and turbines to work, adjusting governors, valves, etc., while every possible precaution was taken to minimize shocks, he kept a specially close watch upon the pipes near the point C; but no accident ever occurred more serious than the starting of a slight weeping of joints. Rhythmic vibrations, such as those referred to by Mr. Rutter and presumably due to water-hammer, had been observed only during the testing of governors and of valves. The closing of a valve would send a pressure-wave up the line of pipe, but it was partly dissipated in the penstock-chamber. In the case of governor-adjusting, the subsequent pulsations of pressure following the first one at regular intervals, travelled through the pipes, and apparently returned again, as indicated by occasional "peaks" of pressure. These were considered to be due to the meeting of a fresh outgoing wave with a returning one. The time taken for pressure-waves to travel to the top of the line and back was about 7 seconds, which would correspond with a velocity of about 1,800 feet per second. On one occasion, in connection with certain tests, a main valve-door was lifted about $\frac{1}{4}$ inch and closed again, this operation being repeated eight or ten times in comparatively rapid succession. This set up a pressure much greater than ever happened with a single stroke, and started a weeping at almost every joint in its own pipe-line. In his opinion this must have been occasioned by return waves meeting fresh outgoing ones. With all the plant adjusted and started, and the speed-control devices fitted on the main valves, he thought it unlikely that pressure-vibrations of any appreciable intensity would arise. An excess of 10 or 12 per cent. had been usually adopted as a proper safe limit within which to work, but this had been exceeded sometimes in the earliest operations. Mr. Rutter asked whether the automatic air-valves had fulfilled their functions. He confidently believed they were doing so; he was of opinion that, if they had in

Mr. Roberts any way failed in their performance, the fact would have been unmistakably indicated in the valves themselves or in the pipe-joints in their neighbourhood. As to the coating of the pipes, it had not been considered necessary to attempt to re-coat them internally. Three coats were applied at the works where the pipes were made, and were found to be quite sound on delivery and erection, except for trifling abrasions at the ends, which were carefully made good before the pipes were put together and jointed up. At Kinlochleven the velocity in the pipes was about 6 to 7 feet per second, but the water was almost entirely free from sand and grit. There was also the important consideration that the pipes were very easily accessible internally for inspection, coating, etc. From notes of conversations he had the impression that the late Mr. Meik had roughly put the evaporation at a fixed figure equal to 14 inches of rainfall, and that the flood-losses were originally allowed for at about 10 per cent. of the annual rainfall. But the figures obtained by Mr. Morrison seemed to indicate that, on the Moor of Rannoch at all events, evaporation did not amount to more than about 6 inches of rainfall. Mr. Morrison believed that temperatures in the interior of a dam remained high for considerable periods. Mr. Roberts's recent observations indicated that temperatures of 80° to 90° F., occasioned by the setting of concrete in large masses,¹ did not cool down to atmospheric temperature in less than about 6 months, and the period was much increased by the constant addition of new layers of concrete. Regarding the side-stream regulating-valves, the intake-chambers were designed with the intention of employing large-sized Appold siphons, but on looking into the matter the balanced-valve type of offset in use on the Crinan Canal was brought to notice and ultimately adopted. In reply to Mr. Binnie, the question of preventing silt and detritus from entering the conduit and pipes was of the first importance. Very careful provision had been made at Loch Leven, especially in the case of the side-stream intakes, to trap all sand and stones brought down. Fig. 6a, Plate 1, showed a section through the offset chamber, and the silt-trapping arrangements described on pp. 49 and 50 lay in an adjoining chamber communicating with the conduit; there was also further provision at each intake dam. In working these had been found quite efficient; they required, of course, occasional scouring out, but this was attended to periodically. Replying to Mr. Poulton, when the foundation rock had been sufficiently excavated the surface was very thoroughly washed and

¹ Experiments were made in the heart of a wall 16 feet thick.—A. H. R.

covered with a layer of 2-to-1 cement mortar 2 inches thick, upon Mr. Roberts. which the concrete was deposited. The section shown in Figs. 3a was theoretical; in actual fact the foundation was sloped towards the water very generally, following natural ridges which occurred in the beds; the surface was also thoroughly serrated throughout. The contraction-cracks did not in any way follow the lines of construction; they occurred vertically from top to bottom. The leakage took place entirely through the cracks themselves, which were of uniform size on both sides of the dam. It was clear that neither the presence of displacers nor the layers of the work in any way accounted for the cracks or leakage. The water used for the village was analysed, and thorough long-period tests were made by Mr. J. Falconer King, Analyst to the City of Edinburgh, to ascertain its effect upon lead. It was found to be of an unusually high quality and to have practically no effect upon lead. It might be explained that the gathering-ground was at a high level, and the surface consisted principally of clean rock and glacial gravel, so that the water was very free from peat. In the case of the pipe-line no magnetic disturbance had been observed. With reference to Mr. Frame Thomson's remarks, he suggested that elasticity in the utilization of labour might be obtained under a policy of management which aimed at running a few of the spare units for the longest possible periods, thereby obviating the starting of more units for shorter periods. The permanent workmen, the number of whom would be based upon the average requirements, would be trained to a high degree of efficiency themselves and in the supervision of less skilled men. With the starting-up of a spare unit of power, additional unskilled labour would be engaged and spread over the whole factory, so that the proportion of less skilled labour would be low. The best results would probably be obtained in a metal-producing industry. In certain works in England the problem of occasional extra labour has been successfully met in an agricultural district. The occasional labourer was capable of serving with tolerable success in either the field or the factory. Regarding the question of an empirical formula for correlating the depth of water with the storage-capacity at that depth, the figures suggested by Mr. Thomson held good in the case of Kinlochleven for the 36-feet and 75-feet depths as far as the reservoir-capacity was known, but the Author was not in possession of sufficient information to test them with any degree of certainty or to check them for the intermediate depths. It appeared to him that a fixed power of the depth could only apply to a reservoir with straight sides. In the case of the Loch Leven reservoir, whose banks were much "dished," the power would be higher, but variable.

Mr. Sonnen-
schein.

Mr. SONNENSCHIEIN, in replying, wished first to express his thanks to Mr. Morrison, Messrs. Escher, Wyss and Company, and Messrs. Dick, Kerr and Company, for their assistance, which had enabled him to give the results of the tests on the plant at Kinlochleven in a complete form. Referring to Mr. Poulnden's remarks on the subject of the measuring-staff, which had been placed approximately in the position shown in Fig. 1, the baffle on the up-stream side of the staff had greatly reduced the error that might have occurred if the baffle had been omitted; and it was not thought that the inaccuracy introduced owing to the wave striking the baffle gave rise to incorrect results of any practical magnitude. The readings from which the weir-curve had been drawn were based on measurements made after time had been given for the wave to die down very considerably, and the weir-curve also agreed very closely with what might have been estimated from standard formulas. As, however, no experiments could be found dealing with weirs under similar conditions, the measurements described had been carried out. It was not quite clear on what Mr. Poulnden based his statement that the cost of overhead distribution was more expensive with aluminium than with copper. The conductivity of aluminium was slightly more than 60 per cent. of that of copper, volume for volume; but, as aluminium weighed only about one-third of copper, its conductivity was approximately double that of copper on a weight basis. Its adoption, therefore, at present prices, showed a very considerable saving in cost. It might be useful to compare Mr. Morrison's interesting figures for the cost of a unit at the switchboard at Kinlochleven with those of other British power-installations. The same figures for capital expenditure and running-cost had been taken in the following estimates, but the allowances for depreciation were those which it was expected the Local Government Board would have permitted. It was assumed that 5 per cent. was paid for interest on the whole of the capital; that sums of money were put aside annually, as a sinking-fund at 3 per cent. compound interest, which would pay off the whole of the capital expenditure in 30 years for the dam, 25 years for the conduit, 20 years for the pipe-line and buildings, and 15 years for the plant in the power-house, etc. On this basis the total cost of a unit as the plant was erected (including interest and depreciation, rent, rates and taxes, wages and management, repairs, oil, and waste) was 0·08*d.* at the switchboard. Had the station been built for a bulk supply, the power-factor might have been in the neighbourhood of 30 per cent.; and taking 20 per cent. of spare plant, the capital

charges and all works-costs would have been considerably increased, bringing the total cost of a unit at the switchboard up to 0·16*d.* instead of 0·08*d.* This figure of 0·16*d.* per unit was, however, less than the cost of coal alone at Glasgow, as published in the reports of the electric light and power undertaking there for the year ending May, 1911.

Correspondence.

Mr. M. B. DUFF congratulated The Institution upon receiving, Mr. Duff. and the Authors upon presenting, Papers giving an account of works so novel, large, and interesting. The physical conditions appeared to have been particularly favourable, a factor conducing very materially to success in a work of this magnitude, especially when combined with engineering and constructional skill such as had been exemplified. To obtain a foundation for a dam more than 1,000 yards in length and with 75 feet head of water, at a depth not exceeding 15 feet, was not always the fortune of an engineer. The basin of the reservoir, too, as pointed out, was of an exceptionally favourable character: for waterworks purposes, a reservoir-site, situated within reasonable distance of the area to be supplied, and affording only 3 per cent. of the Kinlochleven storage for a similar height of dam would be considered quite favourable. Suitability of site for a storage-reservoir, one of the features Mr. Roberts claimed as necessary for a successful power-installation, had undoubtedly been secured at Kinlochleven. He agreed generally with Mr. Roberts's views as to the difference between the storage of water for domestic supply and for power purposes, but considered that the statement as to the storage being usually reckoned at about one-third of the annual draught was much too vague. Even in the case of Kinlochleven, with its high rainfall, storage probably exceeded this. If 80 per cent. of an average rainfall of 70 inches were taken, and a reasonable allowance were made for loss by evaporation, the yield from the drainage-area of 55 square miles was about 90 million gallons per day; so that the contents of the reservoir as constructed, namely, 20,000 million gallons, represented 222 days' storage. Mr. Roberts stated that a community receiving a domestic supply would consume a fairly constant quantity at all seasons and in all years. Unfortunately for those responsible for domestic supplies, the warmer and drier the weather, the greater the demand for water. A consideration of some of the