Discussion.

The President. The PRESIDENT moved a vote of thanks to the Author for his Paper.

The Author. The AUTHOR exhibited a number of lantern-slides illustrating the works.

Professor
Dawkins.

Professor W. BOYD DAWKINS observed that he had had to do with the Derwent Valley enterprise at its inception; and had watched with great pleasure its growth into one of the largest engineering works in the country. He wished to say a few words on the geological side of the subject. Looking at Fig. 3, Plate 3, showing the Howden dam, it would be observed that the very interesting fold in the strata, which had been shown also in the photographs exhibited by the Author, was nearly at the bottom of the valley; and the question arose how had it been formed. For the last 30 years or so it had been his business to find out the conditions under which dams could be made in the deep valleys of the Pennine Chain, and he had found that, as a rule where the bottom of the valley was composed of shales, more or less interbedded with sandstones, but especially where there was a preponderance of shales, folds were present; and the question had been often put to him what would happen in the cutting of trenches for the puddle or concrete. The folds near the surface let the water through freely; were they shallow, or were they continued downwards to great depths? Now the experience brought forward in this Paper was the experience which he had invariably found in dealing with these matters—namely, that the disturbance was at a maximum near the surface, and diminished gradually, going downwards from the surface until a strong bed of material was reached—sometimes a strong shale, at other times a bed of sandstone—and then it ceased. That, of course, pointed to the conclusion that the fold was the result of some operation working from the surface downwards, and was not the result of folds or faultings, or earth movements coming from the interior upwards—in other words, that it was a localized movement due to some external cause. Now the invariable result of the working of coal, where there was a shale roof or shale sides and the working was deep, was that the

removal of the material in the working caused the floor to rise, the sides to crush in, and the roof to crush down, due to the intense lateral pressure of the rock on either side. These phenomena were commonly known under the name of "creep." He therefore ranked all these superficial folds with the creep in mines, and he applied the terms creep fold and creep fault to them. But how was it that the pressure was localized on those points, seeing that the general contours of the valley, as shown by Figs. 2 and 3, Plate 3, were not of a kind that would allow of the pressure of the rocks being brought to bear on one centre only in each case? The Author, in dealing with that point, had assumed that the contours of the valleys were those which they had always presented in past times; but Professor Boyd Dawkins had clear proof that the existing valleys had been moulded and worn by the passage of glaciers. They were ordinary glaciated valleys in which the original contours had been swept away by ice. The proof that the valleys were all older than glacial times was to be found, he thought, in the history of the caverns which he had explored in the neighbourhood of Buxton and elsewhere.¹ The present valley system of the Pennine Chain had been formed long before the glacial period in the Pliocene, if not before. The beds of thick sandstone and thick shales, of which they consisted, were elsewhere invariably, wherever the glaciers had not been at work to grind them, cut by the natural sub-aerial agents—rivers for the most part—into deep ravines, gorges or canyons, as might be seen to perfection in New South Wales and more especially in the Blue Mountains round Mount Victoria. They were narrow gorges, with very precipitous sides, and as much in some cases as 2,000 feet deep. He took it, then, that in pre-glacial times, long before there were glaciers in the Pennine Chain, there were ravines where these wide valleys were now. Those ravines had been swept away, and the debris would be found to-day in the Midlands and elsewhere, in the boulder clays, gravels and sands, far away from the Pennine Chain. These folds were therefore of great practical interest to geologists, who were, of course, entitled to exercise their scientific imagination in studying them. The geologist looked upon each of these folds as marking the position of the bottom of one of these deep gorges which had been swept away; hence their interest from the geological point of view.

¹ Quarterly Journal of the Geological Society, vol. lix (1903), pp. 126-8.

Professor Dawkins. With regard to the engineering side of the matter, he need not point out the importance of being able to distinguish between the deep normal folds and faults and the superficial, which he had ventured to call creep folds and creep faults.

Mr. Watson. Mr. JAMES WATSON congratulated the Author, and also Mr. Winsor, on the important and interesting information set out in such detail, and on the clearness of the accompanying diagrams of the large dams and aqueducts, which, to those engaged on similar work, especially the younger members of The Institution, would be very useful and instructive. The Author referred to the interesting discussions that arose on the subject of earth embankments versus masonry dams, the first year that the Derwent Valley Bill was before Parliament. The late Sir Benjamin Baker very strongly advocated masonry for the Derwent Valley dams. The late Mr. Charles Hawksley, on the other hand, advocated earthwork dams; and those two gentlemen were in the first degree qualified by experience and otherwise to give sound advice on each class of reservoir. To him, engaged as he was at that time on a large masonry dam, those discussions had been both useful and instructive. With regard to irregular building of masonry dams, and to the method adopted to pass the flow of the river in flood-time, this break in the length of the dam, necessitating its being built far from level, and leaving a large mass of masonry 90 or 100 feet high, having a rough sloping face about $1\frac{1}{2}$ vertically to 1 horizontally, did not commend itself to him, notwithstanding the fact that the dam was sound. He had finished about 2 years ago at Angram probably the highest masonry dam in Great Britain: the height from the river to the crest of the overflow was 130 feet, and to the roadway, over 145 feet; the foundation level was $66\frac{1}{2}$ feet below the river-bed, or 196 feet below the crest; and horizontally and transversely he had insisted upon a minimum of 6 feet and a maximum of 12 feet with flat slopes. The up-stream face of the dam was heavy pitched ashlar, grooved on all the beds, bedded in 1-to-1 cement mortar, and with joints run with neat cement. The down-stream side was formed of large stretchers and headers, one in each square yard. The heart of the dam was formed of displacers up to 10 tons in weight, bedded in 2 inches of cement mortar, all beds being roughly dressed and the stones laid on a level bed, breaking bond in every direction. Between the up-stream ashlar face and the nearest "plums" there was a thickness of 4 feet of 5-to-1 concrete. Several hundred of these "plums" were quite 10 tons in weight. All of them were dressed on the underbed, and broke bond by keying into each other almost everywhere across the

ANGRAM RESERVOIR.

Capacity 1,100 million gallons.

Description of Work.	Quantity.	Amount.		Description of Work.	Quantity.	Amount.		Price per Million Gallons.
		£	s. d.			£	s. d.	
Excavation for dam . . .	Cub. Yds. 92,800	24,999	8 6	Excavation for dam . . .	Cub. Yds. 159,692	45,087	3 6	41.0
Concrete in foundations . .	6,462	7,584	0 0	Concrete in foundations . .	7,976	8,568	2 6	7.8
" tongue . . .	6,157	5,135	2 0	" tongue . . .	33,255	33,255	0 0	30.0
" and displacers in wall	51,237	40,989	12 0	" and displacers in wall	203,102	182,791	16 0	168.0
Sundry work to dam, including facework, trial-pits, etc.	..	2,903	19 11	Sundry work to dam, including facework, crest stones, bank- ing, etc.	..	13,245	7 5	12.0
Culverts	..	1,840	15 6	Culverts	..	2,000	12 5	1.8
Wath quarry bridge . . .	..	2,768	16 6	By-pass channels	..	43,174	6 2	39.0
Bridge over dam, roads, etc.	..	18,162	17 10	Bridge over dam and roads	..	17,184	14 9	15.6
Gauge-basin	..	8,052	18 10	Gauge-basin	..	8,783	5 9	8.0
River-channel	..	2,552	7 2	River-channel	..	5,105	12 0	4.6
Forebays	..	671	9 0	Hydraulic pipe-line	..	252	17 9	0.23
Earthwork embankment	..	18,253	8 1	Valve-tower	..	5,795	11 11	5.3
River diversion	..	2,028	17 7	General items	..	4,915	15 8	4.5
Valve-towers	..	1,804	16 5					
Total cost	..	140,084	18 7	Total cost	..	372,760	2 6	339.0

Cubic Yards.
1 Concrete 118,745 = 58.4 per cent.
Displacers 84,357 = 41.6 "

0

or, approximately, 3s. concrete; 2s. displacers.

Summary.

	£	s. d.
Angram	372,760	2 6
Gouthwaite	140,084	18 7
	£512,845	1 1
	£190	

Mr. Watson.

Mr. Watson centre of the dam. The spaces between them were filled with small displacers set in 5-to-1 concrete. In the 4-foot wall of 5-to-1 concrete behind the ashlar face the largest stone allowed had to pass a mesh of $1\frac{1}{2}$ inch. That plan had given, he thought, very considerable security and ensured absolute watertightness. Instead of making a break in the masonry, he had preferred to divert the river. One of the dams, called the Gouthwaite dam, held up 1,600 million gallons of water, from a drainage-area of 32,000 acres. The dam had been constructed without risking difficulty due to having large differences in the height of the work at any time during its construction. The other reservoir, the Angram, was supplied by two rivers, the Stone Beck and the Nidd. The Angram dam was 14 miles above Pateley Bridge, and was built on a spur of the Pennine range. It had often occurred to him that the practice of comparing the cost of reservoir-works per million gallons of storage-capacity of the reservoirs was fallacious. In the case of the Gouthwaite dam the river had a rise of 40 feet in 2 miles. In the case of the Angram dam the rivers had a rise of 125 feet in $1\frac{1}{4}$ mile. The Table on p. 193 would enable the cost of these works to be compared with the Author's figures. To illustrate the fallacy to which he had referred, the Gouthwaite dam had cost £87·55 per million gallons, the Angram dam £339 per million gallons. The cost of waterworks was frequently put forward as being so much per million gallons stored, but he thought the figures he submitted showed that too much weight should not be attached to comparisons made on that basis.

Dr. Lapworth Dr. H. LAPWORTH remarked that, as a former resident engineer on the Derwent Valley works, and as one who from time to time had advised on geological matters in connection with them, he thought there were several points of detail that were of interest. He had put on the blackboard a rough sketch showing the manner in which the cut-and-cover section had ultimately been built up. At the bottom blocks of concrete or rough stone were placed, two or three under each set of ribs, to support them; the concrete was then brought up to springing-level, and a short length of wall was built above that level. That had the advantage of preventing the dirt at the side of the trench from falling on to the joint at springing-level, and had tended to prevent leakage when the next concrete was laid. The great trouble in building cut-and-cover work of almost any section was in the cleaning of the horizontal joints against the sides of the trench. The method he had described almost obviated that difficulty; but even there difficulty had been experienced in clearing out the narrow space between the brick arch and the sides of the concrete. It was

impossible to do this perfectly unless jets of high-pressure water Dr. Lapworth. were employed, so that eventually the precaution was taken of putting in 8 inches of mortar at springing-level between the brick arch and the side of the concrete wall (*Fig. 22*). When the work was designed and the first contract let, several contractors said that it would be very difficult to trim the bottom of the trench to a semi-circular section. However, although some of the contractors estimated for taking out the trench to a flat bottom, they had no difficulty, as a rule, in working to that section except in thick-bedded rocks. The sand filters consisted of separate filters, each 200 feet in length. When some of these filters were built, they

Fig. 22.

METHOD OF BUILDING CUT-AND-COVER SECTION.

were left for a time unfilled with either sand or water, or both. A very severe winter ensued and cracks developed in the longer walls. It was found that a simple method of remedying that was by caulking the cracks with lead-wool, and he believed that method had proved entirely satisfactory. Another trouble that arose in connection with the filters was the occurrence of cracks due to the nature of the rubble stone used in the concrete. It took a long time to find out the cause, and, as the Author said, the remedy was found in washing the broken stone. The cause of the trouble was the presence of kaolinite, or decomposed felspar, in the rock itself, which, for some reason, either physical or chemical, caused great shrinkage in the setting of concrete. Experimental blocks,

Dr. Lapworth, a cubic yard in volume, shrank vertically several inches in depth, and left the moulds with $\frac{1}{4}$ inch space all round. At that time nothing was known about this peculiarity, but of late he had found out that it was characteristic of many rocks containing decomposed felspar. He had found in Cornwall and Devon and in the north of Scotland that certain granites containing decomposed felspar (and the same applied to some Leicestershire syenites also) had to be washed before they were used for making concrete or artificial stone. He had also found in Yorkshire a similar grit-stone which had to be washed. The washing, however, caused a fresh difficulty, it being found that the mixture was so harsh and stiff that in the first mass of concrete there was considerable honeycombing, and it was necessary to import a large quantity of sand in order to make the stuff workable. At one time he had been disinclined to believe that the folds to which Professor Boyd Dawkins had referred were due to the weight of the hills on either side, but he now thought that Professor Dawkins was right, and that the evidence in support of that view was strong. Looking at Fig. 2, Plate 3, it would be noticed that on each side of the valley the joints and faults, instead of being parallel to those on the other side of the valley, were each inclined towards the centre of the valley. Now that showed that those faults and cracks were connected with the valley itself and were therefore the effects of local and not regional or tectonic movements.¹ The Yoredale shales, he had found, frequently gave trouble in foundations. Where there were thick beds of rock, fairly good foundations could be obtained, but where the mass as a whole was shales there were almost invariably landslips or movements of that sort, which opened the rock, and necessitated deep foundations. The Author mentioned the escape of water which had occurred since the reservoir was filled. Dr. Lapworth agreed with him that it was extremely likely that the formation of the wing trenches on each side of the reservoir had increased the amount of escaping water; that was to say, if a barrier were introduced between the natural flow of ground-water and the reservoir, the water sought the easiest way of escape, and found its way to the surface at the nearest outlet. It might be contended that grouting could have been adopted successfully instead of the wing trenches; but he thought the answer to that criticism was that making wing trenches was the utmost that could

¹ Mr. P. M. Crosthwaite, M. Inst. C.E., has recently shown (Minutes of Proceedings Inst. C.E., vol. cciii, p. 160) that in plastic materials such as clay there is a critical depth beyond which they must yield under their own weight, and the same law probably applies to plastic shales.—H. L.

be done, and that although grouting might have been cheaper, the leakage which took place showed that even wing trenches did not stop it entirely, and it was exceedingly doubtful whether a satisfactory job could have been made by grouting, especially in view of the extensive nature of the wide fissures in the rocks. He would like to add that whatever portion of the success of the works was due to the work of the staff, was very largely the result of the Author's own enthusiasm, his scientific method of investigating each problem on its merits, with an unbiased mind, and his willingness at all times to receive any suggestion from the staff and consider it thoroughly.

Mr. F. J. WARING wished to ask a few questions in regard to this very interesting Paper. He supposed that "by administration," on p. 157, meant what was sometimes called "departmentally," that was to say, without the intervention of a large contractor, who accepted certain responsibilities. He presumed, however, that the work had not been carried out by day labour, but by petty contract or piece-work whenever practicable. He would like to know whether that was the case. Of course, under that system many contingencies, which under a large contract would devolve upon the contractor, were borne by the Board or Company. The Author described the concrete as varying from 5-to-1 to 6-to-1 in different parts of the work: this description appeared to be somewhat indefinite, and Mr. Waring would like to ask how much of the aggregate was sand and how much was stone, and to what gauge the stone was broken. It appeared to him that a perfect concrete should be one in which there were no voids; and, from certain experiments lately carried out at his suggestion, it would seem that that condition was very fairly met when the cement filled the voids in the sand, and the cement and sand, together with the water taken up by the cement in setting, filled the voids in the stone. The experiments in question had shown that with gneiss rock broken to a gauge ranging from 1 inch to 2 inches, the average being about $1\frac{1}{2}$ inch, that condition would be met with the sand used in those experiments by concrete mixed in the proportions of 4 stone, 2 sand, 1 cement; or 6 stone, 3 sand, 1 cement, the proportion of the sand generally being about one-half that of the stone. The Author described the hearting of the dams as masonry; but it seemed to him that it would be more properly described as cement concrete in which plums or displacers were used to an unusually large extent. According to the statement at the foot of p. 165 the displacers formed about 44 per cent. of the whole work, 56 per cent. being concrete. Now in his own experience with coursed masonry

Mr. Waring. of a fair quality the mortar would only form one-fifth to one-seventh of the whole bulk, and in the case of the dams described in the Paper, with the very large stones used, had the dam been built in masonry he thought the proportion of mortar would have been somewhat less than one-fifth to one-seventh of the bulk.

Mr. Binnie. Mr. W. J. E. BINNIE considered that the Author, who frankly described the difficulties encountered and successfully overcome, had contributed a Paper which would be of the greatest service to engineers. The subject was of particular interest to him, and he had had the opportunity of seeing some of the works during construction. In referring to the probability of water outflanking the Derwent dam, owing to the disturbed character of the rock, the Author did not state whether any water had, in fact, outflanked the Derwent dam. The experience gained at the Carno reservoir of the Ebbw Vale Urban District Council illustrated the rapidity with which leakage through rock fissures might decrease. The puddle trench was excavated into shale and grit at the base of the Coal Measures below the "farewell" rock, and a fissured bed of grit about 8 feet in thickness cropped out at the site of the bank, the top of the bed being 32 feet below top water-level. A heading was driven for a distance of 200 feet into the hill along this grit bed and was filled with concrete, but it was certain that some water would pass through the bed, outflanking the heading, even if that heading were extended for a long distance into the hill. The dip of the rock would have necessitated a somewhat costly wing trench to prevent any possibility of the water impounded obtaining access to the fissured rock. It was thought probable that any water which did pass through this rock would appear again in the valley at such a short distance below the bank, and at such a level, that it could readily be brought back into the compensation-basin. In that case nothing would be gained by carrying out further works unless the leakage exceeded the quantity of compensation-water. It was therefore decided not to start on the wing trench until the reservoir had been filled and tested. The scour-valve was closed, and by November, 1911, the reservoir having filled, a copious spring had appeared from the grit a short distance below the bank, and the flow of several springs was augmented. These springs were collected and brought back to the compensation-basin, where they were measured, with the following result. In November, 1911, the flow amounted to 173,000 gallons per diem with the reservoir full, after a week's dry weather, the compensation-water being 205,000 gallons per diem. In order

to compare the flows at different periods it was necessary that these two conditions should hold good, owing to the fact that a certain quantity of water, which increased rapidly with the rainfall, made its appearance from the grit below the reservoir bank before the filling of the reservoir. By September, 1912, the flow had decreased to about 81,000 gallons per diem, or rather less than half, and by May, 1913, it had fallen to 48,000 gallons per diem, or about 28 per cent. of the original flow, since which date no appreciable decrease had taken place. It was probable, therefore, that the original leakage from the reservoir had now almost entirely ceased, through the fissures becoming silted up, as the water in the reservoir contained a good deal of suspended matter, owing to the banks being mostly of shale and boulder clay, and owing to the presence of peat on the drainage-area. It was difficult to see how contraction cracks could be avoided unless special measures were taken. The Alwen dam, which had just been completed for the Birkenhead Corporation, showed two cracks which ran right through the masonry. It was possible to find one of them easily enough, but without the assistance of the Resident Engineer the other was hard to discover, and now that the reservoir had been filled and the face had been discoloured by the overflow of peat-stained water they defied detection. The Resident Engineer had gauged the water which found its way through those cracks, but as it had to be measured by drops, they were of no consequence whatever. The dam was arched in plan and therefore any radial cracks tended to close under water-pressure, which probably accounted for the small leakage. Recently several masonry dams had been built with joints made purposely to allow for contraction, but it was to be doubted whether such joints were required. Although some water might escape through cracks at first, it was generally found that they closed in time, and they had no effect on the stability of the structure if they were more or less vertical and normal to the face. If the dam was constructed of plain concrete without block facework, they were, of course, unsightly, but when the dam was faced it was very difficult to detect them. The temperature observations set out on pp. 166 to 170 were of great interest. It would be instructive to know whether any of the cracks recorded at the Howden dam bore any relation to the line of junction between the old and new work in the irregular building of the dam. However desirable it might be to prevent one portion of the structure from rising above the level of adjacent portions, it was generally found impracticable to carry out the work in horizontal layers, and it was therefore of great interest to know that this procedure could be

Mr. Binnie.

Mr. Binnie. departed from to such an extent without danger of subsequent weakening at the point of juncture between the old and the new work. It was very interesting, too, to find that the roughing-filters had been so successful in reducing the work of cleaning the sand filters. The water was, however, somewhat peat-stained, although bacterially harmless, and experience had shown that sand filtration would not remove the peat stain without the addition of coagulants. It must be acknowledged that a slight peat stain was quite immaterial, but it was apt to give rise to doubts as to the quality of the water in the minds of the ignorant and to lead to attacks in the local press. Perhaps, if the Author had had the advantage of the experience gained with so-called mechanical filters in recent years, he might have adopted a system where coagulants were used. Referring to the size of the main pipes, which were stated to have a capacity 25 per cent. in excess of the average delivery, the average demand was apparently 13 million gallons per diem, the pipes 45 inches in diameter, and the gradient 1 in 1,508. This would give a discharge, when clean, of about 19 million gallons per diem. Possibly the 25 per cent. allowance referred to was in addition to an allowance for incrustation. The pressure to which the pipes of the various thicknesses mentioned would be subjected was not stated, but they appeared to be thicker than the thickness laid down for pipes, 46 inches in diameter, in the British Standard specification issued in October, 1917. He had compared the thickness of pipes of various diameters subjected to different pressures, as tabled in that specification, with a similar table prepared by the late Dr. Deacon, and used by his firm, and had found that, if cast in accordance with the British Standard specification, the pipes would be 17 to 26 per cent. weaker.

Sir William
Ellis.

Sir WILLIAM ELLIS, G.B.E., remarked that, as a user of the Derwent Valley water, he would like to congratulate the Author on his work. The several visits he had paid to the works during construction had certainly formed some of his most interesting experiences as an engineer. He would only say a word or two on the domestic side of the matter, not feeling able to discuss its technical side. He thought a Paper of that kind was incomplete without some allusion to the men who carried out the work. To him, living in a neighbouring city where men did not always conduct themselves as they might, it had been wonderful that the moral effect of the presence of one policeman—certainly of enormous build, who would be remembered for many years in that district—and one small lock-up should have sufficed to keep that large population in order. He doubted if there had ever been, in a body of

men gathered together under such conditions, less crime, and he thought it right that that should be recorded in their favour. Again, a good deal had been said about the works of engineers leaving ugly marks on a district of that sort; but he was sure that as soon as Nature had reasserted herself here, and the trees which had been planted in all directions had become fully grown, the engineer would have actually improved on Nature. The work had been excellently carried out, and those who had seen the flow of water over one of those dams in a strong wind, and with snow-covered surroundings, would regard it as one of the most beautiful sights they had ever seen. The only other point to which he would like to allude was of some importance to The Institution. When the Derwent Valley scheme first came up, the City of Sheffield was debarred from participating, on the ground that the ruling of the Courts had always been that the water belonged to those to whom it would flow; and owing to a big watershed between the Derwent Valley and Sheffield, the water would not flow there. But it was felt to be very desirable that a large partner like Sheffield should come in, especially as there was water enough. The difficulty had been solved by boring a tunnel through the watershed, which enabled the water to comply with the ruling of the Court; the water did now run by gravity from the Derwent Valley, and so allowed Sheffield to participate. If he might make one criticism, he thought the Author had been a little unwilling to consider that the district was a pleasure-ground for thousands of people, and that whatever could have been done to assist them in the way of roads and footpaths would have been of great benefit. In the southern arm of the Howden reservoir, instead of making a very expensive road going right up the west end of the valley and turning round, the expense of a bridge would have been fully justified, and a bridge would have been a great boon to many. No doubt the Author had considered that matter, as also the construction of a road on the northern side—made at great expense, but still a private road—and had done what he could; but if more had been done it would have been very welcome to those who used the district in the way indicated.

Sir William
Ellis.

The AUTHOR, in answer to the question asked by Mr. Watson as to the irregular building of dams, and also to Mr. Binnie's question whether the temperature cracks coincided with the irregular building-lines, stated that the temperature cracks did not coincide with those irregular building-lines, and, in his opinion, had nothing whatever to do with them. The temperature cracks occurred always in winter; they began with a small fissure at the top of the dam, and

The Author.

The Author. with each successive wave of cold they gradually tore the dam, just as one might tear a sheet of paper. He had watched one such crack extend gradually from the top of the dam downwards to ground-level. That was the only one which went right through the dam. It had nothing to do with the irregular building, and as to that, he personally was absolutely convinced, as Sir Benjamin Baker had been also, that there was no danger from irregular building. The question had occasioned him much anxiety at the time; but he knew that Sir Benjamin Baker in building the Assuan dam had left out a V-shaped piece from the top to the bottom of the dam, simply for the purpose of running a railway through it. Sir Benjamin evidently had no fear of any trouble arising from it. The Author confessed that he was inclined to agree that Professor Boyd Dawkins's theory was more correct than his own suggestion as to the cause of the faults and folds in the strata. But he would like to say, with regard to those faults and folds running out as deeper and deeper excavations were made, that they had not come to the end of them; although excavation had gone to a great depth it had not come to the end of the broken strata, which continued, although in a minor degree. They had not reached a bed of rock from which the effects of the faults and folds were entirely absent. In reply to Mr. Waring's question, the work carried out under administration had been done mostly by day labour, but some excavation and stone cutting had been done by piece-work. The effect of the construction of the long wing walls at the east and west ends of the Derwent dam was quite as satisfactory as had been expected. There was no watertight ground in the valley sides into which the ends of these walls could be tied, and it had been entirely a question of judgment as to where they should end. There was no visible flow of water, but there was some increase in the quantity of water in the bed of the stream between the dam and the compensation-gauge. It did not amount to more than a very small percentage of the compensation-water which had to be discharged into the river, and of which it formed a part. He agreed with Mr. Binnie that the thicknesses of the pipes used were in excess of those given in the British Standard specification, and also that the latter were not sufficient for very large pipes. The thickness of the 45-inch pipes under a head of 50 feet was $1\frac{1}{8}$ inch, and increased $\frac{1}{8}$ inch for every additional 50 feet. The delivering capacity of the pipes was approximately 25 per cent. in excess of the average delivery, and was in addition to the allowance for incrustation. He was grateful to Sir William Ellis for his reference to the good general behaviour of the men living in Birchinlee village, the population of which was

for 12 years between 900 and 1,000. The Board had taken every care that the inhabitants should be well and comfortably housed, and the village, with its school for 125 children, recreation-room, canteen, fever- and accident-hospitals, and shops, might be said to have been a model one of its kind. The two resident engineers who had successively had charge of it — Mr. M. G. Weekes M. Inst. C.E., and Mr. W. F. H. Creber, M. Inst. C.E.—together with the Missioner, Mr. G. E. Sutton, deserved high credit for their painstaking efforts to afford healthy entertainment for the men, women and children, and for their untiring zeal in promoting their welfare. The result was entirely satisfactory, and Sir William was correct in saying there was less crime than there was usually in an ordinary village of the same size. The provision of a bridge over the west end arm of the Howden Reservoir had been fully considered. To shorten materially the road round this arm would have entailed a high and expensive viaduct, whilst to make a viaduct across the shallower part would have given no advantage equivalent to the expense. The houses in the district had all been pulled down, and, apart from the occasional visitors, there was hardly any traffic. After considering these points, it was decided that the reasonable course was to build the road round the reservoir. The other road referred to, which lay on the eastern side of the reservoir, had been constructed in accordance with the agreement made with the Duke of Norfolk when the original Bill was before Parliament. He thanked cordially those members who had spoken in such complimentary terms of the work. He also wished to take this opportunity of thanking Mr. W. A. Legg, M. Inst. C.E., for valuable assistance rendered in connection with the diagrams of temperature.

Correspondence.

Mr. BERTRAM BLOUNT observed that there was no doubt as to the value of the Paper, dealing as it did in detail with a question of the highest public importance; there were in addition certain questions concerning the structural materials which might be worth attention. On p. 160 it was stated that on the up-stream side the joints were caulked with neat cement slightly damped with water, and that the caulking was kept back a little from the pitch-line, so as to prevent damage by frost. It was very doubtful whether it would not be better to use a caulking of 1-to-1 cement and sand or,

The Author.